
PROJECT REFERENCE NO. X-0002F



SECTION FACING WEST

NOTES

- . PROVIDE A SINGLE FIXED LADDER LEADING TO THE ACCESS PLATFORM FOR BOTH DMS UNITS.
- 2. EQUIP THE LADDER WITH A SECURITY COVER (LADDER GUARD).
 START THE FIRST LADDER RUNG NO MORE THAN 18 INCHES ABOVE A CONCRETE LANDING PAD. DESIGN RUNGS ON 12 INCH CENTER-TO-CENTER TYPICAL SPACING.
- 3. INSTALL A CONCRETE LANDING PAD MEASURING A MINIMUM 4 INCHES DEEP, 24 INCHES WIDE, AND 36 INCHES LONG DIRECTLY BENEATH THE LADDER.
- 4. USE ACTUAL DIMENSIONS AND WEIGHT OF THE DMS TO COMPLETE THE DESIGN OF THE DMS STRUCTURE.
- 5. FIELD VERIFY ALL FOOTING ELEVATIONS AND GROUND SLOPES AT THE FOOTING USING THE LATEST NCDOT STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES.
- 6. ENSURE THAT THE TOP OF THE FOOTING EXTENDS AT LEAST 6 INCHES AND NOT MORE THAN 24 INCHES ABOVE THE HIGHEST POINT OF THE GROUND SURFACE AT THE FOOTING.
- 7. DESIGN AND CONSTRUCT THE PEDESTAL STRUCTURE AND DMS ENCLOSURE TO WITHSTAND WIND VELOCITIES OF 130 MPH.
- 8. VERIFY ALL UNDERGROUND UTILITY LOCATIONS BEFORE BEGINNING ANY UNDERGROUND WORK. DO NOT DAMAGE ANY EXISTING UTILITIES OR NCDOT CABLES DURING CONSTRUCTION.



NC-295 FAYETTEVILLE OUTER LOOP ITS DMS-6 & DMS-6A PROFILE

CUMBERLAND COUNTY JUNE 2016 REVIEWED BY:

DIVISION 06 PLAN DATE: PREPARED BY: J. CROSS REVIEWED BY: K. SMITH REVISIONS

030472 6/30/2016 CADD Filename:

SEAL