COMPUTED BY: DG DATE: 5-4-2016
CHECKED BY: TG DATE: 5-6-2016

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PLANS PREPARED BY :
PARSONS
RALEIGH, NORTH CAROLINA, (919) 854-1345
NC LICENSE NO. F-0246
FOR NORTH CAROLINA DEPT. OF TRANSPORTATION

PROJECT REFERENCE NO.	SHEET NO.
U-2524D	3B-2
R/W SHEET NO.	

REMOVAL OF EXISTING ASPHALT PAVEMENT

LINE	STATION	STATION	LOCATION	LENGTH OR AREA	WIDTH	SQUARE YARDS
-Y6-	21+32	24+49	RT	9384.00		1042.67
-PED-	10+03	12+02	RT	7348.00		816.44
-PED-	15+53	18+55	RT	3323.00		369.22
-L-	454+05	454+98	LT	3869.00		429.89
-Y7A-	10+33	10+69	RT	1169.00		129.89
-Y7A-	10+96	11+14	RT	70.00		7.78
-Y7A-	11+50	11+83	RT	22.00		2.44
-Y7A-	12+62	12+81	RT	256.00		28.44
-Y6A_DET-	10+15	14+00	LT/RT	8706.00		967.33
					TOTAL	3,794.11
					SAY	3,800

WOVEN WIRE FENCE SUMMARY

STATION TO STATION	LT. OR RT.	A FABRIC L.F.	B END BRACE	C CORNER BRACE	D LINE BRACE	E 4" POSTS	F 5" POSTS
422+03.28 -L- TO 438+37.37 -L-	LT	1,689.00	2	3	7	102	34
5+73.18 RPAY8 TO 3+95.57 RPAY8	RT.	186.00	2	2		8	10
3+74.23 RPAY8 TO 525+21.66 -L-	RT/LT	1,969.00	2	1	8	124	31
434+06.08 -L- TO 437+00 -L-	RT.	299.00	2	1		18	7
4+89.23 RPDY8 TO 1+92.07 RPDY8	LT	308.00	2	2	1	15	13
519+74.01-L- TO 525+21.66 -L-	RT.	784.00	2	1	3	47	16
TOTAL		5,235.00				314	111
SAY		5,240				314	111

SUMMARY OF EXPRESSWAY GUTTER

LINE	SIDE	STATION	STATION	LENGTH
-L-	LT	442+38.00	446+83.00	445
-L-	LT	448+18.00	451+69.00	351
-L-	RT	455+00.00	456+45.00	145
-RPDY4-	LT	1+58.00	5+70.00	412
			TOTAL	1,353
			SAY	1,360

48" CHAIN LINK FENCE SUMMARY

STATION TO STATION	LT. OR RT.	A FABRIC L.F.	B END BRACE	C CORNER BRACE	D LINE BRACE	E LINE POSTS	F TERMINAL POSTS
438+37.37 -L- TO 443+59.45 -L-	LT	532.00	2	1	1	44.33	4
445+70.17 -L- TO 26+03.59 -Y6-	LT/LT	273.00	2	3	2	23.25	7
26+52.69 -Y6- TO 28+56.22 -Y6-	LT	222.50	2	1	1	18.54	4
26+53.04 -Y6- TO 28+63.26 -Y6-	RT.	214.00	2		2		
27+54.62 -Y6- TO 12+33.61-PED-	RT./RT	283.00	2	1	1	23.58	4
10+50.00 -PED- TO 12+76.20 -PED-	RT.	221.00	2		1	18.25	3
10+50.00 -PED- TO 12+79.48 -PED-	LT	235.00	2		1	19.42	3
452+72.28 -L- TO 478+36.33 -L-	LT	2688.50	2	6	5	225.54	13
478+75.26 -L- TO 0+75.11-SPBY8-	LT	1454.50	2	3	5	122.21	10
1+04.14 -SPBY8- TO 10+00.00 -Y8-	LT/RT	706.00	2	2	2	59.17	6
10+00.00 -Y8- TO 12+72.00 -Y8-	LT	272.00	2			22.33	2
13+32.00 -Y8- TO 6+43.38 -RPAY8-	LT/RT	1005.00	2	2	4	84.42	8
436+99.22 -L- TO 19+69.14 -Y6-	RT/LT	965.00	2	3	1	80.75	6
444+11.13 -L- TO 446+06.44 -L-	RT	205.00	2	1		16.92	3
11+40.00 -Y6A- TO 446+78.28 -L-	LT/RT	504.00	2	2		42.00	4
447+94.12 -L- TO 14+65.43 -PED-	RT/RT	506.00	2	1	2	42.33	5
14+46.29 -PED- TO 18+35.00 -PED-	RT	389.00	2		1	32.25	3
14+49.39 -PED- TO 18+00.00 -PED-	LT	351.00	2		1	29.08	3
452+76.88 -L- TO 471+00.00 -L-	RT	1879.00	2	5	3	157.58	10
1+17.97 -SPCY8- TO 1+70.14 -SPCY8-	RT	63.00	2	1		5.08	3
2+04.57 -SPCY8- TO 23+80.05 -Y8-	RT/RT	335.00	2	3	1	28.25	6
24+68.09 -Y8- TO 27+00.00 -Y8-	LT	228.00	2		3	19.17	5
23+10.73 -Y8- TO 24+00.00 -Y8	LT	95.00	2	1		7.75	3
24+00.00 -Y8- TO 5+20.35 -RPDY8-	LT	1009.00	2	2	4		
491+00 -LREV- TO 493+95 -LREV-	LT	300.00	2			24.67	2
491+00 -LREV- TO 493+95 -LREV-	RT	291.00	2			23.92	2
496+35 -LREV- TO 501+00.00 -LREV-	LT	474.00	2		1	39.33	3
496+35 -LREV- TO 498+00.00 -LREV-	RT	162.00	2			13.17	2
TOTAL		15862.50				1223.29	124
SAY		15863.00				1224.00	124.00

GATES

-L-	446+93	LT	48' High, 15' wide, 15' Opening	2 gate posts

TEMPORARY 48" CHAIN LINK FENCE SUMMARY

STATION TO STATION	LT. OR RT.	A FABRIC L.F.	B END BRACE	C CORNER BRACE	D LINE BRACE	E LINE POSTS	F TERMINAL POSTS
TRAFFIC CONTROL							
14+38.35 -Y8_DET- TO 21+84.79 -Y8_DET-	LT	811.75	2	2	2	67.98	6
13+64 -Y8_DET- TO 13+81 -Y8_DET-	RT	111.00	2	2		9.25	4
20+30 -Y8_DET- TO 20+45 -Y8_DET-	RT	63.00	2	2		5.25	4
29+69.37 -Y6- TO 31+64.71 -Y6-	RT	195.00	2			15.92	2
TOTAL		1180.75				98.40	16
SAY		1181.00				99.00	16.00

23-JUN-2016 08:39
U:\U2524D_Parsons\Proj\U2524D_RDY_SUM_03B-2.dgn
$$$$USERNAME$$$$