



CONSTRUCTION NOTES:

- 1) RECORD THE EXISTING SPLICE ARRANGEMENTS IN "AERIAL SPLICE ENCLOSURE #2" AND THE "SIGNAL CABINET GBO-007" FOR COMPARISON TO THE SUPPLIED SPLICE PLANS FOR FUTURE USE IN THE FINAL PHASE OF CONSTRUCTION "TMP-FINAL". IF DISCREPANCIES EXIST, CONTACT THE ENGINEER TO DETERMINE HOW TO PROCEED IN THE FINAL CONSTRUCTION PHASE.
- 2) REMOVE THE 6-FIBER DROP CABLE BETWEEN "AERIAL SPLICE ENCLOSURE #2" AND THE "SIGNAL CABINET GBO-007". LEAVE MESSENGER CABLE AND CONDUIT SYSTEM INTACT FOR FUTURE USE IN THE FINAL PHASE OF CONSTRUCTION "TMP-FINAL".
- 3) SAVE ETHERNET SWITCH FOR RE-INSTALLATION IN THE NEW SIGNAL CABINET DURING THE FINAL PHASE OF CONSTRUCTION "TMP-FINAL".

GENERAL NOTES:

- 1) NOTIFY THE CITY OF GREENSBORO TRANSPORTATION ENGINEER, JOE MULLINAX, AT (336) 373-2860; 5 DAYS PRIOR TO BEGINNING WORK ON THE SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE TRANSPORTATION ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

 <small>750 N. Greenfield Pkwy., Garner, NC 27529</small>	COMMUNICATIONS CABLE AND CONDUIT ROUTING PLANS		 <small>SEAL 023919</small>
	<small>DIVISION 07 GUILFORD COUNTY</small> <small>PLAN DATE: APRIL 2016</small> <small>PREPARED BY: A. J. SKUCE</small>	<small>REVIEWED BY: [Signature]</small> <small>DATE: []</small>	<small>INIT. DATE</small> <small>[] []</small>
<small>SCALE 1" = 60'</small>		<small>CADD Filename:</small>	