



CONSTRUCTION NOTES:

- 1) INSTALL NEW 6-FIBER DROP CABLES AND NEW 24-FIBER TRUNK CABLE AS SHOWN. REMOVE EXISTING 24-FIBER CABLE AS SHOWN.
- 2) RE-INSTALL ETHERNET SWITCH THAT WAS REMOVED DURING "TMP PHASE 1" FROM "GBO-041".
- 3) RE-INSTALL ETHERNET SWITCH THAT WAS REMOVED DURING "TMP PHASE 1" FROM "GBO-010" IN THE NEW "07-0535" SIGNAL CABINET.

GENERAL NOTES:

- 1) NOTIFY THE CITY OF GREENSBORO TRANSPORTATION ENGINEER, JOE MULLINAX, AT (336) 373-2860; 5 DAYS PRIOR TO BEGINNING WORK ON THE SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE TRANSPORTATION ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.

TMP FINAL

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

	<p>COMMUNICATIONS CABLE AND CONDUIT ROUTING PLANS</p>		
	<p>DIVISION 07 GUILFORD COUNTY GREENSBORO</p> <p>PLAN DATE: APRIL 2016 REVIEWED BY: <i>Neil Lacey</i></p> <p>PREPARED BY: A. J. SKUCE</p>	<p>REVISIONS</p> <p>INIT. DATE</p>	
<p>750 N. Greenfield Pkwy., Garner, NC 27529</p> <p>SCALE: 1" = 70'</p>		<p>DocuSigned by: <i>Gregory A. Fuller</i> 4/28/2016</p> <p>CADD File name:</p>	