


BM #19: RR SPIKE SET IN 18" OAK, STA. 31+26 -Y8-, S 22° 19' 57.9" E DIST. 312.72', EL. 841.27'

F.A. PROJECT NO. NHF-0708(53)



FOR UTILITY INFORMATION, SEE UTILITY PLANS AND SPECIAL PROVISIONS.

LOCATION SKETCH

HYDRAULIC DATA

DESIGN DISCHARGE	=	712 CFS
FREQUENCY OF DESIGN FLOOD	=	50 YRS.
DESIGN HIGH WATER ELEVATION	=	772.00
DRAINAGE AREA	=	1.12 SQ. MI.
BASE DISCHARGE (Q100)	=	902 CFS
BASE HIGH WATER ELEVATION	=	773.64

OVERTOPPING FLOOD DATA

OVERTOPPING DISCHARGE	=	1100 CFS
FREQUENCY OF OVERTOPPING FLOOD	=	100+ YRS.
OVERTOPPING FLOOD ELEVATION	=	777.39

GRADE DATA

GRADE POINT ELEVATION @		
STA. 2+22.93 -SPCY8-	=	777.95'
BED ELEVATION @		
STA. 2+22.93 -SPCY8-	=	762.42'
ROADWAY FILL SLOPES	=	2:1

TOTAL STRUCTURE QUANTITIES

CLASS A CONCRETE		
PHASE C3-P1	288.7	C.Y.
PHASE C3-P2	146.4	C.Y.
PHASE C3-P3	41.6	C.Y.
TOTAL	476.7	C.Y.
REINFORCING STEEL		
PHASE C3-P1	44,082	LBS.
PHASE C3-P2	22,723	LBS.
PHASE C3-P3	6,426	LBS.
TOTAL	73,231	LBS.
FOUNDATION COND. MATERIAL		
PHASE C3-P1	307	TONS
PHASE C3-P2	162	TONS
PHASE C3-P3	46	TONS
TOTAL	514	TONS
CULVERT EXCAVATION (TOTAL)	LUMP SUM	

NOTES

- ASSUMED LIVE LOAD -----HL-93 OR ALTERNATE LOADING.
- DESIGN FILL ----- 8.80'
- FOR OTHER DESIGN DATA AND NOTES, SEE STANDARD NOTE SHEET.
- 3" Ø WEEP HOLES INDICATED TO BE IN ACCORDANCE WITH THE SPECIFICATIONS.
- CONCRETE IN CULVERTS TO BE POURED IN THE FOLLOWING ORDER:
 1. WING FOOTING AND FLOOR SLAB INCLUDING 4" OF ALL VERTICAL WALLS.
 2. THE REMAINING PORTIONS OF THE WALLS, AND WING FULL HEIGHT FOLLOWED BY ROOF SLAB AND HEADWALL.
- THE RESIDENT ENGINEER SHALL CHECK THE LENGTH OF CULVERT BEFORE STAKING IT OUT TO MAKE CERTAIN THAT IT WILL PROPERLY TAKE CARE OF THE FILL.
- DIMENSIONS FOR WING LAYOUT AS WELL AS ADDITIONAL REINFORCING STEEL EMBEDDED IN BARREL ARE SHOWN ON WING SHEET.
- TRANSVERSE CONSTRUCTION JOINTS SHALL BE USED IN THE BARREL, SPACED TO LIMIT THE POURS TO A MAXIMUM OF 70 FEET. LOCATION OF JOINTS SHALL BE SUBJECT TO APPROVAL OF THE ENGINEER.
- AT THE CONTRACTOR'S OPTION, HE MAY SPLICE THE VERTICAL REINFORCING STEEL IN THE INTERIOR FACE OF EXTERIOR WALL AND BOTH FACES OF INTERIOR WALLS ABOVE LOWER WALL CONSTRUCTION JOINT. THE SPLICE LENGTH SHALL BE AS PROVIDED IN THE SPLICE LENGTH CHART SHOWN ON THE PLANS. EXTRA WEIGHT OF STEEL DUE TO THE SPLICES SHALL BE PAID FOR BY THE CONTRACTOR.

THE CONTRACTOR SHALL PROVIDE INDEPENDENT ASSURANCE SAMPLES OF REINFORCING STEEL AS FOLLOWS: FOR PROJECTS REQUIRING UP TO 400 TONS OF REINFORCING STEEL, ONE 30 INCH SAMPLE OF EACH SIZE BAR USED, AND FOR PROJECTS REQUIRING OVER 400 TONS OF REINFORCING STEEL, TWO 30 INCH SAMPLES OF EACH SIZE BAR USED. THE BARS FROM WHICH THE SAMPLES ARE TAKEN MUST THEN BE SPLICED WITH REPLACEMENT BARS OF THE SIZE AND LENGTH OF THE SAMPLE, PLUS A MINIMUM LAP SPLICE OF THIRTY BAR DIAMETERS. PAYMENT FOR THE SAMPLES OF REINFORCING STEEL SHALL BE CONSIDERED INCIDENTAL TO VARIOUS PAY ITEMS.

ALL PIPES THROUGH THE SIDEWALL OF THE CULVERT SHALL BE LOCATED BY THE ENGINEER. THE REINFORCING STEEL SHALL BE FIELD BENT AS NECESSARY TO CLEAR PIPE.

FOR CULVERT DIVERSION DETAILS AND PAY ITEM, SEE EROSION CONTROLS PLANS.

A 3 FOOT STRIP OF FILTER FABRIC SHALL BE ATTACHED TO THE FILL FACE OF THE WING COVERING THE ENTIRE LENGTH OF THE EXPANSION JOINT.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

FOR MAINTENANCE OF TRAFFIC, SEE TRAFFIC CONTROL PLANS.

FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.


FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.

FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.

NO PRECAST REINFORCED BOX CULVERT OPTION WILL BE ALLOWED.

FOR CONSTRUCTION SEQUENCE, SEE EROSION CONTROL PLANS.


I HEREBY CERTIFY THESE PLANS ARE THE AS-BUILT PLANS



PROFILE ALONG CULVERT #3

PROJECT NO. U-2524D
 GUILFORD COUNTY
 STATION: 2+22.93 -SPCY8-

SHEET 1 OF 5



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

CULVERT #3
 SINGLE 10' X 7' RCBC
 C3-P1, C3-P2 & C3-P3
 127° -05'-21" SKEW

REVISIONS				SHEET NO.
NO.	BY:	DATE:	NO.	DATE:
1			3	
2			4	

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

ASSEMBLED BY: E.I. OMILE DATE: 4/14
 CHECKED BY: I.H. FANG DATE: 6/6/16
 DRAWN BY: R.W. WRIGHT DATE: JULY, 1990
 CHECKED BY: D.A. GLADDEN DATE: JULY, 1990

SPECIAL
 STANDARD

ADDED NOV. 1, 1990