

SOLDIER PILE WALL WITH PRECAST PANEL - TYPICAL SECTIONS

AT THE CONTRACTOR'S OPTION, CONNECT COPING TO PANELS WITH DOWELS OR EXTEND COPING DOWN BACK OF PANELS AND PILES. *SEE CONCRETE DITCH BEHIND WALL DETAILS. **SEE PLANS FOR FINISHED GRADE OR END BENT SLOPE DETAILS.

NOTES:

FOR SOLDIER PILE RETAINING WALLS, SEE SOLDIER PILE RETAINING WALLS PROVISION.

DRILLED-IN H-PILES ARE REQUIRED FOR RETAINING WALL NO. 2.

AT THE CONTRACTORS OPTION USE A SOLDIER PILE RETAINING WALL WITH PRECAST CONCRETE PANELS THAT MEET SECTION 1077 OF THE STANDARD SPECIFICATIONS FOR RETAINING WALL NO. 2.

PAINT GALVANIZED H-PILES GRAY IN ACCORDANCE WITH ARTICLE 442-12 OF THE STANDARD SPECIFICATIONS FOR RETAINING WALL NO. 2.

AT THE CONTRACTOR OPTION USE A SOLDIER PILE RETAINING WALL WITH A CAST-IN-PLACE REINFORCED CONCRETE FACE FOR RETAINING WALL NO. 2.

BEFORE BEGINNING SOLDIER PILE WALL DESIGN FOR RETAINING WALL NO. 2, SURVEY WALL LOCATION AND SUBMIT A REVISED WALL PROFILE VIEW (WALL ENVELOPE) FOR REVIEW. DO NOT START WALL DESIGN OR CONSTRUCTION UNTIL THE REVISED WALL ENVELOPE IS ACCEPTED.

DESIGN RETAINING WALL NO. 2 FOR THE FOLLOWING: 1) H = DESIGN HEIGHT + WALL EMBEDMENT

2) DESIGN LIFE = 100 YEARS 3) MINIMUM WALL EMBEDMENT ELEVATION = 3,042 FT 4) MINIMUM PILE PENETRATION INTO ROCK = 10 FT

5) IN-SITU ASSUMED MATERIAL PARAMETERS FOR COLLUVIUM, ALLUVIUM AND FILL IN-SITU ASSUMED MATERIAL PARAMETERS ABOVE ELEVATION 3062 FT

UNIT WEIGHT, g = 120 LB/CF FRICTION ANGLE, f = 32 DEGREES

COHESION, c = 0 LB/SF

6)IN-SITU ASSUMED MATERIAL PARAMETERS FOR RESIDUAL ABOVE ELEVATION

3,055 FT:

UNIT WEIGHT, g = 125 LB/CF FRICTION ANGLE, f = 34 DEGREES

COHESION, c = 0 LB/SF 7) IN-SITU ASSUMED MATERIAL PARAMETERS FOR PARTIALLY WEATHER ROCK


ABOVE ELEVATION 3050 FT:

UNIT WEIGHT, g = 135 LB/CF FRICTION ANGLE, f = 38 DEGREES

COHESION, c = 0 LB/SF 8) IN-SITU ASSUMED MATERIAL PARAMETERS ROCK:

UNIT WEIGHT, g = 150 LB/CF FRICTION ANGLE, f = 45 DEGREES

COHESION, c = 0 LB/SF



GEOTECHNICAL

ENGINEER

SEAL 028893

Michael Stephens

9/14/2016

ENGINEER

SIGNATURE

DATE

*SEE CONCRETE DITCH BEHIND WALL DETAILS. **SEE PLANS FOR FINISHED GRADE OR END BENT SLOPE DETAILS.

SOLDIER PILE WALL WITH

CAST-IN-PLACE FACE - TYPICAL SECTION

B-5380 PROJECT NO.:

AVERY

COUNTY STATION: 12+65.00 -L- to 13+50.00 -L-

SHEET 2 OF 3



NORTH CAROLINA DEPARTMENT OF TRANSPORTATION **DIVISION OF HIGHWAYS**

GEOTECHNICAL ENGINEERING UNIT

SOLDIER PILE OPTION FOR RETAINING WALL #2

| REVISIONS | | | | | | SHEET |
|-----------|-----|---------|-----|--------------|------|-------|
| Ю. | BY | DATE | NO. | BY | DATE | NO. |
| 1 | MHS | 7-12-16 | 3 | - | - | W-2 |
| 2 | Ī | - | 4 | - | - | V V-Z |

PREPARED BY: MHS DATE: 9/14/16 REVIEWED BY: SCC DATE: 9/14/16