


INCLUDE ON THE COVER OF EACH SPLICE TRAY THE FOLLOWING:  
REFERENCE SECTION 1731 "FIBER OPTIC SPLICE ENCLOSURE"

- 1) SPLICE LOCATION
- 2) DATE
- 3) COMPANY NAME
- 4) NAME OF INDIVIDUAL PERFORMING THE SPICING

PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (1-4) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS.

ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.

NOTES:  
TRANSCIVER TERMINATION CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING \ ENSURING PROPER TERMINATIONS.



- NOTES:
1. REMOVE RADIO EQUIPMENT. RETURN RADIO, ANTENNA, MOUNTING HARDWARE AND LIGHTNING ARRESTOR TO THE ENGINEER. RECONNECT FIBER TRANSCIVER AND CONTROLLER.

TMP FINAL

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

	<b>SPLICE DETAIL</b>		SEAL
	DIVISION 14    MACON CO.    FRANKLIN		
PLAN DATE: MARCH 2016	REVIEWED BY:	INIT.	
PREPARED BY: I. N. AVERY	REVIEWED BY:	REVISIONS	DATE
DocuSigned by: <i>Gregory A. Fuller</i> 3/29/2016		CADD Filename:	