## STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

# PAVEMENT MARKING PLAN

# RANDOLPH COUNTY

LOCATION: BRIDGE NO. 374 OVER SANDY CREEK ON SR 2481 (LOW BRIDGE ROAD)

# B-5360 Rence Roach **DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED**

SHEET NO. PMP - 1

PROJECT REFERENCE NO.

### ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" -PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	_TITLE_
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO-LANE AND MULTILANE ROADWAYS
1205.12	PAVEMENT MARKINGS - BRIDGES
1261.01	GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS - TYPES AND MOUNTING
1262.01	GUARDRAIL END DELINEATION

### *INDEX*

SHEET NO.

DESCRIPTION

PMP - 1 PMP-2-3 PAVEMENT MARKING PLAN TITLE SHEET PAVEMENT MARKING DETAIL

### GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

MARKING ROAD NAME LOW BRIDGE ROAD THERMOPLASTIC NO MARKERS

- B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.
- C) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS.
- D) PASSING ZONES WILL BE DETERMINED IN THE FIELD AND MUST BE APPROVED BY THE ENGINEER.

### PAVEMENT MARKING SCHEDULE

SYMBOL

DESCRIPTION

THERMOPLASTIC (4", 90 MIL)

WHITE EDGELINE

THERMOPLASTIC (4", 120 MIL)

YELLOW DOUBLE CENTER

PLAN PREPARED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

R. B. ROACH, PE SIGNING & DELINEATION REGIONAL ENGINEER

A. N. KIDD

SIGNING & DELINEATION PROJECT DESIGN ENGINEER/TECHNICIAN

