# This electronic collection of documents is provided for the convenience of the user and is Not a Certified Document –

The documents contained herein were originally issued and sealed by the individuals whose names and license numbers appear on each page, on the dates appearing with their signature on that page.

This file or an individual page shall not be considered a certified document.

#### STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

### SIGNING PLAN RANDOLPH COUNTY

LOCATION: BRIDGE NO. 307 OVER MOUNT PLEASANT CREEK ON SR 2481 (LOW BRIDGE ROAD)

## PROJECT REFERENCE NO. B-5546 SIGN-1 APPROVED: Production of the state of the st

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

#### GENERAL NOTES

- . SIGNS FURNISHED BY CONTRACTOR
- . ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
- . IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- . WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
- . ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- . WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- . THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.
- . SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

#### ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO. TITLE

903.10 GROUND MOUNTED SIGN SUPPORTS

904.10 ORIENTATION OF GROUND MOUNTED SIGNS

904.50 MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS


#### SUMMARY OF QUANTITIES


ITEM NO.		TTEM DECODED TON	OLIANITITY	LINITT
DESC. NO.	SECT. NO.	ITEM DESCRIPTION	QUANTITY	UNIT
4072000000	903	SUPPORTS, 3 LB STEEL U-CHANNEL	351	L.F.
4096000000	904	SIGN ERECTION, TYPE D	2	EA.
4102000000	904	SIGN ERECTION, TYPE E	10	EA.
4155000000	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	8	EA.

PLAN PREPARED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

R. B. ROACH, PE SIGNING & DELINEATION REGIONAL ENGINEER

A. N. KIDD SIGNING & DELINEATION PROJECT DESIGN ENGINEER





#### INDEX

SHEET NO. DESCRIPTION

SIGN-1 TITLE SHEET, SIGN DESIGN,
& NOTES

SIGN-2 "E" SIGNS

SIGN-3 SIGN DETAIL SHEET

QUANTITY REQ'D 1  30 X 30 W1-28  ONE "U" POST PER SIGN	PROJECT REFERENCE NO.  B - 5546  SIGN - 2  APPROVED:  PROJECT REFERENCE NO.  B - 5546  SIGN - 2  APPROVED:  PROJECT REFERENCE NO.  B - 5546  SIGN - 2  APPROVED:  PROJECT REFERENCE NO.  B - 5546  SIGN - 2  APPROVED:  SSCOCKET CHAMBO.  CAROL  SEAL  O24921  MG   NE.  O24921  MG   NE.  O24921  MG   NE.  MG
402 QUANTITY REQ'D 1	
30 X 30 W1-2L	
403 QUANTITY REQ'D 2	
MOUNT BELOW SIGN 401 IN .1. INSTALLATIONS	
MOUNT BELOW SIGN 402 IN 1. INSTALLATIONS  404 QUANTITY REQ'D 3_	
18 X 24 W1-8L	
ONE "U" POST PER SIGN  ONE "U" POST PER SIGN  405 QUANTITY REQ'D 3_	
18 X 24 W1-8R	
ONE "U" POST PER SIGN	TYPE "E" SIGNS

