



8/17/99

PAVEMENT SCHEDULE			
(FINAL PAVEMENT DESIGN)			
A1	12" CONCRETE TRUCK APRON.	J3	PROPOSED 8" AGGREGATE BASE COURSE
A2	6" PORTLAND CEMENT CONCRETE PAVEMENT	K1	LIME STABILIZATION: (METHOD-SLURRY) 40% OF PROJECT; DEPTH OF 8", AT A RATE OF 20 LBS PER SQ. YD. AS DIRECTED BY THE ENGINEER. OR CEMENT STABILIZATION: 60% OF PROJECT; DEPTH OF 7", AT A RATE OF 55 LBS. PER SQ. YD. AS DIRECTED BY THE ENGINEER.
C1	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.	N1	GEOTEXTILE FOR PAVEMENT STABILIZATION.
C2	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT TO EXCEED 2" IN DEPTH.	R1	1'-6" CONCRETE CURB AND GUTTER.
D1	PROP. APPROX. 2.5" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 285 LBS. PER SQ. YD.	R2	2'-6" CONCRETE CURB AND GUTTER.
D2	PROP. APPROX. 4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.	R3	8"x18" CONCRETE CURB.
D3	PROP. VAR. DEPTH ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 2½" IN DEPTH OR GREATER THAN 4" IN DEPTH.	R4	2'-9" CONCRETE CURB AND GUTTER (SEE DETAIL).
E1	PROP. APPROX. 3" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 342 LBS. PER SQ. YD.	S1	4" CONCRETE SIDEWALK.
E2	PROP. APPROX. 4" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.	T1	EARTH MATERIAL.
E3	PROP. APPROX. 4.5" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 513 LBS. PER SQ. YD.	U1	EXISTING PAVEMENT.
E4	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 3" IN DEPTH OR GREATER THAN 5½" IN DEPTH.	V1	MILLING ASPHALT PAVEMENT. 3" DEPTH.
J1	PROPOSED 4" AGGREGATE BASE COURSE	W1	VARIABLE DEPTH ASPHALT PAVEMENT (SEE STANDARD WEDGING DETAILS).
J2	PROPOSED 6" AGGREGATE BASE COURSE	W2	VARIABLE DEPTH ASPHALT PAVEMENT (SEE STANDARD WEDGING DETAILS).


NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.



W1: WEDGING DETAIL FOR RESURFACING



W2: WEDGING DETAIL FOR RESURFACING
-DR2- ONLY



PROJECT REFERENCE NO.	SHEET NO.
U-3440	2A-1
ROADWAY DESIGN ENGINEER	PAVEMENT DESIGN ENGINEER
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	



Stantec Consulting Services Inc.
801 Jones Franklin Road
Suite 300
Raleigh, NC 27606
Tel. (919) 851-6866
Fax. (919) 851-7024
www.stantec.com
License No. F-0672