PROJ. REFERENCE NO.	SHEET NO.
B-5343	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Clearing and grubbing, unclassified excavation, borrow excavation, fine grading, and removal of existing asphalt pavement will be paid for at the lump sum price for "Grading."

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt
L (LT)	(cu. yd.)	(cu. yd.)	L (RT)	(cu. yd.)	(cu. yd.)	LDET	(cu. yd.)	(cu. yd.)	DR	(cu. yd.)	(cu. yd.)						
12+09.00	0	0	12+09.00	0	0	10+00.00	0	0	10+13.37	0	0						
12+25.00	0	0	12+25.00	0	0	10+25.00	1	1	10+25.00	0	1						
12+50.00	0	0	12+50.00	0	0	10+50.00	2	1	10+50.00	0	6						
12+75.00	0	0	12+75.00	0	0	10+75.00	2	2	10+75.00	9	3						
13+00.00	0	0	13+00.00	0	0	11+00.00	2	3	11+00.00	15	0						
13+25.00	0	0	13+25.00	0	0	11+25.00	7	7	11+25.00	17	0						
13+50.00	14	0	13+50.00	6	3	11+44.96	11	10	11+50.00	22	0						
13+75.00	13	0	13+75.00	9	0	11+50.00	3	3	11+52.53	2	0						
14+00.00	17	0	14+00.00	7	0	11+75.00	15	13									
14+25.00	20	0	14+25.00	8	0	12+00.00	12	13									
14+50.00	18	0	14+50.00	9	0	12+25.00	9	13									
14+75.00	16	0	14+75.00	11	0	12+50.00	10	11									
15+00.00	17	0	15+00.00	12	0	12+75.00	11	11									
15+25.00	9	0	15+25.00	11	0	13+00.00	7	11									
15+50.00	1	0	15+50.00	9	0	13+25.00	3	13									
15+75.00	1	0	15+75.00	11	1	13+50.00	1	18									
16+00.00	0	1	16+00.00	12	1	13+75.00	0	24									
16+23.88	1	2	16+23.88	5	6	14+00.00	0	50									
Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt									
L (LT)	(cu. yd.)	(cu. yd.)	L (RT)	(cu. yd.)	(cu. yd.)	LDET	(cu. yd.)	(cu. yd.)									
16+96.13	0	0	16+96.13	0	0	14+90.00	0	0									
17+25.00	1	2	17+25.00	2	2	15+25.00	0	176									
17+50.00	1	6	17+50.00	1	1	15+50.00	0	98									
17+75.00	10	9	17+75.00	1	0	15+75.00	0	82									
18+00.00	18	8	18+00.00	1	0	16+00.00	0	73									
18+25.00	16	7	18+25.00	2	0	16+25.00	0	70									
18+50.00	16	5	18+50.00	3	0	16+50.00	0	67									
18+75.00	15	4	18+75.00	3	0	16+75.00	0	61									
19+00.00	9	3	19+00.00	4	0	17+00.00	0	50									
19+25.00	5	2	19+25.00	3	0	17+25.00	2	37									
19+50.00	0	0	19+50.00	0	0	17+50.00	3	26									
19+75.00	0	0	19+75.00	0	0	17+75.00	2	17									
20+00.00	0	0	20+00.00	0	0	17+88.37	1	6									
20+25.00	0	0	20+25.00	0	0	18+00.00	1	4									
20+50.00	0	0	20+50.00	0	0	18+25.00	2	7									
20+75.00	0	0	20+75.00	0	0	18+50.00	2	4									
21+00.00	0	0	21+00.00	0	0	18+75.00	2	2									
21+31.77	0	0	21+31.77	0	0	19+00.00	2	1									
						19+26.15	1	0									