



**SCOPE OF WORK:**

REMOVE AND REPAIR UNSOUND CONCRETE ON BRIDGE DECK.  
 REMOVE EXISTING BRIDGE DECK JOINT MATERIAL.  
 INSTALL NEW SILICONE JOINT SEALS.  
 PARTIALLY REMOVE BRIDGE DECK CONCRETE, USING SHOTBLAST METHOD.  
 OVERLAY PREPARED BRIDGE DECK WITH EPOXY OVERLAY SYSTEM.  
 EPOXY INJECTION OF CONCRETE CRACKS.  
 PERFORM SHOTCRETE REPAIRS.  
 REPAIR PILES WITH NEW PILE JACKETS OR REJACKET PILES.  
 REPAIR PIVOT PIER PILES.  
 MECHANICAL AND ELECTRICAL REHABILITATION.  
 MILL AND PAVE ASPHALT APPROACHES.

PROJECT NO. B-5936  
TYRRELL COUNTY  
 BRIDGE NO. 7

SHEET 1 OF 3



DocuSigned by:  
 Robbie Weisz 10/2016

CEA153463B6D43D...

STATE OF NORTH CAROLINA  
 DEPARTMENT OF TRANSPORTATION  
 RALEIGH

**GENERAL DRAWING  
 BRIDGE #7 ON US64  
 OVER THE ALLIGATOR  
 RIVER**

DRAWN BY : P. D. BRYANT DATE : 6/2016  
 CHECKED BY : R. WEISZ DATE : 6/2016

DOCUMENT NOT CONSIDERED  
 FINAL UNLESS ALL  
 SIGNATURES COMPLETED

REVISIONS						SHEET NO.	
NO.	BY:	DATE:	NO.	BY:	DATE:	S-2	
1			3			TOTAL SHEETS	
2			4			394	