REPAIR QUANTITY TABLE NOTES: REPAIR LOCATIONS AND ESTIMATE OF QUANTITIES ARE GIVEN WITH THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE INSPECTOR OR ENGINEER THE CONTRACTOR SHALL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATION AND DESCRIPTION OF THE REPAIRS AND ADJUST THE ACTUAL QUANTITIES ENTERED INTO THE REPAIR QUANTITY TABLE. QUANTITIES REPAIRS BENT 157 ESTIMATE ACTUAL VOLUME CF VOLUME CF AREA SE SHOTCRETE REPAIRS CAP (VERTICAL FACE) 0.0 0.0 CAP (HORIZONTAL, CORNER) 0.0 0.0 FOR CAP REPAIR DETAILS, SEE "TYPICAL CAP REPAIR DETAILS" SHEET. EPOXY RESIN INJECTION LN.FT. LN.FT. FOR "SHOTCRETE REPAIRS", SEE SPECIAL PROVISIONS. FOR "EPOXY RESIN INJECTION", SEE SPECIAL PROVISIONS. 0.0 VALUES IN CHART REPRESENT ESTIMATED REPAIR TOTALS AFTER REMOVAL OF UNSOUND CONCRETE, MIN. OF 1"BEHIND REBAR AND MIN. 2"CL TO SAWCUT. SEE REPAIR DETAILS. SPAN 158 SPAN 157 Р3 P2 ELEVATION END VIEW <u>ELEVATION</u> END VIEW EAST SIDE B-5936 PROJECT NO. TYRRELL COUNTY DocuSigned by: Paul Bryant BRIDGE NO. SPAN 157 -3653D2AF1B77448.. SPAN 158 - SHOTCRETE REPAIR 8/10/2016 STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION ERI - EPOXY RESIN INJECTION PLAN NO REPAIRS NOTED DURING INSPECTION BY STRUCTURES MANAGEMENT UNIT. THE CONTRACTOR AND ENGINEER SHALL INSPECT THE BENT PRIOR TO BEGINNING WORK. BOTTOM OF CAP **BENT 157** REVISIONS DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED S-198 DATE : <u>4-2016</u> DATE : <u>4-2016</u> P. D. BRYANT DRAWN BY : CHECKED BY :