



LOCATION SKETCH

INFORMATION INDICATED ON THE LOCATION SKETCH SHALL BE CONSIDERED GENERAL INFORMATION ONLY. THE CONTRACTOR SHALL CONFIRM, THROUGH OTHER SOURCES, SPECIFIC INFORMATION REGARDING BRIDGES, ROADWAYS, UTILITIES, THE SURROUNDING AREA, AND ANY OTHER ASPECTS THAT MAY BE NECESSARY TO PERFORM AND COMPLETE THE PROJECT.

TOTAL BILL OF MATERIAL

BRIDGE	CLEANING AND PAINTING EXISTING WEATHERING STEEL FOR BRIDGE #_	PAINTING CONTAINMENT FOR BRIDGE #_	POLLUTION CONTROL	CONCRETE DECK REPAIR FOR EPOXY OVERLAY	EPOXY OVERLAY SYSTEM - MECHANICALLY DISTRIBUTED	BRIDGE JOINT DEMOLITION	ELASTOMERIC CONCRETE	FOAM JOINT SEALS
	LUMP SUM	LUMP SUM	LUMP SUM	SQ. FT.	SQ. FT.	SQ. FT.	CU. FT.	LUMP SUM
McDOWELL #12	LUMP SUM	LUMP SUM	LUMP SUM	—	6,719	162	40.4	LUMP SUM
McDOWELL #16	LUMP SUM	LUMP SUM	LUMP SUM	6	6,789	162	40.4	LUMP SUM
TOTAL	LUMP SUM	LUMP SUM	LUMP SUM	6	13,508	324	80.8	LUMP SUM

NOTES

EXISTING DIMENSIONS AND BRIDGE CONDITION ARE FROM THE BEST INFORMATION AVAILABLE. THE CONTRACTOR SHALL FIELD VERIFY THE INFORMATION SHOWN ON THE PLANS AND NOTIFY THE ENGINEER IF ACTUAL DIMENSIONS AND CONDITIONS DIFFER.

IT IS THE CONTRACTOR'S RESPONSIBILITY TO FOLLOW ALL STATE AND FEDERAL SAFETY REQUIREMENTS.

FOR EPOXY OVERLAY SYSTEM, SEE SPECIAL PROVISIONS.

FOR CONCRETE DECK REPAIR FOR EPOXY OVERLAY, SEE SPECIAL PROVISIONS.

EXISTING JOINTS AND DECK DRAINS SHALL BE SEALED PRIOR TO BEGINNING REPAIR OF BRIDGE DECKS.

FOR CONTROL OF TRAFFIC AND LIMITS ON PHASING OF CONSTRUCTION, SEE TRANSPORTATION MANAGEMENT PLANS.

LONGITUDINAL CONSTRUCTION JOINTS OF OVERLAYS SHALL BE LOCATED ALONG THE CENTERLINE OR EDGE OF TRAVEL LANES.

FOR CLEANING AND PAINTING OF BRIDGE, SEE PAINTING EXISTING WEATHERING STEEL STRUCTURE SPECIAL PROVISION.

FOR POLLUTION CONTROL, SEE PAINTING EXISTING WEATHERING STEEL STRUCTURE SPECIAL PROVISION.

FOR PAINTING CONTAINMENT, SEE PAINTING EXISTING WEATHERING STEEL STRUCTURE SPECIAL PROVISION.

FOR BRIDGE JOINT DEMOLITION, SEE SPECIAL PROVISIONS.

FOR ELASTOMERIC CONCRETE, SEE SPECIAL PROVISIONS.

FOR FOAM JOINT SEALS, SEE SPECIAL PROVISIONS.

FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.

FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.

PROJECT NO. I-5833
McDOWELL COUNTY
 BRIDGE NO. 12 & 16

DocuSigned by:
John A. Yannaccone
 7BC3680
 NORTH CAROLINA
 PROFESSIONAL
 SEAL
 32492
 JOHN A. YANNACCONE
 ENGINEER
 7/19/2016

SHEET 3 OF 3
 STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 GENERAL DRAWING
 FOR BRIDGES ON I-40
 OVER SR 1103
 (CATAWBA AVENUE)

DRAWN BY : S. WANCP DATE : 06/16
 CHECKED BY : J. YANNACCONE DATE : 06/16

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	TOTAL SHEETS
1			3			S-3
2			4			6