PROJECT REFERENCE NO.	SHEET NO.
R-3826	EC-3

ROADSIDE ENVIRONMENTAL PROJECT ENGINEER

LEVEL III CERTIFIED BY:
STACEY H. BAILEY, PE
CERTIFICATION NUMBER: 3074
ISSUED: SEPTEMBER 27, 2016

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	12+00	14+00	RT	185
4	-L-	12+00	14+00	LT	250
5	-L-	25+50	31+50	RT	565
5	-L-	25+50	30+20	LT	380
5	-L-	35+00	39+63	RT	435
5	-L-	38+50	39+61	LT	90
5	-Y-	21+50	22+70	RT	45
6	-L-	39+61	41+50	LT	155
6	-L-	46+07	47+00	LT	75
8	-L-	73+50	74+00	RT	45
9	-L-	81+00	82+00	RT	85
9	-L-	81+00	81+50	LT	45
9	-Y1-	19+00	19+81	LT	65
9	-Y1-	21+00	22+00	RT	85
9	-Y1-	21+00	21+75	LT	65
9	-Y1-	21+00	22+00	LT	90
10	-L-	106+50	112+00	RT	505
13	-L-	135+50	138+00	LT	255
13	-L-	141+00	148+00	LT	810
13	-L-	140+00	141+00	RT	95
13	-Y2-	10+50	12+25	LT	165
13	-Y2-	12+25	16+50	RT	420
13	-Y2-	13+50	14+00	LT	55
13	-Y2-	14+50	16+00	LT	155
15	-Y1-	14+50	15+00	RT	45
				SUBTOTAL	5,165
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					11,195
				TOTAL	16,360
				SAY	16,400

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
6	-L-	40+00	40+50	RT	55
6	-L-	45+50	46+50	RT	95
7	-L-	58+66	59+00	LT	35
8	-L-	74+00	74+96	RT	100
8	-L-	74+50	75+50	LT	80
12	-L-	134+00	135+50	RT	140
14	-Y-	28+50	30+40	RT	195
14	-Y-	30+40	32+00	RT	165
				SUBTOTAL	865
		ADDITIONAL PSRM TO BE INSTALLED			0
				TOTAL	865
				SAY	900