# 1 P . R - 3876

## T: C203830

### STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

### SIGNING PLAN MARTIN COUNTY

LOCATION: NC 125 WILLIAMSTON BYPASS FROM SR 1182 (EAST COLLEGE ROAD) TO NC 125 NORTHWEST OF WILLIAMSTON

### GENERAL NOTES

- . SIGNS FURNISHED BY STATE
- . CONFIRM IN WRITING AT LEAST 4 MONTHS IN ADVANCE, THE ACTUAL DATE THE DEPARTMENT FURNISHED SIGNS WILL BE REQUIRED.
- . ALL TYPE  $^\prime D^\prime$  SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
- . IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- . WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL  $^{\prime}\text{E}^{\prime}$  AND  $^{\prime}\text{F}^{\prime}$  SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
- . ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- . WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- . THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.

### ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:


STD. NO.	<u>TITLE</u>
901.50	ARROWS AND SHIELDS
901.70	SIGN STRINGERS AND SUPPORT SPACING
903.10	GROUND MOUNTED SIGN SUPPORTS
903.20	MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON WOOD POSTS
904.10	ORIENTATION OF GROUND MOUNTED SIGNS

### SUMMARY OF QUANTITIES ITEM DESCRIPTION ITEM NO. |QUANTITY| UNIT DESC. SECT. NO. 903 4072000000 SUPPORTS, 3-LB STEEL U-CHANNEL (CROSS BRACING) 130 4082000000 903 SUPPORTS, WOOD 4096000000 SIGN ERECTION, TYPE D EA. 904 4102000000 SIGN ERECTION, TYPE E EA. 4108000000 SIGN ERECTION, TYPE F EA. 4116100000 EA. SIGN ERECTION, RELOCATE SIGN TYPE D EA. 4116100000 SIGN ERECTION, RELOCATE SIGN TYPE E 4116100000 SIGN ERECTION, RELOCATE SIGN TYPE F EA. 4141000000 EA. DISPOSAL OF SUPPORT, WOOD 4155000000 907 DISPOSAL OF SIGN SYSTEM, U-CHANNEL 4158000000 DISPOSAL OF SIGN SYSTEM, WOOD EA. EA. 4192000000 DISPOSAL OF SUPPORT, U-CHANNEL 4273000000 DISPOSAL OF SIGN SYSTEM, SPAN WIRE EA. 4238000000 907 DISPOSAL OF SIGN, D, E OR F EA.

### PLAN REVIEWED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

A. ALQUDWAH, P.E. SIGNING & DELINEATION REGIONAL ENGINEER

D. M. EATON, P.E. SIGNING & DELINEATION PROJECT DESIGN ENGINEER



### SHEET NO. DESCRIPTION SIGN-1 SIGN-2 E SHEET SIGN-3 F SHEET SIGN-4-7 SIGN DESIGNS SIGN-8-12 PROPOSED SIGN DETAIL SHEETS SIGN-13-17 EXISTING SIGN DETAIL SHEETS

*INDEX* 

PLAN PREPARED BY: HDR/ICA

M. T. RZEPKA, P.E. PROJECT ENGINEER

A. C. PILZ, P.E. DESIGN ENGINEER

FDS ICA

SHEET NO.

SIGN-1

TIP NO.

R-3826

Michael T. Ryepha

**UNLESS ALL SIGNATURES COMPLETED** 

10/5/2016

5121 Kingdom Way, Suite 100 Raleigh, NC 27607