DocuSign Envelope ID: 278E99FF-264E-47E6-94FD-B6F998932D8D

TIP NO.	SHEET NO.
R-5023B	PMP-1A

APPROVED: DocuSigned by: Rhonda B. Early F34CAF5AC6BF48A...

DATE: 9/29/2016

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 023521 ENGINEER RHONDA B. EARLY

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

FINAL PAVEMENT MARKING SCHEDULE

MATERIAL	SYMBOL	DESCRIPTION
PAVEMENT MARKING		
THERMOPLASTIC (4″, 90 MILS)		
	TA	WHITE EDGELINE
THERMOPLASTIC (4″, 120 MILS)		
	T8	2FT-6FT WHITE MINI-SKIP
	TD	3FT-9FT WHITE MINI-SKIP
	TE	4″ WHITE SOLID LANE LINE
	TF	10FT YELLOW SKIP
	TH	YELLOW SINGLE CENTER
	TI	YELLOW DOUBLE CENTER
THERMOPLASTIC (12″, 90 MILS)		
	TV	YELLOW DIAGONAL
THERMOPLASTIC (24″, 120 MILS)		
	T2	WHITE STOP BAR
THERMOPLASTIC SYMBOL (90 MILS)		
	UA	LEFT TURN ARROW
	UC	STRAIGHT ARROW
	UE	STRAIGHT/RIGHT TURN ARROW
THERMOPLASTIC CHARACTER (120 MILS)		
	UI	ALPHANUMERIC CHARACTERS
PERMANENT RAISED PAVEMENT MARKERS		
	MA	YELLOW & YELLOW
SNOWPLOWABLE PAVEMENT MARKERS		
	ME	YELLOW & YELLOW
	MF	CRYSTAL & RED

LEGEND

GENERAL

DIRECTION OF TRAFFIC FLOW

NORTH ARROW

PROPOSED PVMT. ---------- EXIST. PVMT.

PAVEMENT MARKINGS

PAVEMENT MARKING SYMBOLS

UA

UC

UE

HNTB
HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554

PAVEMENT MARKING DETAIL

4:16:50 PM
PMP\R5023B_pmp_PMP01A.dgn