

## ECONOLITE ASC/3-2070 OVERLAP PROGRAMMING DETAIL

(program controller as shown)

1. From Main Menu select 2. CONTROLLER
2. From CONTROLLER Submenu select 2. VEHICLE OVERLAPS

*OVERLAP A*

Select TMG VEH OVLP [A] and 'PPLT FYA'

TMG VEH OVLP...[A] TYPE: ....PPLT FYA

PROTECTED LEFT TURN.... PHASE 1  
OPPOSING THROUGH..... PHASE 2

FLASHING ARROW OUTPUT....CH9 ISOLATE

DELAY START OF: FYA..0.0 CLEARANCE..0.0

ACTION PLAN SF BIT DISABLE..... 0

Toggle Once

*OVERLAP B*

Select TMG VEH OVLP [B] and 'PPLT FYA'

TMG VEH OVLP...[B] TYPE: ....PPLT FYA

PROTECTED LEFT TURN.... PHASE 3  
OPPOSING THROUGH..... PHASE 4

FLASHING ARROW OUTPUT....CH10 ISOLATE

DELAY START OF: FYA..0.0 CLEARANCE..0.0

ACTION PLAN SF BIT DISABLE..... 0

Toggle Once

*OVERLAP C*

Select TMG VEH OVLP [C] and 'PPLT FYA'

TMG VEH OVLP...[C] TYPE: ....PPLT FYA

PROTECTED LEFT TURN.... PHASE 5  
OPPOSING THROUGH..... PHASE 6

FLASHING ARROW OUTPUT....CH11 ISOLATE

DELAY START OF: FYA..0.0 CLEARANCE..0.0

ACTION PLAN SF BIT DISABLE..... 0

Toggle Once

*OVERLAP D*

Select TMG VEH OVLP [D] and 'PPLT FYA'

TMG VEH OVLP...[D] TYPE: ....PPLT FYA

PROTECTED LEFT TURN.... PHASE 7  
OPPOSING THROUGH..... PHASE 8

FLASHING ARROW OUTPUT....CH12 ISOLATE

DELAY START OF: FYA..0.0 CLEARANCE..0.0

ACTION PLAN SF BIT DISABLE..... 0

END PROGRAMMING

## FLASHER CIRCUIT MODIFICATION DETAIL


In order to ensure that signals flash concurrently on the Same approach, make the following flasher circuit changes:

1. On rear of PDA - remove wire from Term. T2-4 and terminate on T2-2.
2. On rear of PDA - remove wire from Term. T2-5 and terminate on T2-3.
3. Remove flasher unit 2.

The changes listed above ties all phases and overlaps to flasher unit 1.

THIS ELECTRICAL DETAIL IS FOR  
THE SIGNAL DESIGN: 06-0016  
DESIGNED: April 2016  
SEALED: 10-14-16  
REVISED: N/A

18-007-2016\_08-16  
 S:\IT\ASIS\TSS\Sigal\work\hgr\pda\sig\Main\Peterson\060016\_sml.ele\_xxx.dgn  
 J.Peterson

Electrical Detail Sheet 2 of 3		DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED									
<div style="text-align: center;">  <p>750 N. Greenfield Pkwy, Garner, NC 27529</p> </div>	<p><b>I-95 Business / US 301</b> (Eastern Boulevard) at <b>SR 2299 (Russell Street)</b></p> <p>Division 6 Cumberland County Fayetteville</p> <p>PLAN DATE: October 2016 REVIEWED BY: BAS</p> <p>PREPARED BY: James Peterson REVIEWED BY:</p>	<div style="border: 1px solid black; border-radius: 50%; padding: 10px; width: 80px; margin: auto;"> <p>SEAL</p> <p style="font-size: x-small;">NORTH CAROLINA PROFESSIONAL ENGINEER KEITH M. MINS</p> </div> <p>DocuSigned by: <b>Keith M. Mins</b> 10/20/2016 27807886C03M4S DATE</p> <p>SIG. INVENTORY NO. 06-0016</p>									
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 80%;">REVISIONS</th> <th style="width: 10%;">INIT.</th> <th style="width: 10%;">DATE</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>			REVISIONS	INIT.	DATE						
REVISIONS	INIT.	DATE									