INDEX OF SHEETS

ITS-1..... TITLE SHEET
ITS-2..... INDEX OF SHEETS, ROADWAY STANDARD DRAWINGS, AND ABBREVIATIONS
ITS-3..... CONSTRUCTION NOTES AND LEGEND
ITS-4-ITS-5..... PLAN KEY
ITS-6..... JUNCTION BOX AND DELINEATOR DETAILS
ITS-7-ITS-12..... CCTV ELECTRICAL SERVICE DETAILS
ITS-13..... SYSTEM BLOCK DIAGRAM
ITS-14-ITS-19..... TRAFFIC OPERATIONS CENTER LAYOUT
ITS-20-ITS-21..... NCDOT DIVISION 6 LAYOUT
ITS-22-ITS-39..... SUMMARY OF WORK BY INTERSECTION
ITS-40-ITS-41..... SUMMARY OF WORK BY CCTV
ITS-42-ITS-117..... COMMUNICATIONS PLANS
ITS-118-ITS-141..... EXISTING CCTV UPGRADES
ITS-142-ITS-160..... NEW CCTV INSTALLATIONS
ITS-161-ITS-172..... CABLE SCHEMATIC
ITS-173-ITS-258..... SPLICE DETAILS

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS"- ROADWAY DESIGN UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
848.01	CONCRETE SIDEWALK
1101.02	TEMPORARY LANE CLOSURES
1101.04	TEMPORARY SHOULDER CLOSURES
1700.01	ELECTRICAL SERVICE OPTIONS
1700.02	ELECTRICAL SERVICE GROUNDING
1705.01	SIGNAL HEADS
1705.02	SIGNAL HEADS
1705.03	SIGNAL HEADS
1715.01	UNDERGROUND CONDUIT
1716.01	JUNCTION BOXES
1720.01	WOOD POLES
1730.01	FIBER OPTIC CABLE
1736.01	SPREAD SPECTRUM RADIO
1751.01	CONTROLLERS AND CABINETS

ABBREVIATIONS

AGUY = AERIAL GUY
ATT = AT&T TELEPHONE
BS = BACK SIDE OF POLE
BKT = BRACKET
C.LINK = CENTURY LINK
CITY = CITY OF FAYETTEVILLE
COMM = COMMUNICATIONS CABLE
DEP = DUKE ENERGY PROGRESS
DL = DRIP LOOP
DOT = N.C. DEPARTMENT OF TRANSPORTATION
(F) = FRONT SIDE OF POLE
FOC = FIBER OPTIC CABLE
GUY = GUY ASSEMBLY
LLI = LOOP LEAD IN
MESS. CABLE = MESSENGER CABLE
NEU = DUKE ENERGY NEUTRAL
OHG = OVERHEAD GUY
OWS = OPEN WIRE SECONDARY
P GUY = POWER GUY
PWC = PUBLIC WORKS COMMISSION
PWR = POWER
RSR = RISER
SEC = SECONDARY POWER
SGUY = SIDEWALK GUY
SIG = SIGNAL CABLE
SLB = STREET LIGHT BRACKET
SLDL = STREET LIGHT DRIP LOOP
SVC RSR = SERVICE RISER
TPX = TRIPLEX
TFMR = TRANSFORMER
TWC = TIME WARNER CABLE
VERIZON = VERIZON COMMUNICATIONS
WH = WEATHERHEAD
XMESS = CROSS MESSENGER

Kimley»Horn
NC License #F-0102
421 Fayetteville St., Suite 600
Raleigh, NC 27636
Tel: (919) 677-2000
Fax: (919) 677-2050

Plans Prepared For:
750 N. Greenfield Pkwy., Garner, NC 27529

SCALE 0

FAYETTEVILLE COMPUTERIZED SIGNAL SYSTEM
INDEX OF SHEETS, ROADWAY STANDARD DRAWINGS, AND ABBREVIATIONS

DIVISION 06 CUMBERLAND COUNTY
PLAN DATE: NOVEMBER 2016 REVIEWED BY: K. NICHOLAS
PREPARED BY: J. CROSS REVIEWED BY: K. SMITH

REVISIONS	INIT.	DATE

SEAL
NORTH CAROLINA PROFESSIONAL SEAL 030472 ENGINEER KEVIN W. SMITH
DocuSigned by: Kevin Smith 11/15/2016
0886E0A6380440F...
SIGNATURE DATE
CADD Filename:

11/15/2016
K:\RAL_TPTO_ITS\011036305 - Fayetteville Sig Sys\Plans\011036305_ITS_psh_2.dgn