

**\* TOTAL BILL OF MATERIAL**

BRIDGE	MOBILIZATION	INCIDENTAL MILLING	ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B	ASPHALT BINDER FOR PLANT MIX	△ REINFORCING STEEL	SHOTCRETE REPAIRS	EPOXY RESIN INJECTION	BRIDGE JOINT REMOVAL	PILE JACKETS	REJACKETS	SILICONE JOINT SEALANT	PRESTRESSED CONCRETE GIRDER FLANGE REPAIR MATERIAL	CONCRETE DECK REPAIR FOR EPOXY OVERLAY	EPOXY OVERLAY SYSTEM- MECHANICALLY DISTRIBUTED
	LUMP SUM	SQ.YDS.	TONS	TONS	LBS.	CU. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	CU. FT.	SQ. FT.	SQ. FT.
TYRRELL #7	LUMP SUM	267	22.5	1.5	1000	938	98.1	9,429	7,013.5	438	9,489	279	566.7	387,507

\* EXCLUDES BILL OF MATERIAL FOR PIVOT PIER PILE REPAIRS AND FOR MECHANICAL AND ELECTRICAL PLANS, SEE SHT'S SA-1 THRU SA-3 AND SHT'S G-1 THRU M-23.  
 △ REINFORCING STEEL QUANTITY IS NOT ANTICIPATED, A TOKEN PAY ITEM IS INDICATED FOR PRICING PURPOSES, IN CASE UNANTICIPATED REPAIRS ARE ENCOUNTERED.

PROJECT NO. B-5936  
TYRRELL COUNTY  
 BRIDGE NO. 7

1/11/2017



DocuSigned by  
*Robbie Weisz*

CEA153463B8D43D  
 DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					
<b>TOTAL BILL OF MATERIAL</b>					
REVISIONS					SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
TOTAL SHEETS					S-1
394					

DRAWN BY : S. T. SANDOR DATE : 06/2016  
 CHECKED BY : R. N. WEISZ DATE : 06/2016