



SCOPE OF WORK:

REMOVE AND REPAIR UNSOUND CONCRETE ON BRIDGE DECK.
 REMOVE EXISTING BRIDGE DECK JOINT MATERIAL.
 INSTALL NEW SILICONE JOINT SEALS.
 PARTIALLY REMOVE BRIDGE DECK CONCRETE, USING SHOTBLAST METHOD.
 OVERLAY PREPARED BRIDGE DECK WITH EPOXY OVERLAY SYSTEM.
 EPOXY INJECTION OF CONCRETE CRACKS.
 PERFORM CONCRETE SUPERSTRUCTURE REPAIRS.
 PERFORM CONCRETE SUBSTRUCTURE REPAIRS.
 REPAIR PILES WITH NEW PILE JACKETS OR REJACKET PILES.
 REPAIR PIVOT PIER PILES.
 MECHANICAL AND ELECTRICAL REHABILITATION.
 MILL AND PAVE ASPHALT APPROACHES.

PROJECT NO. B-5936
TYRRELL COUNTY
 BRIDGE NO. 7

SHEET 1 OF 3

1/11/2017



DocuSigned by:
Robbie Weisz

CEA153463B6D43D...
 DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH						SHEET NO.
GENERAL DRAWING BRIDGE #7 ON US64 OVER THE ALLIGATOR RIVER						S-2
REVISIONS						TOTAL SHEETS
NO.	BY:	DATE:	NO.	BY:	DATE:	394
1			3			
2			4			

DRAWN BY : P. D. BRYANT DATE : 6/2016
 CHECKED BY : R. WEISZ DATE : 6/2016