FAR SIDE PIER CONDUIT SCHEDULE

COND NO.	FROM EQUIPMENT	TO EQUIPMENT	NO. AND SIZE OF CABLE	GROUND COND.	SPARE	FILL (SQ. IN)	TRADE SIZE
C86	FAR SIDE SUBMARINE CABINET	FAR SIDE ROADWAY JUNCTION BOX	51 - NO. 12, 9 - NO. 10	1 - NO. 12	NONE	1.160	2"
C87	FAR SIDE ROADWAY JUNCTION BOX	FAR SIDE ONCOMING WARNING GATE	11 - NO. 12, 3 - NO. 10	1 - NO. 12	NONE	0.290	1"
C88	FAR SIDE ROADWAY JUNCTION BOX	FAR SIDE OFFGOING WARNING GATE	11 - NO. 12, 3 - NO. 10	1 - NO. 12	NONE	0.290	1"
C89	FAR SIDE ROADWAY JUNCTION BOX	FAR SIDE BARRIER GATE	21 - NO. 12, 3 - NO. 10	1 - NO. 12	NONE	0.471	1 1/4"
C90	FAR SIDE ROADWAY JUNCTION BOX	FAR SIDE TRAFFIC LIGHT	4 - NO. 12	1 - NO. 12	NONE	0.091	3/4"
C91	FAR SIDE ROADWAY JUNCTION BOX	FAR SIDE FLASHING LIGHT	4 - NO. 12	1 - NO. 12	NONE	0.091	3/4"
C92	FAR SIDE FLASHING LIGHT	FAR SIDE GONG	2 - NO. 12	1 - NO. 12	NONE	0.054	3/4"

NOTES:

1. ALL NOTES ON SHEET E-45 APPLY TO THIS SHEET.

PROJECT NO. B-5936

TYRRELL COUNTY

BRIDGE NO: 7

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

CONDUIT SIZE & FILL SCHEDULE 3

ALLIGATOR RIVER SWING SPAN

Hardesty & Hanover
engineering that moves you

DocuSigned by: Scott Reynolds
BFEC5720F8F14B0...
9/14/2016

NORTH CAROLINA PROFESSIONAL SEAL 036065 ENGINEER SCOTT A. REYNOLDS

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	E-47
1			3			TOTAL SHEETS
2			4			51

DRAWN BY: OIV DATE : 8/8/2016
CHECKED BY: MJT DATE : 8/8/2016
DESIGN ENGINEER OF RECORD: CHS DATE : 8/8/2016

DWG NUMBER	TOTAL DWGS
63	90

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

$$$