


TOTAL BILL OF MATERIAL

BRIDGE NO.	GROOVING BRIDGE FLOORS	CLASS II. SURFACE PREPARATION	CLASS III. SURFACE PREPARATION	LATEX MODIFIED CONCRETE OVERLAY - VERY EARLY STRENGTH	PLACING AND FINISHING LATEX MODIFIED CONCRETE OVERLAY - VERY EARLY STRENGTH	◆ CONCRETE REPAIRS	◆ SHOTCRETE REPAIRS	EPOXY RESIN INJECTION	FOAM JOINT SEALS	EXPANSION JOINT SEAL REPAIR	CLEANING & REPAINTING OF BRIDGE #__	CLEANING AND PAINTING EXISTING WEATHERING STEEL FOR BRIDGE #__	POLLUTION CONTROL	PAINTING CONTAINMENT FOR BRIDGE #__	VOLUMETRIC MIXER	CONCRETE FOR DECK REPAIR	ELASTOMERIC CONCRETE	BEAM REPAIR	EPOXY COATING	BRIDGE JOINT DEMOLITION	SCARIFYING BRIDGE DECK	HYDRO-DEMOLITION OF BRIDGE DECK	REMOVE AND RESET BEARINGS	BRIDGE JACKING
	SO. FT.	SO. YDS.	SO. YDS.	CU. YDS.	SO. YDS.	CU. FT.	CU. FT.	LIN. FT.	LUMP SUM	LIN. FT.	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	CU. FT.	CU. FT.	LBS.	SO. FT.	SO. FT.	SO. YDS.	SO. YDS.	EA.	EA.
412	5,430	66.0	2.0	36.5	657	—	6.5	8.0	—	—	LUMP SUM	—	LUMP SUM	LUMP SUM	LUMP SUM	12.0	—	—	—	—	657	657	—	—
415	5,430	66.0	2.0	36.5	657	—	—	12.0	—	—	LUMP SUM	—	LUMP SUM	LUMP SUM	LUMP SUM	12.0	—	—	—	—	657	657	—	—
421	5,834	70.0	1.5	39.3	708	39.6	67.7	9.7	LUMP SUM	—	LUMP SUM	—	LUMP SUM	LUMP SUM	LUMP SUM	9.0	24.5	860	296	98	708	708	—	2
422	5,552	65.0	1.5	37.4	673	12.8	37.8	—	LUMP SUM	—	LUMP SUM	—	LUMP SUM	LUMP SUM	LUMP SUM	9.0	24.5	2,115	300	99	673	673	—	5
429	—	—	—	—	—	86.8	1,056.5	42.5	—	—	LUMP SUM	—	LUMP SUM	LUMP SUM	—	—	—	130	1,132	—	—	—	12	15
827	—	—	—	—	—	—	—	—	—	88.5	—	LUMP SUM	LUMP SUM	LUMP SUM	—	—	—	—	—	—	—	—	—	—
TOTALS	22,246	267.0	7.0	149.7	2,695	139.2	1,168.5	72.2	LUMP SUM	88.5	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	42.0	49.0	3,105	1,728	197	2,695	2,695	12	22

◆ QUANTITY HAS BEEN INCREASED DUE TO THE POTENTIAL FOR FURTHER DETERIORATION SINCE THE FIELD INSPECTION BY STRUCTURES MANAGEMENT UNIT.

PROJECT NO. I-5892
BUNCOMBE COUNTY
 BRIDGE NO. 412,415,421,422
429,827

DocuSigned by:
John A. Yannaccone
 7BC...

 1/31/2017

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
TOTAL BILL OF MATERIAL

DRAWN BY : S. WANCE DATE : 10/16
 CHECKED BY : J. YANNAKONE DATE : 12/16

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			S-1 TOTAL SHEETS 68
2			4			