

PROJECT NO.	SHEET NO.	TOTAL NO.
2017CPT.10.10.10131.1, ETC.	19	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	PATCHING EXISTING PAVEMENT TONS	ASPHALT SURFACE TREATMENT, MATCOAT, #67 STONE SY	ASPHALT SURFACE TREATMENT, MATCOAT, #78M STONE SY	ASPHALT SURFACE TREATMENT, DOUBLE SEAL SY	EMULSION FOR ASPHALT SURFACE TREATMENT GAL	CONCRETE CURB RAMPS EA	6" DRIVEWAYS SY	RETROFIT EXISTING CURB RAMPS EA	ADJ. OF MANHOLES EA	ADJ. OF METER OR VALVE BOX EA	PORTABLE LIGHTING LS	TEMPORARY SILT FENCE LF	WATTLE LF	
2017CPT.10.10.10131.1	Cabarrus	1	US 29 (NORTHBOUND LANES)	FROM GEORGES LILES BLVD. TO PAVEMENT JOINT AT SPEEDWAY MP 3.50 TO MP 1.50	1,2,3	2		NO	NO	2	26	350	38,500			15,400						1	400	320	
TOTAL FOR PROJ NO. 2017CPT.10.10.10131.1										2		350	38,500			15,400						1	400	320	
2017CPT.10.10.10131.2	Cabarrus	2	US 29 (SOUTHBOUND LANES)	PAVEMENT JOINT AT GEORGE LILES BLVD TO PAVEMENT JOINT AFTER BRIDGE MP 3.50 TO 1.50	1,2,3	2		NO	NO	2	26	350	38,900			15,560						*			
TOTAL FOR PROJ NO. 2017CPT.10.10.10131.2										2		350	38,900			15,560									
2017CPT.10.10.10131.3	Cabarrus	3	NC 73 (CHURCH STREET)	FROM CORBIN STREET TO BUFFALO STREET MP 11.47 TO 10.62	4,5	2		NO	NO	0.83	36	300					1		5	6	6	*			
2017CPT.10.10.10131.3	Cabarrus	4	NC 73 (CHURCH STREET)	FROM BUFFALO STREET TO WINECOFF MP 10.62 TO 9.79	4,5	2		NO	NO	0.83	40	300								4	4	*			
2017CPT.10.10.10131.3	Cabarrus	5	NC 73 (CHURCH STREET) (SOUTHBOUND LANES)	FROM WINECOFF STREET TO DAVIDSON DRIVE MP 9.79 TO MP 9.35	6	2		NO	NO	0.44	26	150								5	5	*			
2017CPT.10.10.10131.3	Cabarrus	6	NC 73 (CHURCH STREET) (NORTHBOUND LANES)	WINECOFF STREET TO DAVIDSON DRIVE MP 14.05 TO MP 14.49	6	2		NO	NO	0.44	24	150								3	3	*			
TOTAL FOR PROJ NO. 2017CPT.10.10.10131.3										2.54		900					1		5	18	18				
2017CPT.10.10.20131.2	Cabarrus	7	SR 1002 (OLD SALISBURY CONCORD RD)	FROM SR 2474 (SIMMONS RD) TO SR 2113 (PENNINGER RD) MP 0.80 TO MP 4.00	7	2		NO	NO	3.2	24	1,600	45,056			18,022							300	560	
TOTAL FOR PROJ NO. 2017CPT.10.10.20131.2										3.2		1,600	45,056			18,022							300	560	
2017CPT.10.10.20131.3	Cabarrus	8	SR 1625 (ROGERS LAKE RD)	FROM PAVEMENT JOINT BEFORE SR 1008 (SOUTH MAIN ST TO BRIDGE MP 0.03 TO MP 1.78	8,9	2		NO	NO	1.75	22	500	24,744			8,660				1	1		200	240	
2017CPT.10.10.20131.3	Cabarrus	9	SR 1766 (ROGERS LAKE RD)	FROM NC 3 TO SR 1008 (SOUTH MAIN ST) MP 0.14 TO MP 0.64	21	2		NO	NO	0.5	23	150								1	1		300	160	
TOTAL FOR PROJ NO. 2017CPT.10.10.20131.3										2.25		650	24,744			8,660				2	2		500	400	
2017CPT.10.10.20131.4	Cabarrus	10	SR 1790 (WINECOFF RD)	FROM NC 73 TO SR 1778 (ORPHANGE RD) MP 1.50 TO MP 0.70	10,11,12	2		NO	NO	0.8	22	200							2				400	280	
TOTAL FOR PROJ NO. 2017CPT.10.10.20131.4										0.8		200							2				400	280	
2017CPT.10.10.20131.5	Cabarrus	11	SR 2268 (SUTHER RD)	FROM SR 1002 (OLD SALSI CONCORD RD) TO SR 2289 (FLOWERFIELD DR) MP 0.00 TO MP 0.35	13	2		NO	NO	0.35	20				4,107	2,259								320	
2017CPT.10.10.20131.5	Cabarrus	12	SR 2269 (DIARY FARM RD)	FROM SR 2268 (SUTHER RD) TO END MAINT. MP 0.00 TO MP 0.26	13	2		NO	NO	0.26	20				3,051	1,678								160	
2017CPT.10.10.20131.5	Cabarrus	13	SR 2282 (MOONSHINE DR)	FROM SR 2268 (SUTHER RD) TO SR 2269 (DIARY FARM RD) MP 0.00 TO MP 0.23	13	2		NO	NO	0.23	20				2,699	1,484									
2017CPT.10.10.20131.5	Cabarrus	16	SR 2288 (BRICKSTONE DR)	FROM SR 2282 (MOONSHINE DR) TO SR 2289 (FLOWERFIELD DR) MP 0.00 TO MP 0.30	13	2		NO	NO	0.3	20	75			3,637	2,000									
2017CPT.10.10.20131.5	Cabarrus	17	SR 2289 (FLOWERFIELD DR)	FROM SR 2288 (BRICKSTONE CIRCLE) TO SR 2269 (DIARY FARM RD) MP 0.00 TO 0.17	13	2		NO	NO	0.17	20				1,995	1,098								480	
TOTAL FOR PROJ NO. 2017CPT.10.10.20131.5										1.31		75			15,489	8,519								480	
2017CPT.10.10.20131.6	Cabarrus	14	SR 2287 (CHURCH ST)	FROM NC 73 BUS. TO US 29 MP 0.41 TO MP 0.07	14	2		NO	NO	0.34	60	120								2	2	*			
2017CPT.10.10.20131.6	Cabarrus	15	SR 2287 (CHURCH ST)	FROM US 29 TO NC 73 MP 0.38 TO MP 0.27	14	2		NO	NO	0.11	20	40								2	1	*			
TOTAL FOR PROJ NO. 2017CPT.10.10.20131.6										0.45		160								4	3				
2017CPT.10.10.20131.7	Cabarrus	18	SR 2411 (COLD SPRINGS RD)	FROM NC 49 TO SR 1006 (MOUNT PLEASANT RD) MP 6.65 TO MP 8.20	7	2		NO	NO	1.45	22	700	19,001			7,600							300	320	
TOTAL FOR PROJ NO. 2017CPT.10.10.20131.7										1.45		700	19,001			7,600								300	320
2017CPT.10.10.20131.8	Cabarrus	19	SR 2435 (KLUTZ RD)	FROM SR 2444 (ST STEVENS CH RD) TO SR 2446 (MT OLIVE RD) MP 0.00 TO MO 1.27	15	2		NO	NO	1.27	20				14,902	8,196							300	240	
TOTAL FOR PROJ NO. 2017CPT.10.10.20131.8										1.27					14,902	8,196								300	240
2017CPT.10.10.20131.9	Cabarrus	20	SR 2453 (LENTZ HARNESS SHOP RD)	FROM NC 73 TO PAVEMENT JOINT AT SR 2603 (LITTLE BEAR CREEK RD) MP 0.00 TO MP 2.97	15	2		NO	NO	2.97	21	200			28,213	15,517							300	280	
TOTAL FOR PROJ NO. 2017CPT.10.10.20131.9										2.97		200			28,213	15,517								300	280