

PROJECT NO.	SHEET NO.	TOTAL NO.
2017CPT.08.12.20191,	9	
2017CPT.08.12.20531		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	AGGREGATE SHOULDER BORROW TON	SHOULDER RECONSTRUCTION SMI	1.5" MILLING SY	INCIDENTAL MILLING SY	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TON	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	ASPHALT SURFACE TREATMENT, MATCOAT, #67 STONE SY	EMULSION FOR ASPHALT SURFACE TREATMENT GAL	ADJUST METER OR VALVE BOX EA	INDUCTIVE LOOP SAWCUT LF
2017CPT.08.12.20191	Chatham	1	SR 1012 (PITTSBORO-MONCURE RD)	FROM US 15-501 TO SR 1011 (OLD US 1)	1	2		NO	NO	8.275	24	2,295.00	16.55	560	1,200	10,910		655	1,200	116,700.00	46,700	2	500
TOTAL FOR MAP NO. 1										8.275		2,295.00	16.55	560	1,200	10,910		655	1,200	116,700.00	46,700	2	500
2017CPT.08.12.20191	Chatham	2	SR 1526 (PARKER HERNDON RD)	FROM SR 1525 (HAMLET CHP RD) TO SR 1528 (ANDREWS STORE RD)	2	2		NO	NO	1.915	20	530.00	3.83		167		1,710	115	570				
TOTAL FOR MAP NO. 2										1.915		530.00	3.83		167		1,710	115	570				
TOTAL FOR PROJ NO. 2017CPT.08.12.20191										10.19		2,825.00	20.38	560	1,367	10,910	1,710	770	1,770	116,700.00	46,700	2	500
2017CPT.08.12.20531	Lee	3	SR 1329 (OLD CARBONTON RD)	FROM CONST JOINT @ SR 1009 (CARBONTON RD) TO DEAD END	3	2	2WU	NO	NO	0.303	18	85.00	0.61		471		315	21	251				
TOTAL FOR MAP NO. 3										0.303		85.00	0.61		471		315	21	251				
2017CPT.08.12.20531	Lee	4	SR 1540 (DOYLE COX RD)	FROM CONST JOINT @ SR 1538 (BUCKHORN RD) TO DEAD END	3	2	2WU	NO	NO	0.761	20	212.00	1.52				815	55	722				
TOTAL FOR MAP NO. 4										0.761		212.00	1.52				815	55	722				
2017CPT.08.12.20531	Lee	5	SR 1243 (WOODSIDE DRIVE)	FROM SR 1244 (HUNT SPRINGS DRIVE) TO DEAD END	3	2	2WU	NO	NO	0.334	20	93.00	0.67		225		395	26	20				
TOTAL FOR MAP NO. 5										0.334		93.00	0.67		225		395	26	20				
2017CPT.08.12.20531	Lee	6	SR 1245 (MEADOW DRIVE)	FROM SR 1001 (LEMON SPRINGS RD) TO SR 1244 (HUNT SPRINGS RD)	3	2	2WU	NO	NO	0.167	20	50.00	0.34		2,000		225	15	10				
TOTAL FOR MAP NO. 6										0.167		50.00	0.34		2,000		225	15	10				
2017CPT.08.12.20531	Lee	7	SR 1401 (ZIMMERMAN RD)	FROM SR 1400 (CUMNOCK RD) TO SR 1450 (ZIMMERMAN RD)	3	2	2WU	NO	NO	0.058	24	18.00	0.12		200		105	7	5				
TOTAL FOR MAP NO. 7										0.058		18.00	0.12		200		105	7	5				
TOTAL FOR PROJ NO. 2017CPT.08.12.20531										1.623		458.00	3.26		2,896		1,855	124	1,008				
GRAND TOTAL										11.813		3,283.00	23.64	560	4,263	10,910	3,565	894	2,778	116,700.00	46,700	2	500