

(program controller as shown below)

- 1. FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1, 2, 3, 4, 5 AND 6.
- 2. FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).





## OUTPUT REFERENCE SCHEDULE

OUTPUT 42 = Overlap C Red
OUTPUT 43 = Overlap C Yellow
OUTPUT 44 = Overlap C Green
OUTPUT 50 = Overlap A Red
OUTPUT 51 = Overlap A Yellow
OUTPUT 52 = Overlap A Green

OVERLAP PROGRAMMING DETAIL


PROJECT REFERENCE NO.

U-4715 B

|Sig. 39.2

(program controller as shown below)

FROM MAIN MENU PRESS '8' (OVERLAPS), THEN '1' (VEHICLE OVERLAP SETTINGS).



PRESS '+' TWICE

PAGE 1: VEHICLE OVERLAP 'C' SETTINGS
PHASE: | 12345678910111213141516

VEH OVL PARENTS: | XX

VEH OVL NOT VEH: |
VEH OVL NOT PED: |
VEH OVL GRN EXT: |
STARTUP COLOR: \_ RED \_ YELLOW \_ GREEN
FLASH COLORS: \_ RED \_ YELLOW X GREEN

SELECT VEHICLE OVERLAP OPTIONS: (Y/N)
FLASH YELLOW IN CONTROLLER FLASH?...Y
GREEN EXTENSION (0-255 SEC)......0
YELLOW CLEAR (0=PARENT.3-25.5 SEC)...0.0
RED CLEAR (0=PARENT.0.1-25.5 SEC)...0.0
OUTPUT AS PHASE # (0=NONE, 1-16)...0

OVERLAP PROGRAMMING COMPLETE

## PED 3 PROGRAMMING DETAIL

(program controller as shown below)

## CHANGING OUTPUT ASSIGNMENTS

- 1. FROM MAIN MENU SELECT '6' (OUTPUTS), THEN '1' (OUTPUT ASSIGNMENTS)
- 2. ENTER 17 (PHASE 8 DW) FOR OUTPUT ASSIGNMENT #.
- 3. SCROLL DOWN TO 'PEDESTRIAN PHASE' AND ENTER 'Y' REGARDLESS OF DEFAULT PROGRAMMING!
- 4. ENTER '3' FOR 'SELECT PEDESTRIAN PHASE'. NO CHANGE NEEDED FOR 'SELECT COLOR'
- 5. BACKUP TO 'OUTPUT ASSIGNMENTS AND SETTINGS MENU: BY PRESSING THE 'ESC' BUTTON ON KEYBOARD.
- 6. SELECT '1' (OUTPUT ASSIGNMENTS)
- 7. ENTER 18 (PHASE 8 W) FOR OUTPUT ASSIGNMENT #.
- 8. REPEAT STEPS # 3 AND # 4.

## CHANGING INPUT ASSIGNMENTS

- 1. FROM MAIN MENU SELECT '7' (DETECTORS), THEN '2' (PEDESTRIAN DETECTOR ASSIGNMENTS)
- 2. CYCLE TO PED DETECTOR #8 BY REPEATEDLY DEPRESSING '+' KEY
- 3. MODIFY PHASE ASSIGNED TO PED DETECTOR # 8 FROM PHASE 8 TO PHASE 3

PROGRAMMING COMPLETE

Prepared in the Offices of:

750 N.Greenfield Pkwy, Garner, NC 27529

Electrical Detail - Sheet 2 of 2

ELECTRICAL AND PROGRAMMING US 70-74A (Tunnel Road)

at SR 2042 (Chunns Cove Road)/ Innsbruck Mall Entrance

Innsbruck Mall Entrance

Division 13 Buncombe County Ashev

PLAN DATE: June 2016 REVIEWED BY: BAS

PLAN DATE: June 2016 REVIEWED BY: BAS
PREPARED BY: C. Strickland REVIEWED BY:
REVISIONS INIT. DATE

SEAL
030530

SEAL
030530

ONGINEER

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Zacpary M. Rittle 8/8/2016

OC21EFD94F5341F... DATE

SIG. INVENTORY NO. 13-0231

08-AUG-2016 11:03 S:\*ITS&SU\*ITS Signals\*Workgroups\*Sig Man\*Strickland cestrickland

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 13-0231 DESIGNED: December 2015 SEALED: 8/5/2016 REVISED: