PROJECT REFERENCE NO. SHEET NO. Sig. 74.3

ALTERNATE PHASING ACTIVATION DETAIL

TO RUN ALT. PHASING DURING FREE RUN - PROGRAM CHANGES (SHOWN BELOW) IN A TIME BASED ACTION PLAN.

SCHEDULE A DAY PLAN THAT INCLUDES THE ACTION PLAN PROGRAMMED

TO SELECT PHASE SEQUENCE PAGE 2.

TO RUN ALT. PHASING DURING COORDINATION - SELECT THE TIME BASED ACTION PLAN THAT IS PROGRAMMED

TO SELECT PHASE SEQUENCE PAGE 2.

PHASING	PHASE SEQUENCE PAGE
ACTIONS REQUIRED TO RUN DEFAULT PHASING	1
ACTIONS REQUIRED TO RUN ALTERNATE PHASING	2

IMPORTANT: IF ALT. PHASING IS USED DURING FREE RUN AND COORDINATION, DO NOT OPERATE TIME OF DAY EVENTS CONCURRENTLY WITH COORDINATION PLAN EVENTS IN THE EVENT SCHEDULER. (EX. FREE RUN EVENT STARTS AND VICE-VERSA).

ALTERNATE PHASING CHANGE SUMMARY

THE FOLLOWING IS A SUMMARY OF WHAT TAKES PLACE WHEN PHASE SEQUENCE PAGE 2 ACTIVATED DURING ALTERNATE PHASING:

PH SEQ PAGE 2:

Activates phases 14 and 12 in barriers 3 and 4 allowing extended service on the active phase in the absence of a service call on the opposing phase.

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 13-0291
DESIGNED: February 2016
SEALED: 11/1/2016
REVISED: N/A

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED Electrical Detail - Sheet 3 of 3 US 25 (Hendersonville Road) ELECTRICAL AND PROGRAMMING DETAILS FOR: EB I-40 Exit Ramp Division 13 Buncombe County Asheville PLAN DATE: October 2016 REVIEWED BY: BAS PREPARED BY: S. Armstrong REVIEWED BY: REVISIONS INIT. DATE 750 N.Greenfield Pkwy, Garner, NC 27529 SIG. INVENTORY NO. 13-0291

sarmstrong