

# SUMMARY OF WORK BY CABLE ROUTING PLANS



CABLE ROUTING SHEET NUMBER	MESSENGER CABLE (1/4")	BOND MESSENGER CABLE	TRACER WIRE	UNDERGROUND CONDUIT (1 CONDUIT, 1 INCH)	UNDERGROUND CONDUIT (1 CONDUIT, 2 INCH)	UNDERGROUND CONDUIT (2 CONDUIT, 2 INCH)	DIRECTIONAL DRILL (2 CONDUIT, 2 INCH)	DIRECTIONAL DRILL (1 CONDUIT, 2 INCH)	JUNCTION BOX (OVER-SIZED)	JUNCTION BOX (SPECIAL -SIZED)	REMOVE EXISTING JUNCTION BOX	DELINEATOR MARKER	STANDARD GUY ASSEMBLY	AERIAL GUY ASSEMBLY	SIDEWALK GUY ASSEMBLY	1" RISER WITH WEATHERHEAD FOR CCTV ELEC SERVICE	1" RISER WITH WEATHERHEAD FOR CAT 5E OR COMPOSITE	1" RISER WITH HEAT SHRINK TUBING	1.25" RISER WITH HEAT SHRINK TUBING	2" RISER WITH HEAT SHRINK TUBING	HEAT SHRINK TUBING RETROFIT KIT	DRILL CORE DRILL EXIST FOUNDATION
	LF	EA	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
CRP-6.137	1,410	-	-	-	-	-	-	-	-	-	-	-	3	-	-	-	-	-	-	-	-	-
CRP-6.138	1,550	1	-	-	-	-	-	-	-	-	-	-	4	-	-	-	-	-	-	-	-	-
CRP-6.139	530	2	920	-	-	690	230	-	2	-	-	1	1	-	-	-	-	-	-	2	-	-
CRP-6.140	440	1	980	-	-	110	870	-	3	-	-	1	3	-	-	-	-	-	-	1	-	-
CRP-6.141	620	1	790	-	-	510	280	-	4	1	-	1	1	-	-	-	-	-	-	1	-	-
CRP-6.142	-	-	1,390	-	-	90	1,300	-	3	-	-	2	-	-	-	-	-	-	-	-	-	-
CRP-6.143	-	-	1,390	-	-	670	720	-	6	-	-	1	-	-	-	-	-	-	-	-	-	-
CRP-6.144	-	-	1,340	-	-	890	370	-	5	1	1	1	-	-	-	-	-	-	-	-	-	-
CRP-6.145	470	1	1,330	-	-	-	-	-	-	-	-	-	1	-	-	-	-	-	-	-	-	-
CRP-6.146	130	1	1,570	-	-	230	-	-	1	2	2	1	1	-	-	-	1	-	-	1	-	-
CRP-6.147	370	1	1,010	-	-	-	340	-	1	1	1	-	1	-	-	-	-	-	-	1	-	-
CRP-6.148	1,540	1	-	-	-	-	-	-	-	-	-	-	4	-	-	-	-	-	-	-	-	-
CRP-6.149	1,620	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	-
CRP-6.150	1,510	2	-	-	-	-	-	-	-	-	-	-	2	-	-	-	-	-	-	1	-	-
CRP-6.151	860	2	580	-	-	150	430	-	2	1	-	1	1	-	1	-	-	-	-	2	-	-
CRP-6.152	820	2	650	-	-	-	650	-	2	-	-	-	2	-	2	-	-	-	-	2	-	-
CRP-6.153	1,540	1	-	-	-	-	-	-	-	-	-	-	3	-	2	-	-	-	-	1	-	-
CRP-6.154	1,410	3	340	-	-	-	340	-	2	1	-	3	3	-	5	-	-	-	-	2	-	-
CRP-6.155	290	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	-
CRP-6.156	300	2	-	-	-	-	-	-	-	-	-	-	2	-	-	-	-	-	-	2	-	-
CRP-6.157	270	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	-	-
CRP-6.158	-	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.159	200	1	-	-	-	-	-	-	-	-	-	-	1	-	-	-	-	-	-	-	1	-
CRP-6.160	60	2	-	-	-	-	-	-	-	-	-	-	2	-	-	-	-	-	-	-	1	-
CRP-6.161	110	2	820	-	-	230	590	-	4	-	-	-	1	-	-	-	1	-	-	1	1	-
CRP-6.162	1,420	1	-	-	-	-	-	-	-	-	-	-	4	1	1	-	-	-	-	-	-	-
CRP-6.163	1,440	1	-	-	-	-	-	-	-	-	-	-	2	4	3	-	-	-	-	-	-	-
CRP-6.164	1,400	2	-	-	-	-	-	-	-	-	-	-	1	1	-	-	-	-	-	1	-	-
CRP-6.165	1,580	2	-	-	-	-	-	-	-	-	-	-	3	2	2	-	-	-	1	1	-	1
CRP-6.166	1,790	3	-	-	-	-	-	-	-	-	-	-	2	1	-	-	-	-	1	-	-	-
CRP-6.167	1,410	2	100	-	20	90	-	-	2	1	-	-	6	5	-	-	1	-	-	2	-	-
CRP-6.168	1,360	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.169	1,700	2	-	-	-	-	-	-	-	-	-	-	2	-	1	-	-	-	-	1	-	-
CRP-6.170	1,460	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.171	910	2	-	-	-	-	-	-	-	-	-	-	3	-	-	-	-	-	-	-	-	-

21-DEC-2016 14:20 0:\Projects\Information\Traffic\Cur#100048632 U-4715B Asheville\11\_Typ\_SDW\Volume 1\Main Directory\CRP-1.012.dgn WILE2054 AT DUS300019

- Work shown on this sheet is a summary of work for the installation of the fiber-optic cable and CCTV installations that are shown on the cable routing plans (i.e. CRP sheets). Work to be done for traffic signals is shown separately on the signal designs and the "Summary of Work by Intersection" sheets in Volume III of III.
- The items listed above are for informational purposes only and represent work that is necessary to complete the project and are not necessarily pay items. See Summary of Quantities and the Project Special Provisions for defined Pay Items for this contract.

**ATKINS** 1616 EAST MILLBROOK ROAD, SUITE 310  
RALEIGH, NORTH CAROLINA 27609  
(919) 876-6888 NCBEES #F-0326

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

 Prepared for the Offices of: 750 Greenfield Parkway, Garner, NC 27529	Asheville Signal System Summary of Work by Cable Routing Plans (sheet 13 of 30)		
	Division 13 Buncombe County Asheville	PLAN DATE: December 2016 REVIEWED BY: M B Toth	
NTS	REVISIONS	INIT.	DATE

12/21/2016  
CADD File name: CRP-1.012.dgn