



SUMMARY OF WORK BY CABLE ROUTING PLANS

CABLE ROUTING SHEET NUMBER	MESSENGER CABLE (1/4")	BOND MESSENGER CABLE	TRACER WIRE	UNDERGROUND CONDUIT (1 CONDUIT, 1 INCH)	UNDERGROUND CONDUIT (1 CONDUIT, 2 INCH)	UNDERGROUND CONDUIT (2 CONDUIT, 2 INCH)	DIRECTIONAL DRILL (2 CONDUIT, 2 INCH)	DIRECTIONAL DRILL (1 CONDUIT, 2 INCH)	JUNCTION BOX (OVER-SIZED)	JUNCTION BOX (SPECIAL-SIZED)	REMOVE EXISTING JUNCTION BOX	DELINEATOR MARKER	STANDARD GUY ASSEMBLY	AERIAL GUY ASSEMBLY	SIDEWALK GUY ASSEMBLY	1" RISER WITH WEATHERHEAD FOR CCTV ELEC SERVICE	1" RISER WITH WEATHERHEAD FOR CAT 5E OR COMPOSITE	1" RISER WITH HEAT SHRINK TUBING	1.25" RISER WITH HEAT SHRINK TUBING	2" RISER WITH HEAT SHRINK TUBING	HEAT SHRINK TUBING RETROFIT KIT	DRILL/ CORE DRILL EXIST FOUNDATION
	LF	EA	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
CRP-6.172	100	1	330	-	-	370	200	-	2	1	-	-	1	-	-	-	-	-	-	1	-	-
CRP-6.173	1,190	1	-	-	-	-	-	-	-	-	-	-	2	-	-	-	-	-	-	1	-	-
CRP-6.174	1,620	3	-	-	-	-	-	-	-	-	-	-	4	-	1	-	1	-	-	2	1	-
CRP-6.175	1,750	4	-	-	-	-	-	-	-	-	-	-	3	1	2	-	-	-	-	3	-	-
CRP-6.176	830	1	-	-	-	-	-	-	-	-	-	-	3	-	-	-	-	-	-	1	-	1
CRP-6.177	1,500	1	-	-	-	-	-	-	-	-	-	-	2	-	-	-	-	-	-	-	-	-
CRP-6.178	330	3	780	-	-	-	-	-	1	1	-	-	-	-	-	-	-	-	-	1	2	-
CRP-6.179	1,110	1	270	-	-	140	130	-	2	1	-	-	3	-	-	-	-	-	-	1	-	-
CRP-6.180	-	-	730	-	-	610	210	-	3	1	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.181	640	1	110	-	-	-	110	-	2	1	-	-	3	-	-	-	-	-	-	1	-	-
CRP-6.182	130	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	-	-	-
CRP-6.183	1,680	1	-	-	-	-	-	-	-	-	-	-	5	-	-	-	-	-	-	-	-	-
CRP-6.184	1,170	2	110	-	-	-	110	-	2	-	-	-	4	-	-	-	-	-	-	2	1	-
CRP-6.185	120	2	100	-	20	-	80	-	2	-	-	-	-	-	-	-	-	-	-	1	1	1
CRP-6.186	440	3	-	-	-	-	-	-	-	-	-	-	1	-	-	-	-	-	-	-	3	-
CRP-6.187	-	2	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2	-
CRP-6.188	-	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	-
CRP-6.189	280	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	-
CRP-6.190	1,560	2	-	-	-	-	-	-	-	-	-	-	1	-	-	-	-	-	-	-	2	-
CRP-6.191	-	1	1,860	-	60	280	620	-	2	1	-	-	-	-	-	-	1	-	-	1	1	4
CRP-6.192	-	-	1,450	-	-	1,400	50	-	2	-	-	2	-	-	-	-	-	-	-	-	-	-
CRP-6.193	1,360	2	150	-	-	90	60	-	2	-	-	-	-	-	2	-	-	-	-	2	-	-
CRP-6.194	890	2	340	-	-	90	250	-	3	-	-	-	2	-	-	-	-	-	-	2	-	-
CRP-6.195	990	1	160	-	-	-	160	-	1	-	-	-	-	-	1	-	-	-	-	1	-	-
CRP-6.196	1,090	2	400	-	10	-	400	-	3	1	-	2	1	-	-	-	-	-	-	2	-	-
CRP-6.197	1,380	1	-	-	-	-	-	-	-	-	-	-	8	-	-	-	-	-	-	-	-	-
CRP-6.198	1,400	2	-	-	-	-	-	-	-	-	-	-	1	-	1	-	-	-	-	1	-	-
CRP-6.199	1,790	3	50	-	-	-	50	-	1	-	-	-	2	-	1	-	-	-	-	3	-	1
CRP-6.200	870	2	680	-	-	100	580	-	4	1	-	2	1	-	1	-	-	-	-	2	-	-
CRP-6.201	90	2	140	-	10	60	80	-	2	-	-	-	1	-	1	-	-	-	-	-	-	1
CRP-6.202	1,200	1	-	-	-	-	-	-	-	-	-	-	3	-	-	1	-	1	1	-	-	-
CRP-6.203	1,460	1	-	-	-	-	-	-	-	-	-	-	1	-	-	-	-	-	-	1	-	1
CRP-6.204	1,400	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.205	820	1	-	-	-	-	-	-	-	-	-	-	1	-	-	-	-	-	1	-	-	-
CRP-6.206	620	1	600	-	-	430	170	-	2	1	-	-	1	-	-	-	-	-	-	1	-	-

27-DEC-2016 15:04
 C:\Users\jtruff\Documents\Task 11_Typ_SDW\Volume 1\Main Directory\CRP-1.015.dgn
 WILE2054 AT DUS300019

- Work shown on this sheet is a summary of work for the installation of the fiber-optic cable and CCTV installations that are shown on the cable routing plans (i.e. CRP sheets). Work to be done for traffic signals is shown separately on the signal designs and the "Summary of Work by Intersection" sheets in Volume III of III.
- The items listed above are for informational purposes only and represent work that is necessary to complete the project and are not necessarily pay items. See Summary of Quantities and the Project Special Provisions for defined Pay Items for this contract.

ATKINS 1616 EAST MILLBROOK ROAD, SUITE 310
 RALEIGH, NORTH CAROLINA 27609
 (919) 876-8888 NCBEES #F-0326

Prepared for the Offices of:  Transportation 750 Greenfield Parkway, Garner, NC 27529		Asheville Signal System Summary of Work by Cable Routing Plans (sheet 16 of 30) Division 13 Buncombe County Asheville		SEAL  MELISSA B. TOTH ENGINEER 025892
PLAN DATE: December 2016 PREPARED BY: J A Wiles		REVIEWED BY: M B Toth DATE: 12/27/2016		
REVISIONS:		INIT. DATE:		
NTS		CAD FILE NAME: CRP-1.015.dgn		

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED