DocuSign Envelope ID: 18849B0B-D2D1-455B-8D9A-C02EBEE38C7D

PROJECT REFERENCE NO.	SHEET NO.
U-4715B	CRP-1.025

SUMMARY OF WORK BY CABLE ROUTING PLANS

CABLE ROUTING SHEET NUMBER	COMMUNICATIONS CABLE (24-FIBER)	COMMUNICATIONS CABLE (60-FIBER)	COMMUNICATIONS CABLE (96-FIBER)	DROP CABLE	HANDLASH & AERIAL CABLE PROTECTOR	SPLICE ENCLOSURE	MODIFY EXISTING SPLICE OR INTERCONNECT CENTER	INTERCONNECT CENTER	ETHERNET EDGE SWITCH	REMOVE EXISTING COMMUNICATIONS CABLE	REMOVE HUB CABINET	REMOVE CCTV CABINET	INSTALL CCTV CAMERA ASSEMBLY	REMOVE EX CCTV ASSEMBLY	CCTV CABINET	RADIO CABINET	CCTV WOOD POLE	WOOD POLE	ETHERNET CABLE (CAT 5E)
	LF	LF	LF	LF	LF	EA	EA	EA	EA	LF	EA	EA	EA	EA	EA	EA	EA	EA	LF
CRP-6.277	1,410	-	-	-	30	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.278	1,590	-	-	730	-	2	-	3	3	-	-	-	1	-	1	-	1	-	-
CRP-6.279	1,500	-	-	180	-	1	-	1	1	-	-	-	-	-	-	-	-	-	-
CRP-6.280	290	-	-	180	-	1	-	1	1	-	-	-	-	-	-	-	-	-	-
CRP-6.281	-	1,510	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.282	1,730	-	-	720	-	2	-	2	2	-	-	-	-	-	-	-	-	-	-
CRP-6.283	1,360	-	-	230	-	1	-	1	1	-	-	-	-	-	-	-	-	-	-
CRP-6.284	-	-	1,580	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.285	370	-	1,630	480	-	2	-	1	1	-	-	-	-	-	-	-	-	-	-
CRP-6.286	700	-	1,790	60	-	1	-	1	1	-	-	-	-	-	-	-	-	-	-
CRP-6.287	1,520	-	-	650	-	1	-	2	2	-	-	-	1	-	-	-	1	-	-
CRP-6.288	1,990	-	-	560	-	1	-	1	1	-	-	-	-	-	-	-	-	-	-
CRP-6.289	270	-	-	460	-	1	-	1	1	-	-	-	-	-	-	-	-	-	-
CRP-6.290	2,520	-	-	-	-	1	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.291	490	-	1,320	60	-	1	-	1	1	-	-	-	-	-	-	-	-	-	-
CRP-6.292	1,520	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.293	1,600	-	-	330	-	1	-	1	1	-	-	-	-	-	-	-	-	-	-
CRP-6.294	320	-	-	70	-	1	-	1	1	-	-	-	-	-	-	-	-	-	-
CRP-6.295	1,700	-	-	60	-	1	-	1	1	90	-	-	-	-	-	-	-	-	-
CRP-6.296	450	-	-	990	-	1	-	2	2	-	-	-	-	-	-	-	-	-	-
CRP-6.297	620	-	-	320	-	1	-	1	1	-	-	-	-	-	-	-	-	-	-
CRP-6.298	1,380	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.299	1,240	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.300	1,510	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.301	1,390	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.302	1,540	-	-	170	-	1	-	1	1	-	-	-	-	-	-	-	-	-	-
CRP-6.303	1,480	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.304	1,440	-	-	60	-	1	-	1	1	-	-	-	-	-	-	-	-	-	-
CRP-6.305	-	-	1,610	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.306	-	-	1,460	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.307	-	-	1,510	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.308	-	-	1,440	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.309	-	-	1,470	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.310	-	-	1,510	290	-	1	-	1	1	-	-	-	-	-	-	-	-	-	-
CRP-6.311	-	-	1,590	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

- Work shown on this sheet is a summary of work for the installation of the fiber-optic cable and CCTV installations that are shown on the cable routing plans (i.e. CRP sheets). Work to be done for traffic signals is shown separately on the signal designs and the "Summary of Work by Intersection" sheets in Volume III of III.
- The items listed above are for informational purposes only and represent work that is necessary to complete the project and are not necessarily pay items. See Summary of Quantites and the Project Special Provisions for defined Pay Items for this contract.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Prepared for the Offices of:
NC Transportation
750 Greenfield Parkway, Garner, NC 27529

ATKINS 1616 EAST MILLBROOK ROAD, SUITE 310 RALEIGH, NORTH CAROLINA 27609 (919) 876-6888 NCBEES #F-0326

Asheville Signal System
Summary of Work by Cable Routing Plans (sheet 26 of 30)
Division 13 Buncombe County Asheville

PLAN DATE: December 2016 REVIEWED BY: M B Toth
PREPARED BY: J A Wiles REVIEWED BY:

REVISIONS	INIT.	DATE

NTS

SEAL
NORTH CAROLINA PROFESSIONAL SEAL 025892 ENGINEER MELISSA B. TOTH

Designed by: Melissa B. Toth 12/22/2016
DATE
CADD Filename: CRP-1.025.dgn

22-DEC-2016 13:52
d:*Transportation\Traffic\Curr*100048632 U-4715B Asheville Sig Sys\Task 11_Typ_SD\Volume I\Main Directory\CRP-1.025.dgn
ericd5386 A: L USZ9321