PROJECT REFERENCE NO.	SHEET NO.
U-4715B	Sig. 259.3

EVENT SCHEDULING PROGRAMMING DETAIL

(program controller as shown below)

** THE TIMES MAY BE MODIFIED BY THE CITY OF ASHEVILLE

1. FROM MAIN MENU PRESS '2' (PHASE CONTROL). THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO OMIT PHASE AND SELECT PHASE 1.
2. BACKUP TO MAIN MENU BY PRESSING THE 'ESC' BUTTON ON KEYBOARD.
3. FROM MAIN MENU PRESS 'B' (SCHEDULING).

```
SCHEDULED EVENT #1       NOT ASSIGNED*
START DATE (MM/DD)............01/01
END DATE (MM/DD)..............12/31
START TIME (HH:MM)............16:00
STOP TIME (HH:MM)............18:00
DOW      |SUN MON TUE WED THR FRI SAT
ENABLED  |     X   X   X   X   X
EVENT GROUPS     |123456789101112131415 16
ASSIGNED         |

DELETE EVENT WHEN COMPLETED?........N
CONTINUOUS EVENT?...................N
INVERT EVENT?.......................Y
SELECT 1 EVENT TYPE:
EVENT GROUP (1-16)..................._
PLAN (65=FLSH,66=FREE)..._  OFFSET#.._
PLAN PRIORTY:  LOW.._ MED_..  HIGH.._
CAHNGE PHASE SEQUENCE PAGE (1-12)...._
CHANGE PHASE TIMING PAGE (1-4)......._
CHANGE PHASE CONTROL PAGE (1-4)....._
CHANGE OVERLAP CONTROL PAGE (1-4)...._
.
.
.
OVERIDE PHASE CONTROL FUNCTIONS?....Y
```

→ THIS WILL INVERT/ DISABLE THE PHASE #1 OMIT SELECTED BELOW. IN EFFECT THE PHASE OMIT IS OVERRIDEN DURING THE HOURS/ DAYS SELECTED.

→ WHEN A 'Y' IS ENTERED FOR 'OVERRIDE PHASE CONTROL FUNCTION?' YOU WILL BE PROMPTED TO 'SELECT PHASES FROM 1 CONTROL FUNCTION. SELECT PHASE #1 FOR OMIT PHASE.

EVENT SCHEDULING IS COMPLETE

* AFTER PROGRAMMING THIS SPACE WILL READ 'OMIT PHASE.'

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: COA-0110
DESIGNED: JUNE 2016
SEALED: 12-13-2016
REVISED:

Mattern & Craig
SINCE 1978
CONSULTING ENGINEERS • SURVEYORS
FIRM LICENSE No. C-1154
12 BROAD STREET
ASHEVILLE, NORTH CAROLINA 28801
(828) 254-2201
FAX (828) 254-4562

ELECTRICAL DETAIL SHEET 3 OF 3

ELECTRICAL AND PROGRAMMING DETAILS FOR:

Prepared for the Offices of:

CITY OF ASHEVILLE NORTH CAROLINA

161 S.Charlotte St.Asheville NC 28802

Patton Ave
at
Otis St

Division 13 | Buncombe County | Asheville

PLAN DATE:	OCT 2016	REVIEWED BY:	SMH
PREPARED BY:	BGR	REVIEWED BY:	JBV

REVISIONS	INIT.	DATE

SEAL
NORTH CAROLINA PROFESSIONAL SEAL 022599 ENGINEER JAMES B. VOSO

DocuSigned by: James Voso 140FD60376ED41F...
12/13/2016
SIGNATURE | DATE

SIG. INVENTORY NO. COA-0110

1:09:57 PM
R:\4602 Asheville Signal System\DGN\COA-0110\COA-0110_elec_dsn.dgn
bgrass