PROJECT NO.	SHEET NO.	TOTAL NO.
2017CPT.12.18.10231,	11	
2017CPT.12.18.20231		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	AGGREGATE SHOULDER BORROW TON	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1½" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	LEVELING COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	LEVELING COURSE, S9.5C TONS	SURFACE COURSE, SF9.5A TONS	LEVELING COURSE, SF9.5A TON	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	RETROFIT EXISTING CURB RAMP (STD. 848.06) EA	CONCRETE CURB RAMPS EA	ADJ. OF DROP INLET EA	ADJ. OF MANHOLES EA	ADJ. OF METER OR VALVE BOX EA	PORTABLE LIGHTING LS	JUNCTION BOX (STANDARD SIZE) EA	INDUCTIVE LOOP SAWCUT LF	LEAD-IN CABLE (14-2) LF
2017CPT.12.18.10231	Cleveland	1	US 74 (W DIXON BLVD)	SR 2049 + 1.244 MILES (MM 12.505) TO SR 1152 + 0.3 MILE (MM 19.808)	1 2 3 4 5 6	4	MD	NO	NO	2.58 0.25 0.06 0.38 0.12 3.91	VAR. 58-100 VAR. 58-96 VAR.58-93 VAR. 58-80 VAR. 58-98 VAR. 58-102	2,737	500	15.64	142,520	5,280				26,061	1,520			1,636	2,930			10	14	13	1	2	8,400	500
TOTAL FOR MAP NO. 1										**7.3**		**2,737**	**500**	**15.64**	**142,520**	**5,280**				**26,061**	**1,520**			**1,636**	**2,930**			**10**	**14**	**13**	**1**	**2**	**8,400**	**500**
TOTAL FOR PROJ NO. 2017CPT.12.18.10231										**7.3**		**2,737**	**500**	**15.64**	**142,520**	**5,280**				**26,061**	**1,520**			**1,636**	**2,930**			**10**	**14**	**13**	**1**	**2**	**8,400**	**500**
2017CPT.12.18.20231	Cleveland	2	SR 1001	NC 150 TO SR 2159	7 13	2	2WD	NO	NO	0.43 4.10	VAR. 34-36 VAR. 23-25	1,435	984	8.20	9,713	480	3,362	6,298	1,104					598	1,575								250	50
TOTAL FOR MAP NO. 2										**4.53**		**1,435**	**984**	**8.20**	**9,713**	**480**	**3,362**	**6,298**	**1,104**					**598**	**1,575**								**250**	**50**
2017CPT.12.18.20231	Cleveland	3	SR 1003	NC 150 TO RUTHERFORD CL	8 9 10	2	2WD	NO	NO	0.12 0.58 4.70	VAR. 36-46 VAR. 32-36 VAR. 20-25	1,645	290	9.40	15,408	1,284		6,623	530					432	2,120	30	1		23	10			250	50
TOTAL FOR MAP NO. 3										**5.4**		**1,645**	**290**	**9.40**	**15,408**	**1,284**		**6,623**	**530**					**432**	**2,120**	**30**	**1**		**23**	**10**			**250**	**50**
2017CPT.12.18.20231	Cleveland	4	SR 1572	NC 182 TO DE	11	2	2WD	NO	NO	0.23	18											148		10	9									
TOTAL FOR MAP NO. 4										**0.23**												**148**		**10**	**9**									
2017CPT.12.18.20231	Cleveland	5	SR 1629	SR 1632 TO END PVMT	11	2	2WD	NO	NO	0.22	18											141		9	14									
TOTAL FOR MAP NO. 5										**0.22**												**141**		**9**	**14**									
2017CPT.12.18.20231	Cleveland	6	SR 1666	SR 1004 TO DE	11	2	2WD	NO	NO	0.8	18											513		34	51									
TOTAL FOR MAP NO. 6										**0.8**												**513**		**34**	**51**									
2017CPT.12.18.20231	Cleveland	7	SR 1681	SR 1632 TO DE	11	2	2WD	NO	NO	0.23	18											148		10	14									
TOTAL FOR MAP NO. 7										**0.23**												**148**		**10**	**14**									
2017CPT.12.18.20231	Cleveland	8	SR 1814	NC 182 TO SR 1813	11	2	2WD	NO	NO	1.1	18											706		47	70									
TOTAL FOR MAP NO. 8										**1.1**												**706**		**47**	**70**									
2017CPT.12.18.20231	Cleveland	9	SR 1815	SR 1814 TO DE	11	2	2WD	NO	NO	0.29	18											186		12	18									
TOTAL FOR MAP NO. 9										**0.29**												**186**		**12**	**18**									
2017CPT.12.18.20231	Cleveland	10	SR 1849	SR 1814 TO SR 1814	11	2	2WD	NO	NO	0.37	20											264		18	27									
TOTAL FOR MAP NO. 10										**0.37**												**264**		**18**	**27**									
2017CPT.12.18.20231	Cleveland	11	SR 1850	SR 1337 TO SR 1005	10	2	2WD	NO	NO	3.61	22	1,264		7.22		890		4,330	522					294	780				2	2				
TOTAL FOR MAP NO. 11										**3.61**		**1,264**		**7.22**		**890**		**4,330**	**522**					**294**	**780**				**2**	**2**				
2017CPT.12.18.20231	Cleveland	12	SR 1884	NC 182 TO DE	11	2	2WD	NO	NO	0.17	18											109		7	5									
TOTAL FOR MAP NO. 12										**0.17**												**109**		**7**	**5**									
2017CPT.12.18.20231	Cleveland	13	SR 1886	SR 1858 TO DE	11	2	2WD	NO	NO	0.13	20											93		6	11									
TOTAL FOR MAP NO. 13										**0.13**												**93**		**6**	**11**									
2017CPT.12.18.20231	Cleveland	14	SR 2037	SR 2604 TO END PVMT	11	2	2WD	NO	NO	0.13	18											83		6	7									
TOTAL FOR MAP NO. 14										**0.13**												**83**		**6**	**7**									
2017CPT.12.18.20231	Cleveland	15	SR 2080	SR 2603 TO END MAINT	11	2	2WD	NO	NO	0.7	18											449		30	45									
TOTAL FOR MAP NO. 15										**0.7**												**449**		**30**	**45**									
2017CPT.12.18.20231	Cleveland	16	SR 2122	SR 1001 TO DE	11	2	2WD	NO	NO	0.34	18											218		15										
TOTAL FOR MAP NO. 16										**0.34**												**218**		**15**										
2017CPT.12.18.20231	Cleveland	17	SR 2264	SR 2269 TO SR 2271	11	2	2WD	NO	NO	0.33	20											235		16	10									
TOTAL FOR MAP NO. 17										**0.33**												**235**		**16**	**10**									
2017CPT.12.18.20231	Cleveland	18	SR 2265	SR 2268 TO SR 2269	11	2	2WD	NO	NO	0.19	20											135		9	15									
TOTAL FOR MAP NO. 18										**0.19**												**135**		**9**	**15**									
2017CPT.12.18.20231	Cleveland	19	SR 2266	SR 2263 TO SR 2267	11	2	2WD	NO	NO	0.25	20											178		12	29									
TOTAL FOR MAP NO. 19										**0.25**												**178**		**12**	**29**									
2017CPT.12.18.20231	Cleveland	20	SR 2267	SR 2266 TO DE	11	2	2WD	NO	NO	0.19	18											122		8	20									
TOTAL FOR MAP NO. 20										**0.19**												**122**		**8**	**20**									
2017CPT.12.18.20231	Cleveland	21	SR 2268	SR 2263 TO SR 2267	11	2	2WD	NO	NO	0.25	20											178		12	14									
TOTAL FOR MAP NO. 21										**0.25**												**178**		**12**	**14**									
2017CPT.12.18.20231	Cleveland	22	SR 2269	SR 2263 TO SR 2265	11	2	2WD	NO	NO	0.17	18											109		7	10									
TOTAL FOR MAP NO. 22										**0.17**												**109**		**7**	**10**									
2017CPT.12.18.20231	Cleveland	23	SR 2270	SR 2268 TO SR 2271	11	2	2WD	NO	NO	0.12	20											86		6	7									
TOTAL FOR MAP NO. 23										**0.12**												**86**		**6**	**7**									
2017CPT.12.18.20231	Cleveland	24	SR 2271	SR 2264 TO SR 2270	11	2	2WD	NO	NO	0.08	20											57		4	6									
TOTAL FOR MAP NO. 24										**0.08**												**57**		**4**	**6**									
2017CPT.12.18.20231	Cleveland	25	SR 2272	SR 2268 TO DE	11	2	2WD	NO	NO	0.1	20											71		5	9									
TOTAL FOR MAP NO. 25										**0.1**												**71**		**5**	**9**									
2017CPT.12.18.20231	Cleveland	26	SR 2338	NC 226 TO SR 2348	11	2	2WD	NO	NO	0.35	20											227		15	23									
TOTAL FOR MAP NO. 26										**0.35**												**227**		**15**	**23**									
2017CPT.12.18.20231	Cleveland	27	SR 2346	SR 2283 TO DE	11	2	2WD	NO	NO	0.1	24											85		6	9									
TOTAL FOR MAP NO. 27										**0.1**												**85**		**6**	**9**									
2017CPT.12.18.20231	Cleveland	28	SR 2348	SR 2338 TO SR 2338	11	2	2WD	NO	NO	0.2	20											143		10	15									
TOTAL FOR MAP NO. 28										**0.2**												**143**		**10**	**15**									
2017CPT.12.18.20231	Cleveland	29	SR 2367	NC 180 TO CDS	11	2	2WD	NO	NO	0.14	20											136		9	6									
TOTAL FOR MAP NO. 29										**0.14**												**136**		**9**	**6**									
2017CPT.12.18.20231	Cleveland	30	SR 2368	DE TO DE	11	2	2WD	NO	NO	0.19	20											135		9	7									
TOTAL FOR MAP NO. 30										**0.19**												**135**		**9**	**7**									
2017CPT.12.18.20231	Cleveland	31	SR 2383	SR 2245 TO DE	11	2	2WD	NO	NO	0.09	20											64	15	5	19									
TOTAL FOR MAP NO. 31										**0.09**												**64**	**15**	**5**	**19**									
2017CPT.12.18.20231	Cleveland	32	SR 2423	NC 180 TO SR 2424	11	2	2WD	NO	NO	0.5	20											356		24	54									
TOTAL FOR MAP NO. 32										**0.5**												**356**		**24**	**54**									
2017CPT.12.18.20231	Cleveland	33	SR 2424	SR 2423 TO CDS	11	2	2WD	NO	NO	0.19	20											152		10	21									
TOTAL FOR MAP NO. 33										**0.19**												**152**		**10**	**21**									
2017CPT.12.18.20231	Cleveland	34	SR 2425	NC 180 TO SR 2424	11	2	2WD	NO	NO	0.51	20											364		24	29									
TOTAL FOR MAP NO. 34										**0.51**												**364**		**24**	**29**									
2017CPT.12.18.20231	Cleveland	35	SR 2426	NC 180 TO DE	12	2	2WD	NO	NO	0.1	25											89		6	13									
TOTAL FOR MAP NO. 35										**0.1**												**89**		**6**	**13**									
2017CPT.12.18.20231	Cleveland	36	SR 2446	SR 2246 TO SR 2447	11	2	2WD	NO	NO	0.19	20											135	7	9	21									
TOTAL FOR MAP NO. 36										**0.19**												**135**	**7**	**9**	**21**									
2017CPT.12.18.20231	Cleveland	37	SR 2447	SR 2446 TO SR 2246	11	2	2WD	NO	NO	0.23	20											164	38	13	51									
TOTAL FOR MAP NO. 37										**0.23**												**164**	**38**	**13**	**51**									
2017CPT.12.18.20231	Cleveland	38	SR 2461	SR 2249 TO CDS	11	2	2WD	NO	NO	0.09	18											74	13	6	18									
TOTAL FOR MAP NO. 38										**0.09**												**74**	**13**	**6**	**18**									
2017CPT.12.18.20231	Cleveland	39	SR 2603	SR 1001 TO DE	11	2	2WD	NO	NO	0.84	24											718		48	72									
TOTAL FOR MAP NO. 39										**0.84**												**718**		**48**	**72**									
2017CPT.12.18.20231	Cleveland	40	SR 2617	SR 1001 TO CDS	11	2	2WD	NO	NO	0.33	20											246		16	17									
TOTAL FOR MAP NO. 40										**0.33**												**246**		**16**	**17**									
2017CPT.12.18.20231	Cleveland	41	SR 2621	SR 2617 TO CDS	11	2	2WD	NO	NO	0.08	20											68		5										
TOTAL FOR MAP NO. 41										**0.08**												**68**		**5**										
2017CPT.12.18.20231	Cleveland	42	SR 2631	SR 2617 TO CDS	11	2	2WD	NO	NO	0.07	18											56		4	2									
TOTAL FOR MAP NO. 42										**0.07**												**56**		**4**	**2**									
2017CPT.12.18.20231	Cleveland	43	SR 2663	SR 2604 TO CDS	11	2	2WD	NO	NO	0.2	20											154		10	21									
TOTAL FOR MAP NO. 43										**0.2**												**154**		**10**	**21**									
2017CPT.12.18.20231	Cleveland	44	SR 2664	SR 2604 TO CDS	11	2	2WD	NO	NO	0.2	20											143		10	6									
TOTAL FOR MAP NO. 44										**0.2**												**143**		**10**	**6**									
TOTAL FOR PROJ NO. 2017CPT.12.18.20231										**24.53**		**4,344**	**1,274**	**24.82**	**25,121**	**2,654**	**3,362**	**17,251**	**2,156**			**7,738**	**73**	**1,846**	**5,270**	**30**	**1**		**25**	**12**			**500**	**100**
GRAND TOTAL										**31.83**		**7,081**	**1,774**	**40.46**	**167,641**	**7,934**	**3,362**	**17,251**	**2,156**	**26,061**	**1,520**	**7,738**	**73**	**3,482**	**8,200**	**30**	**1**	**10**	**39**	**25**	**1**	**2**	**8,900**	**600**