

REFORESTATION

□ TREE REFORESTATION SHALL JE PLANTED 6 FT. TO 10 FT. ON CENTER, RANDOM SPACING, AVERAGING 8 FT. ON CENTER, APPROXIMATELY 680 PLANTS PER ACRE.

REFORESTATION MIXTURE, TYPE, SIZE, AND FURNISH SHALL

25% QUERCUS RUJRA

- 25% LIRIODENDRON TULIPIFERA
- 25% PINUS TAEDA
- 25% QUERCUS PHELLOS

PROJECT REFERENCE NO.		SHEET NO.
1-5000		RF-I
R/W SHEET NO).	
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER

NORTHERN RED OAK 12 in - 18 in JR YELLOW POPLAR 12 in - 18 in JR LOJLOLLY PINE 12 in - 18 in JR WILLOW OAK 12 in - 18 in JR	CONFORM TO THE FOLLOWING:			
LO3LOLLY PINE12 in - 18 in 3R	NORTHERN RED OAK	12 in – 18 in <i>J</i> R		
	YELLOW POPLAR	12 in – 18 in 3 R		
WILLOW OAK 12 in – 18 in JR	LOJLOLLY PINE	12 in – 18 in J R		
	WILLOW OAK	12 in – 18 in 3 R		

REFORESTATION DETAIL SHEET

N.C.D.O.T. - ROADSIDE ENVIRONMENTAL UNIT