## NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station	Uncl. Exc.	Embt
L	(cu. yd.)	(cu. yd.)
12+00.00	0	0
12+50.00	34	6
13+00.00	33	8
13+50.00	26	10
14+00.00	13	19
14+50.00	3	31
15+00.00	0	78
15+50.00	0	186
15+72.81 (BR)	0	128

Station	Uncl. Exc.	Embt	
L	(cu. yd.)	(cu. yd.)	
16+95.19 (BR)	0	0	
17+00.00	0	20	
17+50.00	87	177	
18+00.00	232	125	
18+50.00	281	64	
19+00.00	224	30	
19+50.00	181	19	
20+00.00	169	9	
20+50.00	117	7	
21+00.00	56	5	

SIONS

## STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

**CROSS-SECTION SUMMARY** 

-		
	PROJ. REFERENCE NO.	SHEET NO.
	B-5166	X-1A
		-

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION,FINE GRADING, CLEARING AND GRUBBING,AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING"