PROJ. REFERENCE NO.	SHEET NO.
W-5520	X-1C

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L3 CL	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut Exc. (cu. yd.)
310+50.00	37	1	0
311+00.00	39	0	0
311+50.00	44	0	0
312+00.00	43	0	0
312+50.00	72	0	0
313+00.00	109	0	0
313+50.00	117	0	0
314+00.00	114	0	0
314+50.00	108	0	0
315+00.00	109	0	0
315+50.00	90	0	0
316+00.00	49	0	0
316+50.00	31	0	0
317+00.00	35	0	0
317+50.00	31	6	0
318+00.00	28	8	0
318+50.00	28	11	0
319+00.00	26	19	0
319+50.00	27	19	0
320+00.00	29	18	0
320+50.00	32	15	0
321+00.00	34	14	0
321+50.00	29	25	0
322+00.00	30	24	0
322+50.00	37	12	0
323+00.00	40	9	0
323+50.00	38	6	0
324+00.00	39	5	0
324+50.00	43	5	0
325+00.00	41	9	0
325+50.00	30	19	0
326+00.00	25	19	0
326+50.00	32	14	0

Station L4 LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut Exc. (cu. yd.)
426+00.00	0	0	0
426+50.00	3	8	0
427+00.00	11	16	0
427+50.00	16	32	0
428+00.00	15	78	0
428+50.00	18	172	0
429+00.00	25	207	0
429+50.00	14	128	0
429+65.00	0	12	0

Station L4 RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut Exc. (cu. yd.)
408+40.00	0	0	0
408+50.00	9	0	0
409+00.00	110	0	0
409+50.00	92	21	0
410+00.00	42	22	0
410+50.00	35	1	0
411+00.00	49	0	0
411+50.00	41	0	0
412+00.00	18	0	0

Station L4 CL	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut Exc. (cu. yd.)
401+20.00	0	0	0
401+50.00	16	0	0
402+00.00	51	0	0
402+50.00	48	0	0
403+00.00	42	0	0
403+50.00	39	0	0
404+00.00	39	0	0
404+50.00	35	1	0
405+00.00	34	1	0
405+50.00	39	0	0
406+00.00	36	0	0
406+50.00	32	1	0
407+00.00	29	4	0
407+50.00	28	11	0
408+00.00	26	16	0
408+50.00	27	16	0
409+00.00	32	13	0
409+50.00	34	6	0
410+00.00	38	2	0
410+50.00	41	2	0
411+00.00	35	11	0
411+50.00	36	14	0
412+00.00	44	6	0
412+50.00	47	2	0
413+00.00	51	0	0
413+50.00	54	0	0
414+00.00	50	0	0
414+50.00	39	0	0
415+00.00	40	0	0
415+50.00	45	0	0
416+00.00	43	0	0
416+50.00	40	0	0
417+00.00	38	0	0
417+50.00	33	0	0
418+00.00	38	0	0
418+50.00	78	0	0
419+00.00	0	0	0
419+50.00	30	0	0
420+00.00	43	0	0
420+50.00	28	0	0
421+00.00	33	0	0
421+50.00	38	0	0
422+00.00	43	0	0
422+50.00	50	0	0
423+00.00	60	4	0
423+50.00	59	9	0
424+00.00	60	5	0
424+50.00	64	0	0
425+00.00	60	0	0
425+50.00	57	1	0
426+00.00	52	2	0
426+50.00	47	2	0
427+00.00	44	4	0
427+50.00	42	7	0
428+00.00	35	14	0
428+50.00	37	11	0
429+00.00	46	4	0
429+50.00	23	2	0

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut Exc. (cu. yd.)
11+00.00	0	0	0
11+50.00	35	6	0
12+00.00	37	1	0
12+50.00	58	1	0
13+00.00	66	2	0
13+50.00	46	5	0
14+00.00	56	3	0
14+50.00	66	3	0
15+00.00	55	3	0
15+25.00	0	0	0

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut Exc. (cu. yd.)
12+50.00	0	0	0
13+00.00	0	0	0
13+50.00	0	0	0
14+00.00	21	1	0
14+50.00	35	4	0