F.A. PROJECT NO.: STP-0119(9)

NOTES

ASSUMED LIVE LOAD ------HL-93 OR ALTERNATE LOADING.

DESIGN FILL----- 6.42'

FOR OTHER DESIGN DATA AND NOTES, SEE STANDARD NOTE SHEET.

3"Ø WEEP HOLES INDICATED TO BE IN ACCORDANCE WITH THE SPECIFICATIONS.

CONCRETE IN CULVERTS TO BE POURED IN THE FOLLOWING ORDER:

- 1. WING FOOTINGS AND FLOOR SLAB INCLUDING 4" OF ALL VERTICAL WALLS.
- 2. THE REMAINING PORTIONS OF THE WALLS AND WINGS FULL HEIGHT FOLLOWED BY ROOF SLAB AND HEADWALLS.

THE RESIDENT ENGINEER SHALL CHECK THE LENGTH OF CULVERT BEFORE STAKING IT OUT TO MAKE CERTAIN THAT IT WILL PROPERLY TAKE CARE OF THE FILL.

DIMENSIONS FOR WING LAYOUT AS WELL AS ADDITIONAL REINFORCING STEEL EMBEDDED IN BARREL ARE SHOWN ON WING SHEET.

TRANSVERSE CONSTRUCTION JOINTS SHALL BE USED IN THE BARREL, SPACED TO LIMIT THE POURS TO A MAXIMUM OF 70 FT. LOCATION OF JOINTS SHALL BE SUBJECT TO APPROVAL OF THE ENGINEER.

AT THE CONTRACTOR'S OPTION, HE MAY SPLICE THE VERTICAL REINFORCING STEEL IN THE INTERIOR FACE OF EXTERIOR WALL ABOVE LOWER WALL CONSTRUCTION JOINT. THE SPLICE LENGTH SHALL BE AS PROVIDED IN THE SPLICE LENGTH CHART SHOWN ON THE PLANS. EXTRA WEIGHT OF STEEL DUE TO THE SPLICES SHALL BE PAID FOR BY THE CONTRACTOR.

AT THE CONTRACTOR'S OPTION HE MAY SUBMIT, TO THE ENGINEER FOR APPROVAL, DESIGN AND DETAIL DRAWINGS FOR A PRECAST REINFORCED CONCRETE BOX CULVERT IN LIEU OF THE CAST-IN-PLACE CULVERT SHOWN ON THE PLANS. THE DESIGN SHALL PROVIDE THE SAME SIZE OF BARREL AS USED ON THE CAST-IN-PLACE DESIGN. FOR OPTIONAL PRECAST REINFORCED CONCRETE BOX CULVERT. SEE SPECIAL PROVISIONS.

STEEL IN THE BOTTOM SLAB MAY BE SPLICED AT THE PERMITTED CONSTRUCTION JOINT AT THE CONTRACTOR'S OPTION. EXTRA WEIGHT OF STEEL DUE TO THE SPLICES WILL BE PAID FOR BY THE CONTRACTOR.

THE CONTRACTOR SHALL PROVIDE INDEPENDENT ASSURANCE SAMPLES OF REINFORCING STEEL AS FOLLOWS: FOR PROJECTS REQUIRING UP TO 400 TONS OF REINFORCING STEEL, ONE 30 INCH SAMPLE OF EACH SIZE BAR USED, AND FOR PROJECTS REQUIRING OVER 400 TONS OF REINFORCING STEEL, TWO 30 INCH SAMPLES OF EACH SIZE BAR USED. THE BARS FROM WHICH THE SAMPLES ARE TAKEN MUST THEN BE SPLICED WITH REPLACEMENT BARS OF THE SIZE AND LENGTH OF THE SAMPLE, PLUS A MINIMUM LAP SPLICE OF THIRTY BAR DIAMETERS. PAYMENT FOR THE SAMPLES OF REINFORCING STEEL SHALL BE CONSIDERED INCIDENTAL TO VARIOUS PAY ITEMS.

A 3 FOOT STRIP OF FILTER FABRIC SHALL BE ATTACHED TO THE FILL FACE OF THE WING COVERING THE ENTIRE LENGTH OF THE EXPANSION JOINT.

FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.

FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.

FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.

FOR CULVERT DIVERSION DETAILS AND PAY ITEM. SEE EROSION CONTROL PLANS.

FOR CONSTRUCTION SEQUENCE. SEE EROSION CONTROL PLANS.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

NATIVE MATERIAL CONSISTS OF MATERIAL THAT IS EXCAVATED FROM THE STREAM OR FLOOD PLAIN AT THE PROJECT SITE DURING CONSTRUCTION. RIP RAP MAY BE USED TO SUPPLEMENT THE NATIVE MATERIAL IN THE HIGH FLOW CULVERT BARREL(S). IF RIP RAP IS USED TO LINE THE HIGH FLOW CULVERT BARREL(S), NATIVE MATERIAL SHOULD BE PLACED ON TOP TO FILL VOIDS AND PROVIDE A FLAT SURFACE FOR ANIMAL PASSAGE. NATIVE MATERIAL IS SUBJECT TO APPROVAL BY THE ENGINEER AND MAY BE SUBJECT TO PERMIT CONDITIONS.

DO NOT SET ELEVATION OF HIGH SILL ABOVE BANK FULL.

TOTAL STRUCTURE QUANTITIES

CLASS A CONCRETE				
BARREL @	3.378	CY/FT	573.4	_ C.Y.
WINGS, ETC			46.5	_ C.Y.
SILLS			1.6	_ C.Y.
	TOTAL		621.5	_ C.Y.
REINFORCING STEEL				
BARREL			71,561	_LBS.

2,516 LBS. WINGS, ETC. 74,077 LBS. TOTAL 475 TONS


FOUNDATION CONDITIONING MATERIAL LUMP SUM CULVERT EXCAVATION

HYDRAULIC DATA

DESIGN DISCHARGE = 1420 CFS FREQUENCY OF DESIGN FLOOD = 50 YRS. DESIGN HIGH WATER ELEVATION = 582.40 DRAINAGE AREA = 2.08 SQ.MI. BASE DISCHARGE (Q100) = 1700 CFS BASE HIGH WATER ELEVATION = 583.39

OVERTOPPING FLOOD DATA

OVERTOPPING DISCHARGE = 2570 + CFS FREQUENCY OF OVERTOPPING FLOOD = 500+ YRS. OVERTOPPING FLOOD ELEVATION = 586.80 * * OVERTOPS PROPOSED ROADWAY AT STA. 98+00 -L-



WOODS

PROPOSED TRIPLE

PROPOSED GUARDRAIL

(ROADWAY DETAIL &

PAY ITEM)

WOODS

FOR UTILITY INFORMATION,

SPECIAL PROVISIONS.

SEE UTILITY PLANS AND

11' X 9' RCBC

130°-00'-00"

BENCH MARK #6: RAILROAD SPIKE IN BASE OF 18"POPLAR, 208' LEFT STA 103+58, EL. 593.11

— STA. 96+88.00 -L⋅

LOCATION SKETCH

WOODS

WOODS

ASSEMBLED BY: A. SORSENGINH DATE: 4/2014 CHECKED BY: S.B. WILLIAMS DATE: 4/2014

A. SORSENGINH DATE: 4/2014

DESIGN ENGINEER OF RECORD:

CLASS I

RIP RAP

(ROADWAY PAY

ITEM) (TYP.)

GRADE DATA

GRADE POINT ELEVATION @ STA. 96+88.00 -L-= 587.39' BED ELEVATION @ STA. 96+88.00 -L-= 571.43'

ROADWAY FILL SLOPES

SEAL 29441 NOINEER

= 2:1

the Z. W. aford

3/16/2017

DOCUMENT NOT CONSIDERED FINAL

UNLESS ALL SIGNATURES COMPLETED

PROJECT NO. U-3109A ALAMANCE COUNTY STATION: 96+88.00 -L-

SHEET 1 OF 5 CULVERT NO. 437 STATE OF NORTH CAROLINA

DEPARTMENT OF TRANSPORTATION

TRIPLE 11 FT. X 9 FT. CONCRETE BOX CULVERT 130° SKEW

SHEET NO. REVISIONS C1-1 O. BY: DATE: DATE:

STD. NO. CB443A