

REFERENCE: U-3109A

PROJECT: 34900

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

COUNTY ALAMANCE
PROJECT DESCRIPTION DUAL BRIDGES ON -L-
(FUTURE NC 119) OVER SR 1963 (HOLT STREET),
NCRR/NSRR, AND -Y16- (US 70)

CONTENTS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	LEGEND
3	SITE PLAN
4-5	PROFILES
6-8	CROSS SECTIONS
9-20	BORE LOGS
21	SITE PHOTOGRAPHS

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	U-3109A	1	21

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

- NOTES:
1. THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
 2. BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

W. WHICHARD

E. ESTEP

R. TOOTHMAN

W. TRAPP

INVESTIGATED BY D. GOODNIGHT

DRAWN BY T. WELLS

CHECKED BY X. BARRETT

SUBMITTED BY KLEINFELDER


DATE MARCH 2015





DocuSigned by:
Thomas R Wells 4/7/2015
SIGNATURE DATE


**NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SUBSURFACE INVESTIGATION
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS**

SOIL DESCRIPTION										GRADATION										ROCK DESCRIPTION										TERMS AND DEFINITIONS																																							
SOIL IS CONSIDERED UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO THE STANDARD PENETRATION TEST (AASHTO T 209, ASTM D1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY INCLUDE THE FOLLOWING: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. FOR EXAMPLE, VERY STIFF, GRAY, SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6																																								WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORMLY GRADED - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLE SIZES OF TWO OR MORE SIZES.										HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT REFUSAL IF TESTED, AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS IN NON-COASTAL PLAIN MATERIAL. THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:										ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, SUCH AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS, MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (ROD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. STRATA CORE RECOVERY (SREC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SROD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.									
SOIL LEGEND AND AASHTO CLASSIFICATION										ANGULARITY OF GRAINS										WEATHERED ROCK (WR)										CRYSTALLINE ROCK (CR)										NON-CRYSTALLINE ROCK (NCR)										COASTAL PLAIN SEDIMENTARY ROCK (CP)																			
GENERAL CLASS. GRANULAR MATERIALS (<= 35% PASSING #200) SILT-CLAY MATERIALS (> 35% PASSING #200) ORGANIC MATERIALS										THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS: ANGULAR, SUBANGULAR, SUBROUNDED, OR ROUNDED.										FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC.										FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC.										COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.																													
MINERALOGICAL COMPOSITION										COMPRESSION										WEATHERING										GROUND WATER																																							
MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHEN THEY ARE CONSIDERED OF SIGNIFICANCE.										SLIGHTLY COMPRESSIBLE LL < 31 MODERATELY COMPRESSIBLE LL = 31 - 50 HIGHLY COMPRESSIBLE LL > 50										FRESH ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING. ROCK RINGS UNDER HAMMER IF CRYSTALLINE. VERY SLIGHT (V SL.) ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN. CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE. SLIGHT (SL.) ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS. MODERATE (MOD.) SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK. MODERATELY SEVERE (MOD. SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. IF TESTED, WOULD YIELD SPT REFUSAL SEVERE (SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. IF TESTED, WOULD YIELD SPT N VALUES > 100 BPF VERY SEVERE (V SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE THAT ONLY MINOR VESTIGES OF ORIGINAL ROCK FABRIC REMAIN. IF TESTED, WOULD YIELD SPT N VALUES < 100 BPF COMPLETE ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. FABRIC MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.										PERCENTAGE OF MATERIAL ORGANIC MATERIAL GRANULAR SOILS SILT - CLAY SOILS OTHER MATERIAL TRACE OF ORGANIC MATTER 2 - 3% 3 - 5% TRACE 1 - 10% LITTLE ORGANIC MATTER 3 - 5% 5 - 12% LITTLE 10 - 20% MODERATELY ORGANIC 5 - 10% 12 - 20% SOME 20 - 35% HIGHLY ORGANIC > 10% > 20% HIGHLY 35% AND ABOVE										ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS. SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK. ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. IF TESTED, WOULD YIELD SPT REFUSAL ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. IF TESTED, WOULD YIELD SPT N VALUES > 100 BPF ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE THAT ONLY MINOR VESTIGES OF ORIGINAL ROCK FABRIC REMAIN. IF TESTED, WOULD YIELD SPT N VALUES < 100 BPF ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. FABRIC MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.										WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING STATIC WATER LEVEL AFTER 24 HOURS PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA SPRING OR SEEP																			
CONSISTENCY OR DENSENESS										MISCELLANEOUS SYMBOLS										RECOMMENDATION SYMBOLS										ABBREVIATIONS																																							
PRIMARY SOIL TYPE COMPACTNESS OR CONSISTENCY RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE) RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)										ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION SOIL SYMBOL ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT INFERRED SOIL BOUNDARY INFERRED ROCK LINE ALLUVIAL SOIL BOUNDARY										DIP & DIP DIRECTION OF ROCK STRUCTURES SPT TEST BORING AUGER BORING CORE BORING MONITORING WELL PIEZOMETER INSTALLATION										UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK UNCLASSIFIED EXCAVATION - ACCEPTABLE BUT NOT TO BE USED IN THE TOP 3 FEET OF EMBANKMENT OR BACKFILL										AR - AUGER REFUSAL BT - BORING TERMINATED CL - CLAY CPT - COARSE PENETRATION TEST CSE - COARSE DMT - DILATOMETER TEST DPT - DYNAMIC PENETRATION TEST e - VOID RATIO F - FINE FOSS. - FOSSILIFEROUS FRAC. - FRACTURED, FRACTURES FRAGS. - FRAGMENTS HI. - HIGHLY MED. - MEDIUM MICA. - MICACEOUS MOD. - MODERATELY NP - NON PLASTIC ORG. - ORGANIC PMT - PRESSUREMETER TEST SAP. - SAPROLITIC SD. - SAND, SANDY SL. - SILT, SILTY SLI. - SLIGHTLY TCR - TRICONE REFUSAL w - MOISTURE CONTENT V - VERY VST - VANE SHEAR TEST WEA. - WEATHERED % - UNIT WEIGHT %g - DRY UNIT WEIGHT SAMPLE ABBREVIATIONS S - BULK SS - SPLIT SPOON ST - SHELBY TUBE RS - ROCK RT - RECOMPACTED TRIAXIAL CBR - CALIFORNIA BEARING RATIO																													
TEXTURE OR GRAIN SIZE										SOIL MOISTURE - CORRELATION OF TERMS										FRACTURE SPACING										BEDDING																																							
U.S. STD. SIEVE SIZE OPENING (MM) 4 10 40 60 200 270 4.76 2.00 0.42 0.25 0.075 0.053										SOIL MOISTURE SCALE (ATTERBERG LIMITS) FIELD MOISTURE DESCRIPTION GUIDE FOR FIELD MOISTURE DESCRIPTION LL - LIQUID LIMIT PL - PLASTIC LIMIT OM - OPTIMUM MOISTURE SHRINKAGE LIMIT - SATURATED - (SAT.) USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE - WET - (W) SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE - MOIST - (M) SOLID; AT OR NEAR OPTIMUM MOISTURE - DRY - (D) REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE										VERY HARD CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK. HARD CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN. MODERATELY HARD CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS. MEDIUM HARD CAN BE GROUDED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK. SOFT CAN BE GROUDED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE. VERY SOFT CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGER NAIL.										TERM SPACING VERY WIDE MORE THAN 10 FEET WIDE 3 TO 10 FEET MODERATELY CLOSE 1 TO 3 FEET CLOSE 0.16 TO 1 FOOT VERY CLOSE LESS THAN 0.16 FEET										TERM THICKNESS VERY THICKLY BEDDED 4 FEET THICKLY BEDDED 1.5 - 4 FEET THINLY BEDDED 0.16 - 1.5 FEET VERY THINLY BEDDED 0.03 - 0.16 FEET THICKLY LAMINATED 0.008 - 0.03 FEET THINLY LAMINATED < 0.008 FEET																													
PLASTICITY										EQUIPMENT USED ON SUBJECT PROJECT										INDURATION										NOTES:																																							
NON PLASTIC 0-5 VERY LOW SLIGHTLY PLASTIC 6-15 SLIGHT MODERATELY PLASTIC 16-25 MEDIUM HIGHLY PLASTIC 26 OR MORE HIGH										DRILL UNITS: CME-45C, CME-55, CME-550, VANE SHEAR TEST, PORTABLE HOIST, MOBILE B-57 ADVANCING TOOLS: CLAY BITS, 6" CONTINUOUS FLIGHT AUGER, 8" HOLLOW AUGERS, HARD FACED FINGER BITS, TUNG-CARBIDE INSERTS, CASING w/ ADVANCER, TRICONE STEEL TEETH, TRICONE 2-15/16" TUNG-CARB., CORE BIT HAMMER TYPE: AUTOMATIC, MANUAL CORE SIZE: B, H, N HAND TOOLS: POST HOLE DIGGER, HAND AUGER, SOUNDING ROD, VANE SHEAR TEST										FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC. FRIABLE RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE. MODERATELY INDURATED GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER. INDURATED GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER. EXTREMELY INDURATED SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.										BENCH MARK: BM - STA 146+20, 153' LT -L- (854,803' N, 1,912,756' E) ELEVATION: 641.59 FEET FIAD - FILLED IMMEDIATELY AFTER DRILLING																																							
DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-BROWN). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.																																																																					



SKIEW ANGLES:
 EBI NBL - $111^{\circ}-56'-01''$, SBL - $111^{\circ}-35'-25''$
 BI NBL - $108^{\circ}-08'-30''$, SBL - $107^{\circ}-51'-45''$
 B2 NBL - $104^{\circ}-23'-34''$, SBL - $104^{\circ}-10'-26''$
 B3 NBL - $100^{\circ}-38'-32''$, SBL - $100^{\circ}-28'-55''$
 EB2 NBL - $97^{\circ}-39'-31''$, SBL - $97^{\circ}-32'-37''$






EB1
 EB1-B
 142+40
 39' RT


B1
 B1-B
 144+04
 51' RT

B2
 B2-B
 145+07
 43' RT


B3
 B3-B
 146+24
 43' RT

EB2
 EB2-B
 146+92
 48' RT





END BENT NO. 1 CROSS SECTION AT STA 142+41.1



BENT NO. 1 CROSS SECTION AT STA 143+72.3

NOTES:
 GROUNDLINE TAKEN FROM ROADWAY DESIGN
 TIN FILE U3109A_LS TIN.TIN DATED SEPTEMBER 8, 2014
 BASED ON PGD DATED MAY 2014
 INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS
 WITH BOTH PROJECTED ONTO THE CROSS SECTION
 SKEW: NBL - 111°-56'-01", SBL - 111°-35'-25"


NOTES:
 GROUNDLINE TAKEN FROM ROADWAY DESIGN
 TIN FILE U3109A_LS TIN.TIN DATED SEPTEMBER 8, 2014
 BASED ON PGD DATED MAY 2014
 INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS
 WITH BOTH PROJECTED ONTO THE CROSS SECTION
 SKEW: NBL - 108°-08'-30", SBL - 107°-51'-45"

NOTES:
GROUNDLINE TAKEN FROM ROADWAY DESIGN
TIN FILE U3109A LS TIN TIN DATED SEPTEMBER
8, 2014 BASED ON PGD DATED MAY 2014

INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS
WITH BOTH PROJECTED ONTO THE CROSS SECTION

SKEW: NBL - 104°-23'-34", SBL - 104°-10'-26"

B2-A 145+28 45' LT
B2-D 145+20 12' LT
B2-E 145+15 12' RT



HORIZ. SCALE 0 20 40 (FEET) VE = 2:1


BENT NO. 2 CROSS SECTION AT STA 145+02.2

NOTES:
GROUNDLINE TAKEN FROM ROADWAY DESIGN
TIN FILE U3109A LS TIN TIN DATED SEPTEMBER 8, 2014
BASED ON PGD DATED MAY 2014

INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH PROJECTED ONTO THE CROSS SECTION


SKEW: NBL - 100°-38'-32", SBL - 100°-28'-55"

B3-A 146+40 45' LT
B3-D 146+34 12' LT
B3-E 146+30 12' RT
B3-B 146+24 43' RT



HORIZ. SCALE 0 20 40 (FEET) VE = 2:1

BENT NO. 3 CROSS SECTION AT STA 146+32.1







NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 34900.1.2	TIP U-3109A	COUNTY ALAMANCE	GEOLOGIST Goodnight, D. J.
SITE DESCRIPTION Dual Bridges on -L- (Future NC 119) over SR 1962 (Holt Street), NCRR/NSRR, and -Y16- (US 70)			GROUND WTR (ft)
BORING NO. EB1-A	STATION 143+02	OFFSET 58 ft LT	ALIGNMENT -L-
COLLAR ELEV. 638.2 ft	TOTAL DEPTH 55.0 ft	NORTHING 854,719	EASTING 1,912,562
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 73% 02/07/2014		DRILL METHOD H.S. Augers	HAMMER TYPE Automatic
DRILLER Whichard, S. W.	START DATE 12/09/14	COMP. DATE 12/09/14	SURFACE WATER DEPTH N/A



WBS 34900.1.2	TIP U-3109A	COUNTY ALAMANCE	GEOLOGIST Goodnight, D. J.
SITE DESCRIPTION Dual Bridges on -L- (Future NC 119) over SR 1962 (Holt Street), NCRR/NSRR, and -Y16- (US 70)			GROUND WTR (ft)
BORING NO. EB1-C	STATION 142+71	OFFSET 8 ft LT	ALIGNMENT -L-
COLLAR ELEV. 640.3 ft	TOTAL DEPTH 63.1 ft	NORTHING 854,706	EASTING 1,912,620
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 73% 02/07/2014		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Whichard, S. W.	START DATE 12/10/14	COMP. DATE 12/11/14	SURFACE WATER DEPTH N/A



NCDOT BORE DOUBLE U3109A_GEO_BRDG_GINT.GPJ NC_DOT.GDT 3/24/15

NCDOT GEOTECHNICAL ENGINEERING UNIT
BORELOG REPORT

WBS 34900.1.2	TIP U-3109A	COUNTY ALAMANCE	GEOLOGIST Goodnight, D. J.
SITE DESCRIPTION Dual Bridges on -L- (Future NC 119) over SR 1962 (Holt Street), NCR/NSRR, and -Y16- (US 70)			GROUND WTR (ft)
BORING NO. EB1-B	STATION 142+40	OFFSET 39 ft RT	ALIGNMENT -L-
COLLAR ELEV. 642.7 ft	TOTAL DEPTH 70.1 ft	NORTHING 854,693	EASTING 1,912,674
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 73% 02/07/2014		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Whichard, S. W.	START DATE 12/10/14	COMP. DATE 12/10/14	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			ELEV. (ft)	DEPTH (ft)		
645														642.7	0.0	GROUND SURFACE
640	642.7	0.0	7	9	12	21						M		642.7		RESIDUAL Red-Brown to Red and Tan, Coarse to Fine Sandy, Silty CLAY
635	639.2	3.5	6	14	16	30						M		636.7	6.0	Tan-Red to Tan, Clayey SILT
630	634.2	8.5	4	6	8	14						M				
625	629.2	13.5	2	2	2	4						M				
620	624.2	18.5	2	2	3	5						M				
615	619.2	23.5	2	2	4	6						M				
610	614.2	28.5	2	4	7	11						M				
605	609.2	33.5	4	5	7	12						M		605.7	37.0	Tan, Fine Sandy SILT
600	604.2	38.5	4	4	7	11						M				
595	599.2	43.5	4	8	10	18						M				
590	594.2	48.5	11	14	14	28						M				
585	589.2	53.5	10	14	17	31						M				
580	584.2	58.5	20	25	22	47						M				
575	579.2	63.5	10	12	20	32						M		576.7	66.0	WEATHERED ROCK Tan FELSIC METAVOLCANIC ROCK
	574.2	68.5	100/0.2			100/0.2								572.7	70.0	CRYSTALLINE ROCK Tan FELSIC METAVOLCANIC ROCK
	572.7	70.0	60/0.1			60/0.1								572.6	70.1	Boring Terminated with Standard Penetration Test Refusal at Elevation 572.6 ft in CRYSTALLINE ROCK: FELSIC METAVOLCANIC ROCK


NCDOT BORE DOUBLE U3109A_GEO_BRDG_GINT.GPJ NC_DOT.GDT 3/24/15




NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 34900.1.2	TIP U-3109A	COUNTY ALAMANCE	GEOLOGIST Goodnight, D. J.
SITE DESCRIPTION Dual Bridges on -L- (Future NC 119) over SR 1962 (Holt Street), NCRR/NSRR, and -Y16- (US 70)			GROUND WTR (ft)
BORING NO. B1-A	STATION 144+14	OFFSET 49 ft LT	ALIGNMENT -L-
COLLAR ELEV. 640.7 ft	TOTAL DEPTH 68.9 ft	NORTHING 854,832	EASTING 1,912,537
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 73% 02/07/2014		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Whichard, S. W.	START DATE 12/11/14	COMP. DATE 12/11/14	SURFACE WATER DEPTH N/A



WBS 34900.1.2	TIP U-3109A	COUNTY ALAMANCE	GEOLOGIST Wells, T. R.
SITE DESCRIPTION Dual Bridges on -L- (Future NC 119) over SR 1962 (Holt Street), NCRR/NSRR, and -Y16- (US 70)			GROUND WTR (ft)
BORING NO. B1-E	STATION 144+12	OFFSET 24 ft RT	ALIGNMENT -L-
COLLAR ELEV. 641.1 ft	TOTAL DEPTH 63.6 ft	NORTHING 854,850	EASTING 1,912,607
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 73% 02/07/2014		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Whichard, S. W.	START DATE 12/23/14	COMP. DATE 12/23/14	SURFACE WATER DEPTH N/A





NCDOT BORE DOUBLE U3109A_GEO_BRDG_GINT.GPJ NC_DOT.GDT 3/24/15

NCDOT GEOTECHNICAL ENGINEERING UNIT
BORELOG REPORT

WBS 34900.1.2	TIP U-3109A	COUNTY ALAMANCE	GEOLOGIST Wells, T. R.
SITE DESCRIPTION Dual Bridges on -L- (Future NC 119) over SR 1962 (Holt Street), NCRR/NSRR, and -Y16- (US 70)			GROUND WTR (ft)
BORING NO. B1-B	STATION 144+04	OFFSET 51 ft RT	ALIGNMENT -L-
COLLAR ELEV. 640.9 ft	TOTAL DEPTH 73.8 ft	NORTHING 854,849	EASTING 1,912,636
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 73% 02/07/2014		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Whichard, S. W.	START DATE 12/23/14	COMP. DATE 12/29/14	SURFACE WATER DEPTH N/A

WBS 34900.1.2	TIP U-3109A	COUNTY ALAMANCE	GEOLOGIST Wells, T. R.
SITE DESCRIPTION Dual Bridges on -L- (Future NC 119) over SR 1962 (Holt Street), NCRR/NSRR, and -Y16- (US 70)			GROUND WTR (ft)
BORING NO. B1-B	STATION 144+04	OFFSET 51 ft RT	ALIGNMENT -L-
COLLAR ELEV. 640.9 ft	TOTAL DEPTH 73.8 ft	NORTHING 854,849	EASTING 1,912,636
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 73% 02/07/2014		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Whichard, S. W.	START DATE 12/23/14	COMP. DATE 12/29/14	SURFACE WATER DEPTH N/A



NCDOT BORE DOUBLE U3109A_GEO_BRDG_GINT.GPJ NC_DOT.GDT 3/24/15

NCDOT GEOTECHNICAL ENGINEERING UNIT
BORELOG REPORT

WBS 34900.1.2	TIP U-3109A	COUNTY ALAMANCE	GEOLOGIST Goodnight, D. J.
SITE DESCRIPTION Dual Bridges on -L- (Future NC 119) over SR 1962 (Holt Street), NCRR/NSRR, and -Y16- (US 70)			GROUND WTR (ft)
BORING NO. B2-B	STATION 145+07	OFFSET 43 ft RT	ALIGNMENT -L-
COLLAR ELEV. 639.8 ft	TOTAL DEPTH 79.4 ft	NORTHING 854,945	EASTING 1,912,603
DRILL RIG/HAMMER EFF./DATE TRI8016 MOBILE B-57 92% 02/07/2014		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Toothman, R. E.	START DATE 02/04/15	COMP. DATE 02/05/15	SURFACE WATER DEPTH N/A



ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
645															
640	639.8	0.0	1	2	3									639.8	GROUND SURFACE
635	636.3	3.5	3	4	7									636.8	RESIDUAL Brown, Clayey, Coarse to Fine Sandy SILT
630	631.3	8.5	2	3	5									631.8	Tan, Fine Sandy, Silty CLAY
625	626.3	13.5	1	2	3										Tan and Gray, Tan to Green-Tan, Fine Sandy SILT
620	621.3	18.5	1	3	3										
615	616.3	23.5	2	3	3										
610	611.3	28.5	2	3	5										
605	606.3	33.5	2	4	6										
600	601.3	38.5	3	6	7										
595	596.3	43.5	6	10	14										
590	591.3	48.5	6	9	14										
585	586.3	53.5	14	22	35										
580	581.3	58.5	11	19	22										
575	576.3	63.5	9	15	21										
570	571.3	68.5	40	60/0.3										572.8	WEATHERED ROCK Tan FELSIC METAVOLCANIC ROCK
565	566.3	73.5	37	63/0.4										560.4	WEATHERED ROCK Tan FELSIC METAVOLCANIC ROCK (continued)

WBS 34900.1.2	TIP U-3109A	COUNTY ALAMANCE	GEOLOGIST Goodnight, D. J.
SITE DESCRIPTION Dual Bridges on -L- (Future NC 119) over SR 1962 (Holt Street), NCRR/NSRR, and -Y16- (US 70)			GROUND WTR (ft)
BORING NO. B2-B	STATION 145+07	OFFSET 43 ft RT	ALIGNMENT -L-
COLLAR ELEV. 639.8 ft	TOTAL DEPTH 79.4 ft	NORTHING 854,945	EASTING 1,912,603
DRILL RIG/HAMMER EFF./DATE TRI8016 MOBILE B-57 92% 02/07/2014		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Toothman, R. E.	START DATE 02/04/15	COMP. DATE 02/05/15	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
565															
	561.3	78.5	40	60/0.4										560.4	WEATHERED ROCK Tan FELSIC METAVOLCANIC ROCK (continued)
															Boring Terminated at Elevation 560.4 ft in WEATHERED ROCK: FELSIC METAVOLCANIC ROCK

NCDOT BORE DOUBLE U3109A_GEO_BRDG_GINT.GPJ NC_DOT.GDT 3/24/15

NCDOT GEOTECHNICAL ENGINEERING UNIT
BORELOG REPORT



NCDOT BORE DOUBLE U3109A_GEO_BRDG_GINT.GPJ NC_DOT.GDT 3/24/15

NCDOT GEOTECHNICAL ENGINEERING UNIT
BORELOG REPORT

WBS 34900.1.2	TIP U-3109A	COUNTY ALAMANCE	GEOLOGIST Wells, T. R.
SITE DESCRIPTION Dual Bridges on -L- (Future NC 119) over SR 1962 (Holt Street), NCRR/NSRR, and -Y16- (US 70)			GROUND WTR (ft)
BORING NO. EB2-A	STATION 147+04	OFFSET 47 ft LT	ALIGNMENT -L-
COLLAR ELEV. 630.9 ft	TOTAL DEPTH 53.5 ft	NORTHING 855,123	EASTING 1,912,480
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 73% 02/07/2014		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Whichard, S. W.	START DATE 12/19/14	COMP. DATE 12/19/14	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			ELEV. (ft)	DEPTH (ft)		
635																
630	630.9	0.0	3	3	4									630.9	0.0	GROUND SURFACE
625	627.7	3.2	5	12	18											RESIDUAL Reddish Brown, Fine Sandy, Silty CLAY
620	622.7	8.2	5	7	9									623.9	7.0	Reddish, Tan-Brown to Light Gray and Brown, Clayey, Fine Sandy SILT
615	617.7	13.2	3	3	4											
610	612.7	18.2	5	7	11											
605	607.7	23.2	8	11	13											
600	602.7	28.2	17	21	26											
595	597.7	33.2	11	16	27											
590	592.7	38.2	16	31	43											
585	587.7	43.2	32	68/0.4												WEATHERED ROCK Brown and Gray FELSIC METAVOLCANIC ROCK
580	582.7	48.2	18	37	63/0.3											
	577.7	53.2	100/0.3													Boring Terminated at Elevation 577.4 ft in WEATHERED ROCK: FELSIC METAVOLCANIC ROCK

NCDOT BORE DOUBLE U3109A_GEO_BRDG_GINT.GPJ NC_DOT.GDT 3/24/15

NCDOT GEOTECHNICAL ENGINEERING UNIT
BORELOG REPORT

WBS 34900.1.2	TIP U-3109A	COUNTY ALAMANCE	GEOLOGIST Goodnight, D. J.
SITE DESCRIPTION Dual Bridges on -L- (Future NC 119) over SR 1962 (Holt Street), NCR/NSRR, and -Y16- (US 70)			GROUND WTR (ft)
BORING NO. EB2-B	STATION 146+92	OFFSET 48 ft RT	ALIGNMENT -L-
COLLAR ELEV. 634.9 ft	TOTAL DEPTH 73.7 ft	NORTHING 855,123	EASTING 1,912,576
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 73% 02/07/2014		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Whichard, S. W.	START DATE 12/16/14	COMP. DATE 12/16/14	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
645															
640															
635	634.9	0.0	2	3	4									634.9	GROUND SURFACE
630	631.4	3.5	4	4	6									631.9	RESIDUAL Tan-Red, Coarse to Fine Sandy, Silty CLAY
625	626.4	8.5	2	3	4									622.9	Red and Tan, Fine Sandy SILT
620	621.4	13.5	1	2	3									622.9	Tan, Clayey, Fine Sandy SILT
615	616.4	18.5	2	2	2									607.9	Tan, Fine Sandy SILT
610	611.4	23.5	2	2	3									602.9	Tan, Clayey, Fine Sandy SILT
605	606.4	28.5	2	5	7									597.9	Tan, Coarse to Fine Sandy SILT
600	601.4	33.5	2	1	2										
595	596.4	38.5	5	6	11										
590	591.4	43.5	7	9	15										
585	586.4	48.5	12	22	35										
580	581.4	53.5	20	43	50										
575	576.4	58.5	9	25	34										
570	571.4	63.5	8	19	33										
565	566.4	68.5	55	45/0.2										567.9	WEATHERED ROCK Tan FELSIC METAVOLCANIC ROCK

WBS 34900.1.2	TIP U-3109A	COUNTY ALAMANCE	GEOLOGIST Goodnight, D. J.
SITE DESCRIPTION Dual Bridges on -L- (Future NC 119) over SR 1962 (Holt Street), NCR/NSRR, and -Y16- (US 70)			GROUND WTR (ft)
BORING NO. EB2-B	STATION 146+92	OFFSET 48 ft RT	ALIGNMENT -L-
COLLAR ELEV. 634.9 ft	TOTAL DEPTH 73.7 ft	NORTHING 855,123	EASTING 1,912,576
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 73% 02/07/2014		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Whichard, S. W.	START DATE 12/16/14	COMP. DATE 12/16/14	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
565															
	561.4	73.5												561.2	WEATHERED ROCK Tan FELSIC METAVOLCANIC ROCK (continued)
															Boring Terminated at Elevation 561.2 ft in WEATHERED ROCK: FELSIC METAVOLCANIC ROCK
															Notes: Topsoil (0.0 to 0.5 feet)

NCDOT BORE DOUBLE U3109A_GEO_BRDG_GINT.GPJ NC_DOT.GDT 3/24/15

SITE PHOTOGRAPHS



View Looking East along -Y16- from Bent No. 3



Profile of Bridge From End Bent No. 1 Looking North