


BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.

BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETERMINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.

TEMPORARY DRAINAGE AT END BENT



SECTION A-A

* ELEVATIONS BETWEEN BRIDGE SEAT BUILDUPS ARE SHOWN AT THIS POINT

_ DATE : <u>12/2016</u>


_ DATE : <u>12/2016</u>


_ DATE : <u>12/2016</u>


MAL, MKO


DESIGN ENGINEER OF RECORD: MKO

DRAWN BY : ____









END BENT #1					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	5	#11	1	55′-7′′	1477
B2	2	#11	STR	52′-5′′	557
В3	6	#9	1	54'-11''	1120
В4	16	#4	STR	27′-5′′	293
B5	13	#4	STR	3'-11''	34
В6	6	#5	STR	52′-5′′	328
B7	30	#4	STR	3′-2′′	63
H1	24	#4	2	16'-3''	261
H2	24	#4	3	19'-11''	319
K1	28	#4	STR	27′-5′′	513
K2	4	#4	STR	3′-9′′	10
К3	4	#4	STR	3′-9′′	10
S1	84	#5	4	12'-1''	1059
S2	84	#5	5	4'-10''	423
S3	60	#4	6	6'-6''	261
S4	6	#6	9	5′-3′′	47
S5	6	#6	8	9'-1''	82
S6	2	#5	4	12'-4''	26
S7	2	#5	5	5'-1''	11
U1	44	#4	7	4'-2''	122
U2	35	#4	7	7'-11''	185
U3	4	#4	7	9'-8''	26
U4	4	#4	7	13'-3''	35
V1	44	#5	STR	9'-6''	436
V2	42	#5	STR	11'-7''	507
V3	50	#5	STR	11'-4''	591
REINFORCING STEEL				8,796 LBS.	
CLASS A CONCRETE BREAKDOWN POUR #1 CAP, LOWER PART 41.7 C.Y.					

BILL OF MATERIAL

POUR #1 CAP, LOWER PART 41.7 C.Y.
OF WING &
COLLARS

POUR #2 UPPER PART OF 22.2 C.Y. WING & BACKWALL

TOTAL CLASS A CONCRETE 63.9 C.Y.

HP 12 X 53 STEEL PILES
NO: 17
LIN. FT.= 510

STEEL PILE POINTS NO. = 17

PILE DRIVING EQUIPMENT SETUP

HP 12 X 53 NO. = 17

PROJECT NO. R-2707C

CLEVELAND COUNT'

STATION: 29+07.16 -Y2-

SHEET 3 OF 3



DEPARTMENT OF TRANSPORTATION
RALEIGH
SUBSTRUCTURE

END BENT NO.1

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED