
NOTES

- 1. ASSUMED LIVE LOAD = HL-93 OR ALTERNATE LOADING
- 2. THIS BRIDGE HAS BEEN DESIGNED IN ACCORDANCE WITH THE REQUIREMENTS OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS
- 3. THIS BRIDGE IS LOCATED IN SEISMIC ZONE 1.
- 4. FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE SHEET SN.
- 5. FOR SUBMITTAL OF WORKING DRAWINGS. SEE SPECIAL PROVISIONS.
- 6. FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.
- 7. FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.
- 8. FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.
- 9. FOR PLACING LOAD ON STRUCTURE MEMBERS, SEE SPECIAL PROVISIONS
- 10. FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.
- 11. FOR EMBEDDED CLIPS FOR PRESTRESSED CONCRETE GIRDERS, SEE SPECIAL PROVISIONS.
- 12. NEEDLE BEAMS WILL NOT BE ALLOWED UNLESS OTHERWISE CALLED FOR ON THE PLANS OR APPROVED BY THE ENGINEER.
- 13. REMOVABLE FORMS MAY BE USED IN LIEU OF METAL STAY-IN-PLACE FORMS IN ACCORDANCE WITH ARTICLE 420-3 OF THE STANDARD SPECIFICATIONS.
- 14. THE CLASS AA CONCRETE IN THE BRIDGE DECK SHALL CONTAIN FLY ASH OR GROUND GRANULATED BLAST FURNACE SLAG AT THE SUBSTITUTION RATE SPECIFIED IN ARTICLE 1024-1 AND IN ACCORDANCE WITH ARTICLES 1024-5 AND 1024-6 OF THE STANDARD SPECIFICATIONS. NO PAYMENT WILL BE MADE FOR THIS SUBSTITUTION AS IT IS CONSIDERED INCIDENTAL TO THE COST OF THE REINFORCED CONCRETE DECK SLAB.
- 15. FOR FOUNDATION NOTES, SEE SHEET S6-2.

	FOUNDATION EXCAVATION FOR BENT NO.1	REINFORCED CONCRETE DECK SLAB	BRIDGE	CLASS A CONCRETE	BRIDGE APPROACH SLABS	REINFORCING STEEL	SPIRAL COLUMN REINFORCING STEEL	PRESTRESSED	PILE DRIVING EQUIPMENT SETUP FOR HP 12X53 STEEL PILES	HP 12X53 STEEL PILES	1'-2" × 3'-2¾" CONCRETE PARAPET	TWO BAR METAL RAIL	1	ELASTOMERIC BEARINGS
	LUMP SUM	SQ.FT.	SQ.FT.	CY. YDS.	LUMP SUM	LBS	LBS	NO. LIN.FT.	EACH	No. LIN. FT.	LIN. FT.	LIN.FT.	SQ. YDS.	LUMP SUM
SUPERSTRUCTURE		16,915	16,726		LUMP SUM			16 1644.5			414.65	399.40		LUMP SUM
END BENT No. 1				63.9		9,695			10	10 910			317	
BENT No. 1	LUMP SUM			147.9		24,911	2,737		30	30 1,650				
END BENT No. 2				65.2		9,734			10	10 840			402	
TOTAL	LUMP SUM	16,915	16,726	277.0	LUMP SUM	44,340	2,737	16 1644.5	50	50 3,400	414.65	399.40	719	LUMP SUM

Jeff Loftus 3/28/2017

DOCUMENT NOT CONSIDERED FINAL **UNLESS ALL SIGNATURES COMPLETED**



Firm License No. C-1051 421 Fayetteville St, Suite 400 Raleigh, NC 27601 T 919.380.8750 www.stewartinc.com

STATION: 24+07.99 -Y9- POT SHEET 3 OF 4

PROJECT NO. R-2707C

CLEVELAND

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

GENERAL DRAWING FOR BRIDGE OVER US 74/SHELBY BYPASS ON NC 18 (FALLSTON RD.) BETWEEN SR 1845 AND SR 1908

> SHEET NO REVISIONS S6-3 TOTAL SHEETS

COUNTY

DATE : 07-16 H. ASSFOURA DESIGN ENGINEER OF RECORD: <u>J.LOFTUS</u> DATE: <u>07-16</u>

R 2707C_6