

NOTES

ASSUMED LIVE LOAD = HL 93 OR ALTERNATE LOADING.

THIS BRIDGE HAS BEEN DESIGNED IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS.

THIS BRIDGE IS LOCATED IN SEISMIC ZONE 1.

FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE SHEET SN.

THE CLASS AA CONCRETE IN THE BRIDGE DECK SHALL CONTAIN FLY ASH OR GROUND GRANULATED BLAST FURNACE SLAG AT THE SUBSTITUTION RATE SPECIFIED IN ARTICLE 1024-1 AND IN ACCORDANCE WITH ARTICLES 1024-5 AND 1024-6 OF THE STANDARD SPECIFICATIONS. NO PAYMENT WILL BE MADE FOR THIS SUBSTITUTION AS IT IS CONSIDERED INCIDENTAL TO THE COST OF THE REINFORCED CONCRETE DECK SLAB.

REMOVABLE FORMS MAY BE USED IN LIEU OF METAL STAY-IN-PLACE FORMS IN ACCORDANCE WITH ARTICLE 420-3 OF THE STANDARD SPECIFICATIONS.

NEEDLE BEAMS WILL NOT BE ALLOWED UNLESS OTHERWISE CALLED FOR ON THE PLANS OR APPROVED BY THE ENGINEER.

FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

FOR EROSION CONTROL MEASURES. SEE EROSION CONTROL

FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.

FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.

PROVISIONS.

PLANS.

FOR PLACING LOAD ON STRUCTURE MEMBERS, SEE SPECIAL PROVISIONS.

FOR MAINTENANCE AND PROTECTION OF TRAFFIC BENEATH PROPOSED STRUCTURE, SEE SPECIAL PROVISIONS.

					TOTAL B	ILL	OF M	IATERIAL -						
	REINFORCED CONCRETE DECK SLAB	GROOVING BRIDGE FLOORS	CLASS A CONCRETE	BRIDGE APPROACH SLABS	REINFORCING STEEL	PRE:	IFIED 63" STRESSED NCRETE IRDERS	PILE DRIVING EQUIPMENT SETUP FOR HP 12 x 53 STEEL PILES	HP STE	12 x 53 EL PILES	PDA TESTING	CONCRETE BARRIER RAIL	4"SLOPE PROTECTION	ELASTOMERI BEARINGS
	SQ.FT.	SQ.FT.	CU. YDS.	LUMP SUM	LBS.	No.	LIN.FT.	EACH	No.	LIN.FT.	EACH	LIN.FT.	SQ. YD.	LUMP SUM
SUPERSTRUCTURE	3,979	5,505		LUMP SUM		4	356.92					180.58		LUMP SUM
END BENT 1			32.2		5,289			9	9	700.0			14	
END BENT 2			32.2		5,289			9	9	675.0	1		14	
TOTAL	3,979	5,505	64.4	LUMP SUM	10,578	4	356.92	18	18	1,375.0	1	180.58	28	LUMP SUM

R-2707C PROJECT NO. ___ CLEVELAND COUNTY 611 + 32.01 -L-STATION:

SHEET 3 OF 3

DOCUMENT NOT CONSIDERED FINAL

UNLESS ALL SIGNATURES COMPLETED

2/17/2017

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

GENERAL DRAWING

BRIDGE OVER NC 150 (-Y14-) ON SHELBY BYPASS (-L-) BETWEEN NC 180 AND US 74 BUSINESS

(LE	F.	T LAI	VE)	
REVIS	ION	S		SHEET No.
DATE:	No.	BY:	DATE:	S9 – 3

PLANS PREPARED BY **PARSONS**

NC LICENSE No. F-0246