

# EARTHWORK SUMMARY

IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	EMBT + %	BORROW	WASTE
-L- STA 57+65.00 TO 61+62.32	281	348	67	
-Y13- STA 10+00.00 TO STA 12+70.41	606	446		160
-L- STA 62+62.32 TO STA 64+55.95	191	136		55
-L- STA 67+57.38 TO STA 95+00.00	1395	6350	4955	
-L- STA 95+00.00 TO STA 121+11.99	1809	5116	3307	
-L- STA 122+87.15 TO STA 144+15.00	784	7586	6802	
SUB-TOTAL	5066	19982	15131	215
LOSS DUE TO CLEARING & GRUBBING	-3073		3073	
EARTH WASTE TO REPLACE BORROW			-215	-215
ESTIMATED BORROW FOR -L-DET-		379	379	
ESTIMATED SHOULDER MATERIAL		8122	8122	
PROJECT TOTALS	1993	28483	26490	0
EST. 5% FOR REPLACING TOPSOIL ON BORROW PITS			1325	
GRAND TOTALS	1993		27815	0
SAY	2000		27820	0

**Notes:**

1. Approximate quantities only. Unclassified Excavation, Fine Grading, Clearing and Grubbing, and Removal of Existing Pavement will be paid for at the contract lump sum price for "Grading."