

PROJECT NO.	SHEET NO.	TOTAL NO.
2017CPT.08.24.10831, 2017CPT.08.24.20471	7	
2017CPT.08.24.20831,		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	AGGREGATE SHOULDER BORROW TON	SHOULDER RECONSTRUCTION SMI	1.5" MILLING SY	INCIDENTAL MILLING SY	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TON	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	MILLED RUMBLE STRIPS - CENTERLINE LF	MILLED RUMBLE STRIPS - EDGELINE LF	
2017CPT.08.24.10831	Scotland	1	US 15-501	FROM US 401 BYPASS TO CJ AT SR 1429 (SHAW CURRIE RD)	1	2	2WU	NO	NO	2.87	28-42			53,207		4,870		292		17,700	27,000	
TOTAL FOR MAP NO. 1										2.87				53,207		4,870		292		17,700	27,000	
2017CPT.08.24.10831	Scotland	2	US 15-501	FROM 0.12 MILES NORTH OF NC 144 TO HOKE COUNTY LINE	1	2	2WU	NO	NO	12.56	28-42			228,705		19,215		1,153		85,810	132,634	
TOTAL FOR MAP NO. 2										12.56				228,705		19,215		1,153		85,810	132,634	
TOTAL FOR PROJ NO. 2017CPT.08.24.10831										15.43				281,912		24,085		1,445		103,510	159,634	
2017CPT.08.24.20471	Hoke	3	SR 1203 (TURNPIKE ROAD)	FROM BRIDGE # 8 @ SCOTLAND COUNTY LINE TO PVT. JT. @ SR 1202 (FULFORD MCMILLAN ROAD)	2	2	2WU	NO	NO	3.108	24	862.00	6.22		1,585		3,980	267	100			
TOTAL FOR MAP NO. 3										3.108		862.00	6.22		1,585		3,980	267	100			
2017CPT.08.24.20471	Hoke	4	SR 1225 (ASHEMONT ROAD)	FROM MOORE COUNTY LINE (STATE MAINT. ENDS) TO US 15-501	2	2	2WU	NO	NO	1.346	22	373.00	2.69		367		1,550	104	100			
TOTAL FOR MAP NO. 4										1.346		373.00	2.69		367		1,550	104	100			
2017CPT.08.24.20471	Hoke	5	SR 1001 (SHANNON ROAD)	FROM NC 211 TO SR 1449 ((HALL RD)	2	2	2WU	NO	NO	3.46	22	960.00	6.92		700		3,995	268	100			
TOTAL FOR MAP NO. 5										3.46		960.00	6.92		700		3,995	268	100			
TOTAL FOR PROJ NO. 2017CPT.08.24.20471										7.914		2,195.00	15.83		2,652		9,525	639	300			
2017CPT.08.24.20831	Scotland	6	SR 1131 (X WAY ROAD)	FROM NC 79 TO SR 1108 (ODOM ROAD)	2	2	2WU	NO	NO	3.392	22	940.00	6.78		856		3,815	256	100			
TOTAL FOR MAP NO. 6										3.392		940.00	6.78		856		3,815	256	100			
2017CPT.08.24.20831	Scotland	7	SR 1108 (X WAY ROAD)	FROM SR 1131 (X WAY ROAD TO SR 1269 (LYTCH DRIVE)	2	2	2WU	NO	NO	1.223	22	340.00	2.45		150		1,550	104	100			
TOTAL FOR MAP NO. 7										1.223		340.00	2.45		150		1,550	104	100			
TOTAL FOR PROJ NO. 2017CPT.08.24.20831										4.615		1,280.00	9.23		1,006		5,365	360	200			
GRAND TOTAL										27.959		3,475.00	25.06		281,912		24,085	14,890	2,444	500	103,510	159,634