PROJECT NO.	SHEET NO.	TOTAL NO.
2017CPT.08.24.10831, 2017CPT.08.24.20471	8	
2017CPT.08.24.20831,		

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	4457000000-N TEMPORARY TRAFFIC CONTROL LS	4685000000-E 4" X 90 M WHITE THERMO LF	4890000000-E 4" X 120 M YELLOW THERMO (MILLED RUMBLE STRIPS LIMITS) LF	4686000000-E 4" X 120 M YELLOW THERMO LF	4686000000-E 4" X 120 M WHITE THERMO LF	4695000000-E 8" X 90 M YELLOW THERMO LF	4700000000-E 12" X 90 M YELLOW THERMO LF	4705000000-E 16" X 120 M WHITE THERMO LF	4710000000-E 24" X 120 M WHITE THERMO LF	4721000000-E THERMO RXR 120 M EA	4725000000-E THERMO STR & RT ARROW 90 M EA	4725000000-E THERMO LT ARROW 90 M EA	4725000000-E THERMO RT ARROW 90 M EA	4725000000-E THERMO STR & LT ARROW 90 M EA	4725000000-E THERMO STR ARROW 90 M EA	4770000000-E COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE II (4") LF	4810000000-E 4" YELLOW PAINT LF	4810000000-E 4" WHITE PAINT LF	4820000000-E 8" YELLOW PAINT LF	4835000000-E 24" WHITE PAINT LF	4850000000-E 4" LINE REMOVAL LF	4900000000-N YELLOW & YELLOW MARKERS EA	4905000000-N SNOW PLOWABLE MARKERS C & R MARKERS EA	4905000000-N SNOW PLOWABLE MARKERS Y & Y MARKERS EA
2017CPT.08.24.10831	Scotland	1	US 15-501	FROM US 401 BYPASS TO CJ AT SR 1429 (SHAW CURRIE RD)	1	2	2WU	2.87	28-42	322		30,346	8,450	2,435	1,300	600		150	355	6	1	9	4	1			24,250	31,650	600	355			20	195
TOTAL FOR MAP NO. 1								**2.87**		**322**		**30,346**	**8,450**	**2,435**	**1,300**	**600**		**150**	**355**	**6**	**1**	**9**	**4**	**1**			**24,250**	**31,650**	**600**	**355**			**20**	**195**
2017CPT.08.24.10831	Scotland	2	US 15-501	FROM 0.12 MILES NORTH OF NC 144 TO HOKE COUNTY LINE	1	2	2WU	12.56	28-42	1,407		132,240	103,235	5,790	565		340					2	3		2	720	109,000	132,805			720		20	1,150
TOTAL FOR MAP NO. 2								**12.56**		**1,407**	*	**132,240**	**103,235**	**5,790**	**565**		**340**					**2**	**3**		**2**	**720**	**109,000**	**132,805**			**720**		**20**	**1,150**
TOTAL FOR PROJ NO. 2017CPT.08.24.10831								**15.43**		**1,729**	*	**162,586**	**111,685**	**8,225**	**1,865**	**600**	**340**	**150**	**355**	**6**	**1**	**11**	**7**	**1**	**2**	**720**	**133,250**	**164,455**	**600**	**355**	**720**		**40**	**1,345**
														10,090									**22**				**297,705**						**1,385**	
2017CPT.08.24.20471	Hoke	3	SR 1203 (TURNPIKE ROAD)	FROM BRIDGE # 8 @ SCOTLAND COUNTY LINE TO PVT. JT. @ SR 1202 (FULFORD MCMILLAN ROAD)	2	2	2WU	3.108	24	349		32,816		24,642	100																	210		
TOTAL FOR MAP NO. 3								**3.108**		**349**		**32,816**		**24,642**	**100**																	**210**		
2017CPT.08.24.20471	Hoke	4	SR 1225 (ASHEMONT ROAD)	FROM MOORE COUNTY LINE (STATE MAINT. ENDS) TO US 15-501	2	2	2WU	1.346	22	151		14,218		12,572	50																	90		
TOTAL FOR MAP NO. 4								**1.346**		**151**		**14,218**		**12,572**	**50**																	**90**		
2017CPT.08.24.20471	Hoke	5	SR 1001 (SHANNON ROAD)	FROM NC 211 TO SR 1449 ((HALL RD)	2	2	2WU	3.46	22	388		37,000		29,600	100																	250		
TOTAL FOR MAP NO. 5								**3.46**		**388**	*	**37,000**		**29,600**	**100**																	**250**		
TOTAL FOR PROJ NO. 2017CPT.08.24.20471								**7.914**		**888**	*	**84,034**		**66,814**	**250**																	**550**		
														67,064																				
2017CPT.08.24.20831	Scotland	6	SR 1131 (X WAY ROAD)	FROM NC 79 TO SR 1108 (ODOM ROAD)	2	2	2WU	3.392	22	380		35,818		28,259	100																	225		
TOTAL FOR MAP NO. 6								**3.392**		**380**		**35,818**		**28,259**	**100**																	**225**		
2017CPT.08.24.20831	Scotland	7	SR 1108 (X WAY ROAD)	FROM SR 1131 (X WAY ROAD TO SR 1269 (LYTCH DRIVE)	2	2	2WU	1.223	22	137		12,916		10,646	50																	85		
TOTAL FOR MAP NO. 7								**1.223**		**137**	*	**12,916**		**10,646**	**50**																	**85**		
TOTAL FOR PROJ NO. 2017CPT.08.24.20831								**4.615**		**517**	*	**48,734**		**38,905**	**150**																	**310**		
														39,055																				
GRAND TOTAL								**27.959**		**3,134**	**1**	**295,354**	**111,685**	**113,944**	**2,265**	**600**	**340**	**150**	**355**	**6**	**1**	**11**	**7**	**1**	**2**	**720**	**133,250**	**164,455**	**600**	**355**	**720**	**860**	**40**	**1,345**
														116,209									**22**				**297,705**						**1,385**	