

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
U-3330	X-1D

Earthwork quantities are calculated by the Roadway Design Unit. These earthwork quantities are based in part on subsurface data provided by the Geotechnical Engineering Unit.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station Phase 4 L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
49+00.0000	0	0
49+50.0000	154	44
50+00.0000	131	6
50+50.0000	119	17
51+00.0000	57	53
51+50.0000	1	91
52+00.0000	1	94
52+50.0000	0	89
53+00.0000	1	78
53+50.0000	3	61
54+00.0000	2	62
54+50.0000	0	85
55+00.0000	0	109
55+50.0000	1	128
56+00.0000	3	156