PROJECT REFERENCE NO.	SHEET NO.
R-5516	1D-1
R/W SHEET NO.	

Prepared in the Office of: AECOM
NC FIRM LICENSE No: F-0342
701 Corporate Center Drive, Suite 475
Raleigh, NC 27607
(919) 854-6200 - (919) 854-6259 FAX)

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CENTERLINE COORDINATE LIST

Point #	Chain	Station	Northing (Y)	Easting (X)
1	YEB01	10+00.00	433288.6509	2615795.4389
2	YEB01	11+00.00	433197.7207	2615837.0507
3	YEB01	12+00.00	433106.2312	2615877.4179
4	YEB01	13+00.00	433014.5127	2615917.2642
5	YEB01	14+00.00	432922.7943	2615957.1105
6	YEB01	15+00.00	432831.0366	2615996.8658
7	YEB01	16+00.00	432738.4522	2616034.6470
8	YEB01	17+00.00	432644.7938	2616069.6810
9	YEB01	18+00.00	432550.1429	2616101.9373
10	YEB01	19+00.00	432454.5818	2616131.3880
11	YEB01	20+00.00	432358.1936	2616158.0074
12	YEB01	21+00.00	432261.0827	2616181.8598
13	YEB01	22+00.00	432163.7730	2616204.8993
14	YEB01	23+00.00	432066.4633	2616227.9389
15	YEB01	24+00.00	431969.4014	2616251.9793
16	YEB01	25+00.00	431874.4289	2616283.1239
17	YEB01	26+00.00	431783.7883	2616325.2222
18	YEB01	27+00.00	431698.8417	2616377.8727
19	YEB01	28+00.00	431620.8118	2616440.3174
20	YEB01	29+00.00	431550.8220	2616511.6575
21	YEB01	30+00.00	431489.8795	2616590.8662
22	YEB01	31+00.00	431438.8617	2616676.8033
23	YEB01	32+00.00	431398.5029	2616768.2317
24	YEB01	33+00.00	431369.3840	2616863.8355
25	YEB01	34+00.00	431351.9242	2616962.2385
26	YEB01	35+00.00	431346.3747	2617062.0243
27	YEB01	36+00.00	431352.7594	2617161.7628
28	YEB01	37+00.00	431367.8384	2617260.6085
29	YEB01	38+00.00	431384.7229	2617359.1728
30	YEB01	39+00.00	431401.6086	2617457.7368
31	YEB01	40+00.00	431418.4943	2617556.3009
32	YEB01	41+00.00	431435.3800	2617654.8650
33	YEB01	42+00.00	431452.2657	2617753.4290
34	YEB01	43+00.00	431469.1514	2617851.9931
35	YEB01	44+00.00	431486.0371	2617950.5571
36	YEB01	45+00.00	431502.5513	2618049.1831
37	YEB01	46+00.00	431516.8466	2618148.1534
38	YEB01	47+00.00	431528.6635	2618247.4501
39	YEB01	48+00.00	431538.5029	2618346.9645
40	YEB01	49+00.00	431548.1803	2618446.4952
41	YEB01	50+00.00	431557.8577	2618546.0258
42	YEB01	51+00.00	431567.5351	2618645.5564
43	YEB01	52+00.00	431577.2125	2618745.0871
44	YEB01	53+00.00	431586.8899	2618844.6177
45	YEB01	54+00.00	431596.5673	2618944.1483
46	YEB01	55+00.00	431606.2447	2619043.6790
47	YEB01	56+00.00	431615.9221	2619143.2096
48	YEB01	57+00.00	431625.5995	2619242.7403
49	YEB01	58+00.00	431635.2769	2619342.2709
50	YEB01	59+00.00	431644.9543	2619441.8015
51	YEB01	60+00.00	431654.6317	2619541.3322
52	LRA	10+00.00	430661.0578	2617275.7026
53	LRA	11+00.00	430747.8524	2617226.0770
54	LRA	12+00.00	430840.3409	2617188.4834
55	LRA	13+00.00	430938.7271	2617171.8110
56	LRA	14+00.00	431038.3517	2617177.5319
57	LRA	15+00.00	431134.1826	2617205.3570
58	LRA	16+00.00	431221.3791	2617253.8809
59	LRA	17+00.00	431295.5367	2617320.6526
60	LRA	18+00.00	431352.9095	2617402.2991
61	LRA	19+00.00	431390.7110	2617494.6621
62	LRA	20+00.00	431412.4093	2617592.2285
63	LRA	20+30.63	431417.6450	2617622.4094
64	LRB	10+00.00	431812.3407	2616620.8618
65	LRB	11+00.00	431723.8696	2616667.4329
66	LRB	12+00.00	431642.4911	2616725.2683
67	LRB	13+00.00	431575.5945	2616799.3133
68	LRB	14+00.00	431526.9237	2616886.4279
69	LRB	15+00.00	431498.8889	2616982.2025
70	LRB	16+00.00	431488.6446	2617081.6072
71	LRB	17+00.00	431485.5764	2617181.5564
72	LRB	18+00.00	431485.2815	2617281.5529
73	LRB	19+00.00	431487.7167	2617381.5201
74	LRB	20+00.00	431492.8803	2617481.3836
75	LRB	21+00.00	431500.7685	2617581.0689
76	LRB	22+00.00	431511.3753	2617680.5017
77	LRB	22+57.97	431518.7657	2617737.9963
78	Y01	10+00.00	431614.1084	2619124.5556
79	Y01	11+00.00	431630.5713	2619223.1117

Point #	Chain	Station	Northing (Y)	Easting (X)
80	Y01	12+00.00	431660.3553	2619318.4912
81	Y01	13+00.00	431689.8856	2619413.9495
82	Y01	13+98.05	431705.8993	2619510.6105
83	Y02	10+00.00	431669.2047	2619133.2119
84	Y02	11+00.00	431682.9648	2619232.2322
85	Y02	12+00.00	431704.4776	2619329.8716
86	Y02	12+25.45	431710.4641	2619354.6055
87	YWB01	10+00.00	431218.3444	2616849.2957
88	YWB01	11+00.00	431314.1511	2616826.9402
89	YWB01	12+00.00	431404.9269	2616864.8669
90	YWB01	13+00.00	431456.3519	2616948.7368
91	YWB01	14+00.00	431462.0545	2617048.3685
92	YWB01	15+00.00	431465.3305	2617148.3137
93	YWB01	16+00.00	431470.2715	2617248.1904
94	YWB01	17+00.00	431476.8762	2617347.9709
95	YWB01	18+00.00	431485.1426	2617447.6274
96	YWB01	19+00.00	431495.0685	2617547.1324
97	YWB01	20+00.00	431506.6511	2617646.4582
98	YWB01	21+00.00	431519.8028	2617745.5889
99	YWB01	22+00.00	431533.3364	2617844.6689
100	YWB01	23+00.00	431546.8700	2617943.7489
101	YWB01	24+00.00	431560.2981	2618042.8430
102	YWB01	25+00.00	431572.2962	2618142.1192
103	YWB01	26+00.00	431582.5124	2618241.5949
104	Y10A	10+00.00	434679.0126	2614719.4153
105	Y10A	11+00.00	434700.3239	2614817.0901
106	Y10A	12+00.00	434717.3424	2614915.6313
107	Y10A	13+00.00	434733.6036	2615014.2981
108	Y10A	14+00.00	434747.3177	2615113.3503
109	Y10A	15+00.00	434758.3998	2615212.7313
110	Y10A	16+00.00	434766.8423	2615312.3714
111	Y10A	17+00.00	434772.7402	2615412.1953
112	Y10A	18+00.00	434777.9447	2615512.0597
113	Y10A	19+00.00	434783.1491	2615611.9242
114	Y10A	20+00.00	434788.3535	2615711.7887
115	Y10A	21+00.00	434793.5580	2615811.6532
116	Y10A	22+00.00	434798.7624	2615911.5177
117	Y10A	23+00.00	434803.9668	2616011.3821
118	Y10A	24+00.00	434809.1713	2616111.2466
119	Y10A	25+00.00	434823.6332	2616210.0472
120	Y10A	26+00.00	434856.2693	2616304.4166
121	Y10A	27+00.00	434905.9344	2616391.0427
122	Y10A	28+00.00	434970.8853	2616466.8852
123	Y10A	29+00.00	435048.8424	2616529.2822
124	Y10A	30+00.00	435137.0697	2616576.0438
125	Y10A	31+00.00	435232.4706	2616605.5287
126	Y10A	32+00.00	435331.0511	2616622.2849
127	Y10A	33+00.00	435429.7161	2616638.5708
128	Y10A	34+00.00	435528.0864	2616656.5253
129	Y10A	35+00.00	435625.8107	2616677.7161
130	Y10A	36+00.00	435722.7826	2616702.1199
131	Y10A	37+00.00	435818.8964	2616729.7103
132	Y10A	38+00.00	435914.0475	2616760.4571
133	Y10A	39+00.00	436008.1322	2616794.3269
134	Y10A	40+00.00	436101.0480	2616831.2829
135	Y10A	41+00.00	436192.7476	2616871.1647
136	Y11A	18+00.00	435634.5184	2616343.1907
137	Y11A	19+00.00	435643.4636	2616442.7521
138	Y11A	20+00.00	435642.5225	2616542.7060
139	Y11A	21+00.00	435631.6074	2616642.0666
140	Y11A	22+00.00	435610.8273	2616739.8411
141	Y11A	23+00.00	435580.3899	2616835.0526
142	Y11A	24+00.00	435541.2768	2616927.0635
143	Y09A	10+00.00	434952.9511	2616448.6848
144	Y09A	11+00.00	434878.3637	2616515.1317
145	Y09A	12+00.00	434787.0083	2616554.1391
146	Y09A	13+00.00	434687.4745	2616562.8441
147	Y09A	14+00.00	434587.6686	2616569.0723
148	Y09A	15+00.00	434487.8628	2616575.3005
149	Y09A	16+00.00	434388.0569	2616581.5287
150	Y09A	17+00.00	434288.2510	2616587.7568
151	Y09A	18+00.00	434188.4452	2616593.9850
152	Y09A	19+00.00	434088.6393	2616600.2132
153	Y09A	20+00.00	433988.8335	2616606.4413
154	Y09A	21+00.00	433889.0276	2616612.6695
155	Y09A	22+00.00	433789.2217	2616618.8977
156	Y09A	23+00.00	433689.6982	2616627.8330

Point #	Chain	Station	Northing (Y)	Easting (X)
157	Y09A	24+00.00	433595.4127	2616660.1195
158	Y09A	25+00.00	433514.0493	2616717.6707
159	Y09A	26+00.00	433452.2047	2616795.8206
160	Y09A	27+00.00	433414.8933	2616888.2328
161	Y09A	28+00.00	433402.0780	2616987.2816
162	Y09A	28+64.57	433396.4325	2617051.6073

Point #	Chain	Station	Northing (Y)	Easting (X)

Point #	Chain	Station	Northing (Y)	Easting (X)

REVISIONS

DATE/TIME: 9/20/13 AM
DGN: R:\Roadway\Proj\r-5516_rdy_peb_01-1.dgn