


**This electronic collection of documents is provided
for the convenience of the user
and is Not a Certified Document –**

**The documents contained herein were originally issued
and sealed by the individuals whose names and license
numbers appear on each page, on the dates appearing
with their signature on that page.**

**This file or an individual page
shall not be considered a certified document.**


TIP PROJECT: R-5516



CRAVEN COUNTY

LOCATION: INTERCHANGE FROM US 70 TO SLOCUM ROAD AT CHERRY POINT MILITARY BASE

TYPE OF WORK: TRAFFIC SIGNALS



CONTRACT:

Sheet #	Reference #	Index of Plans	Location/Description
Sig. 1.0		Title Sheet	
Sig. 2.0-2.3	02-0563T	US 70 at SR 1761 (Hickman Hill Loop Road) / SR 1772 (Pine Grove Road) Temporary	
Sig. 3.0-3.3	02-0563	US 70 at SR 1761 (Hickman Hill Loop Road) / SR 1772 (Pine Grove Road) Final	
Sig. 4.0-4.1	02-0672T	US 70 at Slocum Road Temporary	
Sig. 5.0-5.2	02-0672	US 70 at Slocum Road Final	
Sig. 6.0-6.1	02-0911	US 70 at Hickman Hill Loop Road EB U-turn	
Sig. M1-M8	N/A	Metal Pole Standards	
Scp. 1-10	N/A	Signal Communication Plans	


INTELLIGENT TRANSPORTATION AND SIGNALS UNIT

Contacts:

Gregory A. Fuller, PE - ITS and Signals Engineer
Jason P. Galloway, PE - Eastern Region Signals Engineer
Keith M. Mims, PE - Signal Equipment Design Engineer


Refer to "Roadway Standard Drawings NCDOT" dated January 2012 and "Standard Specifications for Roads and Structures" dated January 2012.

Prepared in the Office of:
DIVISION OF HIGHWAYS
TRANSPORTATION MOBILITY AND SAFETY DIVISION



D:\MAR_2017_09\41... \Design\Signals\R-5516--sig--teh.dgn

PHASING DIAGRAM



PHASING DIAGRAM DETECTION LEGEND

- DETECTED MOVEMENT
- UNDETECTED MOVEMENT (OVERLAP)
- UNSIGNALIZED MOVEMENT
- PEDESTRIAN MOVEMENT

EV PREEMPT PHASES





TABLE OF OPERATION

SIGNAL FACE	PHASE					
	01+5	02+5	02+6	04+8	P	F
11	←	←	←	←	←	←
21,22	R	R	G	G	R	Y
41	R	R	R	R	G	R
42	R	R	R	R	G	R
51	←	←	←	←	←	←
61,62	R	G	R	G	R	Y
81,82	R	R	R	R	G	R

SIGNAL FACE I.D.

All Heads L.E.D.





OASIS 2070 LOOP & DETECTOR INSTALLATION CHART

LOOP	SIZE (FT)	DISTANCE FROM STOPBAR (FT)	TURNS	NEW LOOP	DETECTOR PROGRAMMING				STRETCH TIME	DELAY TIME	SYSTEM LOOP	NEW CARD
					PHASE	CALLING	EXTENSION	FULL TIME DELAY				
1A	6X60	0	*	Y	1	Y	Y	-	-	20	-	Y
2A	6X6	420	*	Y	2	Y	Y	-	-	-	-	Y
2B	6X6	420	*	Y	2	Y	Y	-	-	-	-	Y
2C	6X60	0	*	Y	2	Y	Y	5.0	2	-	-	Y
2D	6X60	0	*	Y	2	Y	Y	5.0	2	-	-	Y
4A	6X30	0	*	Y	4	Y	Y	-	-	3	-	Y
4B	6X30	0	*	Y	4	Y	Y	-	-	10	-	Y
4C	6X30	0	*	Y	4	Y	Y	-	-	10	-	Y
4D	6X30	0	*	Y	4	Y	Y	-	-	10	-	Y
4E	6X30	0	*	Y	4	Y	Y	-	-	10	-	Y
5A	6X60	0	*	Y	5	Y	Y	-	-	20	-	Y
6A	6X6	420	*	Y	6	Y	Y	-	-	-	-	Y
6B	6X6	420	*	Y	6	Y	Y	-	-	-	-	Y
6C	6X60	0	*	Y	6	Y	Y	5.0	2	-	-	Y
6D	6X60	0	*	Y	6	Y	Y	5.0	2	-	-	Y
8A	6X40	0	*	Y	8	Y	Y	-	-	10	-	Y

5 Phase Fully Actuated w/ EV Preempt US 70 (Havelock) CLS

NOTES

- Refer to "Roadway Standard Drawings NCDOT" dated January 2012 and "Standard Specifications for Roads and Structures" dated January 2012.
- Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- Set all detector units to presence mode.
- Locate new cabinet so as not to obstruct sight distance of vehicles turning right on red.
- Flash beacon 1A, 1B continuously.
- This intersection features an optical preemption system. Shown locations of optical detectors are conceptual only.
- Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.
- Closed loop system data: Controller Asset #: 0563.




OASIS 2070 TIMING CHART

FEATURE	PHASE					
	1	2	4	5	6	8
Min Green 1 *	7	14	7	7	14	7
Extension 1 *	2.0	6.0	3.0	2.0	6.0	3.0
Max Green 1 *	15	90	25	15	90	25
Yellow Clearance	3.0	5.3	3.8	3.0	5.3	3.8
Red Clearance	3.1	1.2	2.9	3.1	1.2	2.9
Walk 1 *	-	-	-	-	-	-
Don't Walk 1	-	-	-	-	-	-
Seconds Per Actuation *	-	-	-	-	-	-
Max Variable Initial *	-	-	-	-	-	-
Time Before Reduction *	-	15	-	-	15	-
Time To Reduce *	-	45	-	-	45	-
Minimum Gap	-	3.4	-	-	3.4	-
Recall Mode	-	MIN RECALL	-	-	MIN RECALL	-
Vehicle Call Memory	-	-	-	-	-	-
Dual Entry	-	-	ON	-	-	ON
Simultaneous Gap	ON	ON	ON	ON	ON	ON

OASIS 2070 EV PREEMPT

FUNCTION	PRE 3
Interval 1 - Dwell Green	255
Interval 1 - Dwell Yellow	3.8
Interval 1 - Dwell Red	2.9
Interval 5 - Exit Green	1
Interval 5 - Yellow	0.0
Interval 5 - Red	0.0
Exit Phase(s)	2,6
Priority	Medium
Delay Time	0.0
Min Green Before Pre	1
Ped Clear Before Pre	0
Yellow Clear Before Pre	0.0*
Red Clear Before Pre	0.0*
Dwell Min Time	7
Enable Backup Protection	Y
Ped Clear Through Yellow	N
Omit Overlaps	-
Preempt Extend**	2



Signal Upgrade - Temporary Design (Phase II)

US 70 at SR 1761 (Hickman Hill Loop Rd.) / SR 1772 (Pine Grove Rd.)

Division 2 Craven County Havelock

PLAN DATE: October 2016 REVIEWED BY: JPG

PREPARED BY: KGP, Jr. REVIEWED BY:

REVISIONS: INIT. DATE

SCALE: 1"=40'

750 N. Greenfield Pkwy, Garner, NC 27529

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL: NORTH CAROLINA PROFESSIONAL ENGINEER JASON P. GALLOWAY SEAL 029904

2/2/2017 DATE

SIG. INVENTORY NO. 02-0563T


02-FEB-2017 11:49 C:\p1\proj\02-0563\020563_s.dgn_2016modL_temp.dgn

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

* Time defaults to time used for phase during normal operation ** Program Timing on Optical Detection Unit.

EDI MODEL 2018ECL-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



REMOVE JUMPERS AS SHOWN

NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Connect serial cable from conflict monitor to comm. port 1 of 2070 controller. Ensure conflict monitor communicates with 2070.

NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Program phases 4 and 8 for Dual Entry.
3. Enable Simultaneous Gap-Out for all phases.
4. Program phases 2 and 6 for Gap Reduction.
5. Program phases 2 and 6 for Start Up In Green.
6. Program phases 2 and 6 for Yellow Flash, and overlap 1 as Wag Overlaps.
7. The cabinet and controller are part of the US 70 Havelock CLS.

EQUIPMENT INFORMATION

CONTROLLER.....2070
 CABINET.....332 W/AUX
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....BASE
 OUTPUT FILE POSITIONS...18 (12-STD; 6-AUX)
 LOAD SWITCHES USED.....S1,S2,S5,S7,S8,S10,S11
 AUX S1,AUX S4
 PHASES USED.....1,2,4,5,6,*7,8
 OVERLAP 'A'.....1+2
 OVERLAP 'B'.....NOT USED
 OVERLAP 'C'.....5+6
 OVERLAP 'D'.....NOT USED

* Phase Used During Preempt Only.

SIGNAL HEAD HOOK-UP CHART

LOAD SWITCH NO.	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10	S11	S12	AUX S1	AUX S2	AUX S3	AUX S4	AUX S5	AUX S6
EMU CHANNEL NO.	1	2	13	3	4	14	5	6	15	7	8	16	9	10	17	11	12	18
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED	OLA	OLB	SPARE	OLC	OLD	SPARE
SIGNAL HEAD NO.	11	21,22	NU	NU	41,42	NU	51	61,62	NU	41	81,82	NU	11	NU	NU	51	NU	NU
RED		128			101			134			107							
YELLOW	*	129			102		*	135		*	108							
GREEN		130			103			136			109							
RED ARROW													A121				A114	
YELLOW ARROW													A122				A115	
FLASHING YELLOW ARROW													A123				A116	
GREEN ARROW	127							133			124							


NU = Not Used

* Denotes install load resistor. See load resistor installation detail sheet 2.

* See pictorial of head wiring in detail below.

INPUT FILE POSITION LAYOUT

(front view)



EX.: 1A, 2A, ETC. = LOOP NO.'S


FS = FLASH SENSE
 ST = STOP TIME
 PRE 3 = EV PREEMPTION

SPECIAL DETECTOR NOTE

Install a video detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the detection scheme shown on the Signal Design Plan.


FLASHER WIRING DETAIL

(wire flasher as shown below)



FYA SIGNAL WIRING DETAIL

(wire signal heads as shown)



NOTE

The sequence display for signal heads 11 and 51 require special logic programming. See sheet 2 for programming instructions.

PREEMPT ONLY PHASE OMIT NOTE

(program controller as shown below)

From Main Menu press '2' (Phase Control). Then '1' (Phase Control Functions). Program Phase 7 for 'Omit Phase' and Phases 1, 2, 4, 5, 6 and 8 for 'Startup Calls'. This is to prevent Phase 7 from being served when not in Preempt.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 02-0563T
 DESIGNED: October 2016
 SEALED: 2/2/2017
 REVISED: N/A

Electrical Detail - Temp Design (Phase II) - Sheet 1 of 3

ELECTRICAL AND PROGRAMMING DETAILS FOR: Prepared In the Offices of: TRANSPORTATION MOBILITY AND SAFETY SOLUTIONS, INC. 750 N. Greenfield Pkwy, Garner, NC 27529	US 70 at SR 1761 (Hickman Hill Loop Rd.) / SR 1772 (Pine Grove Rd.)		SEAL ZACHARY M. LITTLE ENGINEER STATE OF NORTH CAROLINA LICENSE NO. 030530
	Division 2 PLAN DATE: January 2017 PREPARED BY: B. SIMMONS	Craven County REVIEWED BY: Havelock	


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

S:\11-2017-13-16-SIGNALS\02-0563T\SIGNALS\02-0563T\Division 02-0563T_sme.ele_xxxx.dgn
 bjsimmons


LOGICAL I/O PROCESSOR PROGRAMMING DETAIL TO PRODUCE SPECIAL FYA SIGNAL SEQUENCE

(program controller as shown below)


- From Main Menu press '2' (PHASE CONTROL), then '1' (PHASE CONTROL FUNCTIONS). Scroll to the bottom of the menu and Enable ACT Logic Commands 1, 2, 3, 4, 5 and 6.
- From Main Menu press '6' (OUTPUTS), then '3' (LOGICAL I/O PROCESSOR).




NOTE: Logic for Phase 1 RED Clear when transitioning from Phase 1 to Phase 2 (Head 11).




NOTE: Logic for Switching Flashing Yellow Arrow "OFF" during Phase 1 (Head 11).




NOTE: Logic for Yellow Arrow Clearance from Phase 1 (Head 11).



NOTE: Logic for Phase 5 RED Clear when transitioning from Phase 5 to Phase 6 (Head 51).



NOTE: Logic for Switching Yellow Flashing Arrow "OFF" during Phase 5 (Head 51).



NOTE: Logic for Yellow Arrow Clearance from Phase 5 (Head 51).

LOGIC I/O PROCESSOR PROGRAMMING COMPLETE

OUTPUT REFERENCE SCHEDULE

USE TO INTERPRET LOGIC PROCESSOR

OUTPUT 42 = Overlap C Red
OUTPUT 43 = Overlap C Yellow
OUTPUT 44 = Overlap C Green
OUTPUT 50 = Overlap A Red
OUTPUT 51 = Overlap A Yellow
OUTPUT 52 = Overlap A Green

OVERLAP PROGRAMMING DETAIL

(program controller as shown below)

From Main Menu press '8' (OVERLAPS), then '1' (VEHICLE OVERLAP SETTINGS).

PAGE 1: VEHICLE OVERLAP 'A' SETTINGS
PHASE: |12345678910111213141516
VEH OVL PARENTS: |XX
VEH OVL NOT VEH: |
VEH OVL NOT PED: |
VEH OVL GRN EXT: |
STARTUP COLOR: - RED - YELLOW - GREEN
FLASH COLORS: - RED - YELLOW X GREEN
SELECT VEHICLE OVERLAP OPTIONS: (Y/N)
FLASH YELLOW IN CONTROLLER FLASH?...Y
GREEN EXTENSION (0-255 SEC)...0
YELLOW CLEAR (0=PARENT,3-25.5 SEC)...0.0
RED CLEAR (0=PARENT,0.1-25.5 SEC)...0.0
OUTPUT AS PHASE # (0=NONE, 1-16)...0

← NOTICE GREEN FLASH


PRESS '+' TWICE

PAGE 1: VEHICLE OVERLAP 'C' SETTINGS
PHASE: |12345678910111213141516
VEH OVL PARENTS: |XX
VEH OVL NOT VEH: |
VEH OVL NOT PED: |
VEH OVL GRN EXT: |
STARTUP COLOR: - RED - YELLOW - GREEN
FLASH COLORS: - RED - YELLOW X GREEN
SELECT VEHICLE OVERLAP OPTIONS: (Y/N)
FLASH YELLOW IN CONTROLLER FLASH?...Y
GREEN EXTENSION (0-255 SEC)...0
YELLOW CLEAR (0=PARENT,3-25.5 SEC)...0.0
RED CLEAR (0=PARENT,0.1-25.5 SEC)...0.0
OUTPUT AS PHASE # (0=NONE, 1-16)...0

← NOTICE GREEN FLASH


OVERLAP PROGRAMMING COMPLETE

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 02-0563T
DESIGNED: October 2016
SEALED: 2/2/2017
REVISED: N/A



LOAD RESISTOR INSTALLATION DETAIL

VALUE (ohms)	WATTAGE
1.5K - 1.9K	25W (min)
2.0K - 3.0K	10W (min)



Electrical Detail - Temp Design (Phase II) - Sheet 2 of 3

ELECTRICAL AND PROGRAMMING DETAILS FOR: Prepared In the Offices of: 750 N. Greenfield Pkwy, Garner, NC 27529	US 70 at SR 1761 (Hickman Hill Loop Rd.) / SR 1772 (Pine Grove Rd.)		SEAL NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 030530 JACOBARY M. LITTLE	
	Division 2 PLAN DATE: January 2017 PREPARED BY: B. SIMMONS	Craven County REVIEWED BY: REVIEWED BY:		HaveLock DATE: 2/21/2017 DATE:
	REVISIONS			INIT. DATE DATE

DocuSign by: *Jacobary M. Little* 2/21/2017
 02-0563T-02-0563T-02-0563T
 SIG. INVENTORY NO. 02-0563T

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

02-0563-2017-02-29
 C:\Users\simmons\Documents\Working Folder\Electrical\Division 02\020563-smc.ele_xxxx.dgn
 bjsimmons

EMERGENCY VEHICLE PREEMPTION PROGRAMMING DETAIL

(program controller as shown below)

From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions). Press 'NEXT' to advance to Preemption #3.

```

PREEMPTION #3 SETTINGS (NEXT:1-10)
INTERVAL/TIMING CLEAR/DWELL PHASES
GRN YEL RED 12345678910111213141516
1 255 3.8 2.9 X X
2 0 0.0 0.0
3 0 0.0 0.0
4 0 0.0 0.0
5 1 0.0 0.0 X X
EXIT CALLS

PRIORITY (Y/N TO SELECT) .....MED
DELAY TIMER (0-255 SEC) .....0
MIN GREEN BEFORE PRE (0= DEFAULT)...1
PED CLEAR BEFORE PRE (0= DEFAULT)...0
YELLOW CLEAR BEFORE PRE (0= DEFAULT)...0.0
RED CLEAR BEFORE PRE (0= DEFAULT)...0.0
DWELL MIN TIMER (0-255 SEC) .....7
DWELL MAX TIMER (0=OFF,1-255MIN) ...0
DWELL HOLD-OVER TIMER (0-255) .....0
LATCH CALL? .....N
LINK TO NEXT PREEMPT? .....N
ENABLE BACKUP PROTECTION? .....Y
HOLD CLEAR 1 PHASES DURING DELAY? ..N
FAST GREEN FLASH DWELL PHASES? .....N
PED CLEARANCE THROUGH YELLOW? .....N
INHIBIT OVERLAP GREEN EXTENSION? ...N
SERVICE DURING SOFTWARE FLASH? .....N
REST IN RED DURING DWELL INTERVAL? ..N
FLASH DWELL INTERVAL? .....N
ALLOW PEDS IN DWELL INTERVAL? .....N
RE-TIME DWELL INTERVAL? .....N
OVERLAPS: ABCDEFGHIJKLMNPO
DWELL INT FLASH YELLOW
OMIT OVERLAPS:

```

Program extend time on optical detector unit for 2.0 sec for EVP3.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 02-0563T
DESIGNED: October 2016
SEALED: 2/2/2017
REVISED: N/A


02-0563-2017_09:30
S:\ITS\2017\ITS\Sig\Workgroups\Sig_Mark\Simmons\Working_Folder\Electrical_Detail\02-0563_sme_ele_xxx.dgn
bjj\simmons

Electrical Detail - Temp Design (Phase II) - Sheet 3 of 3

<p style="font-size: small;">ELECTRICAL AND PROGRAMMING DETAILS FOR:</p> <p style="font-size: x-small;">Prepared In the Offices of:</p> <p style="font-size: x-small;">750 N. Greenfield Pkwy, Garner, NC 27529</p>	<p>US 70 at SR 1761 (Hickman Hill Loop Rd.) / SR 1772 (Pine Grove Rd.)</p> <p style="font-size: x-small;">Division 2 Craven County HaveLock</p> <p style="font-size: x-small;">PLAN DATE: January 2017 REVIEWED BY:</p> <p style="font-size: x-small;">PREPARED BY: B. SIMMONS REVIEWED BY:</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="font-size: x-small;">REVISIONS</th> <th style="font-size: x-small;">INIT.</th> <th style="font-size: x-small;">DATE</th> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </table>	REVISIONS	INIT.	DATE				<p>SEAL</p> <p style="font-size: x-small;">DocuSigned by: <i>Cary M. Little</i> 2/21/2017 02-0563-2017</p> <p style="font-size: x-small;">SIG. INVENTORY NO. 02-0563T</p>
REVISIONS	INIT.	DATE						

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

PHASING DIAGRAM



EV PREEMPT PHASES






TABLE OF OPERATION

SIGNAL FACE	PHASE			
	Ø 2+6	Ø 4+8	P L S H	F L S H
21,22,23	G	R	R	Y
41	R	G	G	R
42,43	R	G	G	R
61,62,63	G	R	R	Y
81,82,83	R	G	R	R

TABLE OF OPERATION

SIGNAL FACE	INTERVAL	
	1	2
24,26	ON	OFF
25,27	OFF	ON

SIGNAL FACE I.D.




OASIS 2070 LOOP & DETECTOR INSTALLATION CHART

LOOP	SIZE (FT)	DISTANCE FROM STOPBAR (FT)	TURNS	NEW LOOP	DETECTOR PROGRAMMING							
					PHASE	CALLING	EXTENSION	FULL TIME DELAY	STRETCH TIME	DELAY TIME	SYSTEM LOOP	NEW CARD
2A	6X6	420	6	Y	2	Y	Y	-	-	-	-	Y
2B	6X6	420	6	Y	2	Y	Y	-	-	-	-	Y
2C	6X6	420	6	Y	2	Y	Y	-	-	-	-	Y
4A	6X40	0	2-4-2	Y	4	Y	Y	-	-	3	-	Y
4B	6X40	0	2-4-2	Y	4	Y	Y	-	-	15	-	Y
6A	6X6	420	6	Y	6	Y	Y	-	-	-	-	Y
6B	6X6	420	6	Y	6	Y	Y	-	-	-	-	Y
6C	6X6	420	6	Y	6	Y	Y	-	-	-	-	Y
8A	6X40	0	2-4-2	Y	8	Y	Y	-	-	3	-	Y
8B	6X40	0	2-4-2	Y	8	Y	Y	-	-	15	-	Y
S1	6X6	+230	4	Y	-	-	-	-	-	-	-	Y
S2	6X6	+230	4	Y	-	-	-	-	-	-	-	Y
S3	6X6	+230	4	Y	-	-	-	-	-	-	-	Y

2 Phase Fully Actuated w/ EV Preempt US 70 (Havelock) CLS

NOTES

- Refer to "Roadway Standard Drawings NCDOT" dated January 2012 and "Standard Specifications for Roads and Structures" dated January 2012.
- Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- Set all detector units to presence mode.
- Locate new cabinet so as not to obstruct sight distance of vehicles turning right on red.
- Flash beacons numbered 24, 25, 26, 27 two seconds prior to the end of phase 2 green.
- This intersection features an optical preemption system. Shown locations of optical detectors are conceptual only.
- Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.
- Closed loop system data: Controller Asset #: 0563.



OASIS 2070 TIMING CHART



FEATURE	PHASE			
	2	4	6	8
Min Green 1 *	14	7	14	7
Extension 1 *	6.0	1.0	6.0	1.0
Max Green 1 *	45	20	45	20
Yellow Clearance	5.3	3.8	5.3	3.8
Red Clearance	1.9	3.3	1.9	3.3
Walk 1 *	-	-	-	-
Don't Walk 1	-	-	-	-
Seconds Per Actuation *	1.2	-	1.2	-
Max Variable Initial *	46	-	46	-
Time Before Reduction *	15	-	15	-
Time To Reduce *	45	-	45	-
Minimum Gap	3.4	-	3.4	-
Recall Mode	MIN RECALL	-	MIN RECALL	-
Vehicle Call Memory	YELLOW	-	YELLOW	-
Dual Entry	-	ON	-	ON
Simultaneous Gap	ON	ON	ON	ON

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

OASIS 2070 EV PREEMPT

FUNCTION	PRE 3
Interval 1 - Dwell Green	255
Interval 1 - Dwell Yellow	3.8
Interval 1 - Dwell Red	3.3
Interval 5 - Exit Green	1
Interval 5 - Yellow	0.0
Interval 5 - Red	0.0
Exit Phase(s)	2,6
Priority	Medium
Delay Time	0.0
Min Green Before Pre	1
Ped Clear Before Pre	0
Yellow Clear Before Pre	0.0*
Red Clear Before Pre	0.0*
Dwell Min Time	7
Enable Backup Protection	Y
Ped Clear Through Yellow	N
Omit Overlaps	-
Preempt Extend**	2

* Time defaults to time used for phase during normal operation ** Program Timing on Optical Detection Unit.



Signal Upgrade - Final

US 70 at SR 1761 (Hickman Hill Loop Rd.) / SR 1772 (Pine Grove Rd.)

Division 2 Craven County Havelock

PLAN DATE: October 2016 PREPARED BY: KGP, Jr. REVIEWED BY: JPG

750 N. Greenfield Pkwy, Garner, NC 27529

SCALE: 1" = 40'

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL: JASON P. GALLON, PROFESSIONAL ENGINEER, No. 029904


DATE: 2/8/2017

SIG. INVENTORY NO. 02-0563

08-FEB-2017 12:21 R:\Projects\0563\Signal\Signal\0563_Sig.dgn...2016madd_fm.dgn kgspeed



**EDI MODEL 2018ECL-NC CONFLICT MONITOR
PROGRAMMING DETAIL**

(remove jumpers and set switches as shown)



NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Connect serial cable from conflict monitor to comm. port 1 of 2070 controller. Ensure conflict monitor communicates with 2070.



NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Program phases 4 and 8 for Dual Entry.
3. Enable Simultaneous Gap-Out for all phases.
4. Program phases 2 and 6 for Variable Initial and Gap Reduction.
5. Program phases 2 and 6 for Start Up In Green.
6. Program phases 2 and 6 for Yellow Flash.
7. The cabinet and controller are part of the US 70 Havelock CLS.

EQUIPMENT INFORMATION

CONTROLLER.....2070
 CABINET.....332 W/ AUX
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....BASE
 OUTPUT FILE POSITIONS...18 (12-STD; 6-AUX)
 LOAD SWITCHES USED.....S2,**S3,S5,S8,**S9,S10,S11
 PHASES USED.....2,4,6,*7,8
 OVERLAP 'A'.....NOT USED
 OVERLAP 'B'.....NOT USED
 OVERLAP 'C'.....NOT USED
 OVERLAP 'D'.....NOT USED

* Phase Used During Preempt Only.
 ** Used For Advance Beacon Only.

SIGNAL HEAD HOOK-UP CHART

LOAD SWITCH NO.	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10	S11	S12	AUX S1	AUX S2	AUX S3	AUX S4	AUX S5	AUX S6
CMU CHANNEL NO.	1	2	13	3	4	14	5	6	15	7	8	16	9	10	17	11	12	18
PHASE	1	2	ADVANCE BEACON	3	4	PED	5	6	ADVANCE BEACON	7	8	PED	OLA	OLB	SPARE	OLC	OLD	SPARE
SIGNAL HEAD NO.	NU	21,22 23	24,26	NU	41,42 43	NU	NU	61,62 63	25,27	41	81,82 83	NU	NU	NU	NU	NU	NU	NU
RED		128			101			134			107							
YELLOW		129			102			135		*	108							
GREEN		130			103			136			109							
RED ARROW																		
YELLOW ARROW																		
FLASHING YELLOW ARROW																		
GREEN ARROW										124								
PED YELLOW					**	**				**	**							
					114	120				*								

NU = Not Used

* Denotes install load resistor. See load resistor installation detail this sheet.

** Special advance beacons will be wired to S2P-Y and S6P-Y. See wiring and programming details on sheet 2 of this electrical detail.

INPUT FILE POSITION LAYOUT

(front view)


FILE	1	2	3	4	5	6	7	8	9	10	11	12	13	14
U	∅ 2	∅ 2	∅ 2	∅ 4	∅ 4	∅ 8	∅ 8	∅ 8	SYS. DET. S1	PRE 3	FS	DC ISOLATOR	DC ISOLATOR	FS
L	2A	2C	2B	4A	4B	8A	8B	8B	SYS. DET. S2	Opticom 2 Ch. Card	NOT USED	NOT USED	NOT USED	NOT USED
U	∅ 6	∅ 6	∅ 6	∅ 8	∅ 8	∅ 8	∅ 8	∅ 8	SYS. DET. S3	NOT USED	NOT USED	NOT USED	NOT USED	NOT USED
L	6A	6C	6B	8A	8B	8B	8B	8B	NOT USED	NOT USED	NOT USED	NOT USED	NOT USED	NOT USED

EX.: 1A, 2A, ETC. = LOOP NO.'S

FS = FLASH SENSE
 ST = STOP TIME
 PRE 3 = EV PREEMPTION

TYPICAL OPTICOM FIELD WIRE DETAIL

(input file, rear view)




INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	INPUT ASSIGNMENT NO.	DETECTOR NO.	NEMA PHASE	CALL	EXTEND	FULL TIME DELAY	STRETCH TIME	DELAY TIME
2A	TB2-5,6	I2U	39	1	2	2	Y	Y			
2B	TB2-7,8	I2L	43	5	12	2	Y	Y			
2C	TB2-9,10	I3U	63	25	32	2	Y	Y			
4A	TB4-9,10	I6U	41	3	4	4	Y	Y			
4B	TB4-11,12	I6L	45	7	14	4	Y	Y			3
6A	TB3-5,6	J2U	40	2	6	6	Y	Y			
6B	TB3-7,8	J2L	44	6	16	6	Y	Y			
6C	TB3-9,10	J3U	64	26	36	6	Y	Y			
8A	TB5-9,10	J6U	42	4	8	8	Y	Y			3
8B	TB5-11,12	J6L	46	8	18	8	Y	Y			15
* S1	TB6-9,10	I9U	60	22	11	SYS					
* S2	TB6-11,12	I9L	62	24	13	SYS					
* S3	TB7-9,10	J9U	59	21	15	SYS					

* System detector only. Remove the vehicle phase assigned to this detector in the default programming.

INPUT FILE POSITION LEGEND: J2L




PREEMPT ONLY PHASE OMIT NOTE

(program controller as shown below)

From Main Menu press '2' (Phase Control). Then '1' (Phase Control Functions). Program Phase 7 for 'Omit Phase' and Phases 2, 4, 6 and 8 for 'Startup Calls'. This is to prevent Phase 7 from being served when not in Preempt.

LOAD RESISTOR INSTALLATION DETAIL

VALUE (ohms)	WATTAGE
1.5K - 1.9K	25W (min)
2.0K - 3.0K	10W (min)



THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 02-0563
 DESIGNED: October 2016
 SEALED: 2/8/2017
 REVISED: N/A

Electrical Detail - Final - Sheet 1 of 3

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Prepared In the Offices of:
 TRANSPORTATION MOBILITY AND SAFETY ADMINISTRATION
 NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
 Signal Management Section
 750 N. Greenfield Pkwy, Garner, NC 27529

US 70 at SR 1761 (Hickman Hill Loop Rd.) / SR 1772 (Pine Grove Rd.)
 Division 2 Craven County Havelock
 PLAN DATE: January 2017 REVIEWED BY:
 PREPARED BY: B. SIMMONS REVIEWED BY:
 REVISIONS INIT. DATE
 2/21/2017
 DATE
 SIG. INVENTORY NO. 02-0563

02-0563-2017-08-51
 S:\IT\SIG\SIG\Signal\working\working\Folder\Electrical\Detail\02-0563_sme.ele_xxx.dgn
 bjs/simmons

ADVANCE BEACON OUTPUT ASSIGNMENT PROGRAMMING DETAIL

(program controller as shown below)

FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '1' (OUTPUT ASSIGNMENTS). PRESS '+' UNTIL OUTPUT #33 (PIN 35) IS REACHED.

```

PAGE:1 C1 PIN:35 NOT ENABLED
OUTPUT ASSIGNMENT #.....33
FREQUENCY (0=DEFAULT) (0-25.5 HZ)...1.0
DUTY CYCLE (0=DEFAULT) (0 - 100%)...50
MODE (0=SOLID,1=FLASH).....1
SELECT ASSIGNMENT:
NOT ENABLED.....Y
VEHICLE PHASE.....
PEDESTRIAN PHASE.....
VEHICLE OVERLAP.....
PEDESTRIAN OVERLAP.....
WATCHDOG.....
DETECTOR RESET.....
ADVANCE BEACON.....Y
OUT OF PHASE FLASHER.....
CONTROLLER FLASH.....
RUN FREE.....
RESERVED.....
PREEMPT.....
SOFT PREEMPT.....
ANY PREEMPT.....
COORDINATION PLAN.....
OFFSET.....
PHASE CHECK.....
PHASE ON.....
PHASE NEXT.....
    
```

THE FIRST THREE PROGRAMMING ROWS DEFINE THE OUTPUT TO FLASH, ALONG WITH THE RATE IN WHICH IT WILL FLASH.

THE NOT ENABLED 'Y' WILL REMAIN UNTIL THE FUNCTION OF THIS OUTPUT IS CHANGED. DO NOT ENTER AN 'N'.

```

PAGE:1 C1 PIN:35 NOT ENABLED
SELECT BEACON INDEX (1-4).....1
    
```

WHEN A 'Y' IS ENTERED FOR 'ADVANCE BEACON' THE SCREEN SHOWN ABOVE WILL APPEAR. ENTER DATA AS SHOWN.

PRESS THE 'ENT' KEY AFTER INPUTTING DATA, THEN 'ESC'.

DISPLAY WILL NOW SHOW THE SPECIFIED OUTPUT ASSIGNED AS 'ADVANCE BEACON' AS SHOWN BELOW.

```

PAGE:1 C1 PIN:35 ADVANCE BEACON
OUTPUT ASSIGNMENT #.....33
FREQUENCY (0=DEFAULT) (0-25.5 HZ)...1.0
DUTY CYCLE (0=DEFAULT) (0 - 100%)...50
MODE (0=SOLID,1=FLASH).....1
SELECT ASSIGNMENT:
NOT ENABLED.....
VEHICLE PHASE.....
PEDESTRIAN PHASE.....
VEHICLE OVERLAP.....
PEDESTRIAN OVERLAP.....
WATCHDOG.....
DETECTOR RESET.....
ADVANCE BEACON.....Y
OUT OF PHASE FLASHER.....
CONTROLLER FLASH.....
RUN FREE.....
RESERVED.....
PREEMPT.....
SOFT PREEMPT.....
ANY PREEMPT.....
COORDINATION PLAN.....
OFFSET.....
PHASE CHECK.....
PHASE ON.....
PHASE NEXT.....
    
```

FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '1' (OUTPUT ASSIGNMENTS). PRESS '+' UNTIL OUTPUT #34 (PIN 36) IS REACHED.

```

PAGE:1 C1 PIN:36 NOT ENABLED
OUTPUT ASSIGNMENT #.....34
FREQUENCY (0=DEFAULT) (0-25.5 HZ)...0.0
DUTY CYCLE (0=DEFAULT) (0 - 100%)...0
MODE (0=SOLID,1=FLASH).....0
SELECT ASSIGNMENT:
NOT ENABLED.....Y
VEHICLE PHASE.....
PEDESTRIAN PHASE.....
VEHICLE OVERLAP.....
PEDESTRIAN OVERLAP.....
WATCHDOG.....
DETECTOR RESET.....
ADVANCE BEACON.....
OUT OF PHASE FLASHER.....Y
CONTROLLER FLASH.....
RUN FREE.....
RESERVED.....
PREEMPT.....
SOFT PREEMPT.....
ANY PREEMPT.....
COORDINATION PLAN.....
OFFSET.....
PHASE CHECK.....
PHASE ON.....
PHASE NEXT.....
    
```

THE NOT ENABLED 'Y' WILL REMAIN UNTIL THE FUNCTION OF THIS OUTPUT IS CHANGED. DO NOT ENTER AN 'N'.

```

PAGE:1 C1 PIN:36 NOT ENABLED
SELECT OUTPUT ASSIGNMENT (1-64).....33
    
```

WHEN A 'Y' IS ENTERED FOR 'OUT OF PHASE FLASHER' THE SCREEN SHOWN ABOVE WILL APPEAR. ENTER DATA AS SHOWN.

PRESS THE 'ENT' KEY AFTER INPUTTING DATA, THEN 'ESC'.


DISPLAY WILL NOW SHOW THE SPECIFIED OUTPUT ASSIGNED AS 'OUT OF PHASE FLASHER' AS SHOWN BELOW.

```


PAGE:1 C1 PIN:36 OUT OF PHASE FLASHER
OUTPUT ASSIGNMENT #.....34
FREQUENCY (0=DEFAULT) (0-25.5 HZ)...0.0
DUTY CYCLE (0=DEFAULT) (0 - 100%)...0
MODE (0=SOLID,1=FLASH).....0
SELECT ASSIGNMENT:
NOT ENABLED.....
VEHICLE PHASE.....
PEDESTRIAN PHASE.....
VEHICLE OVERLAP.....
PEDESTRIAN OVERLAP.....
WATCHDOG.....
DETECTOR RESET.....
ADVANCE BEACON.....
OUT OF PHASE FLASHER.....Y
CONTROLLER FLASH.....
RUN FREE.....
RESERVED.....
PREEMPT.....
SOFT PREEMPT.....
ANY PREEMPT.....
COORDINATION PLAN.....
OFFSET.....
PHASE CHECK.....
PHASE ON.....
PHASE NEXT.....
    
```

OUTPUT REFERENCE SCHEDULE	
OUTPUT 33	= Ø 2 Ped Yellow
OUTPUT 34	= Ø 6 Ped Yellow

ADVANCE BEACON #1 WIRING DETAIL (wire flashers as shown below)



- IMPORTANT**
- REMOVE, TAPE AND LABEL CONFLICT MONITOR WIRE ATTACHED TO THE REAR OF TERMINAL 114 (2PY) AND TERMINAL 120 (6PY).
 - INSERT LOADSWITCH FOR S2P AND S6P.
 - MAKE SURE LOAD RESISTORS ARE IN PLACE AS SHOWN IN LOAD RESISTOR INSTALLATION DETAIL ON THIS SHEET.
 - TO ACTIVATE SIGN OPERATION AS INDICATED ON THE SIGNAL PLANS, REASSIGN OUTPUT 33 AND 34 AS SHOWN ON THIS SHEET.



ADVANCE BEACON PROGRAMMING DETAIL

(program controller as shown below)

- FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '2' (OUTPUT BEACON SETTINGS).

```

          OUTPUT BEACON SETTINGS
TRIGGER PHASES: 12345678910111213141516
BEACON #1 OFF      X
BEACON #2 OFF
BEACON #3 OFF
BEACON #4 OFF
          BEACON 1 2 3 4
OFF DELAY TIME (0-255) 0 0 0 0
ON DELAY TIME (0-255)  0 0 0 0
STOP-TIME HOLD (0-255) 2 0 0 0
    
```

SCROLL DOWN TO VIEW ALL DATA

ADVANCE BEACON PROGRAMMING COMPLETE

← NOTICE STOP-TIME HOLD SETTINGS FOR BEACON #1

NOTE: AN OUTPUT HAS TO BE ASSIGNED AS AN ADVANCE BEACON IN ORDER FOR PROPER OPERATION TO OCCUR. SEE OUTPUT ASSIGNMENT DETAIL ON THIS SHEET.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 02-0563
DESIGNED: October 2016
SEALED: 2/8/2017
REVISED: N/A

Electrical Detail - Final - Sheet 2 of 3

<p>Electrical and Programming Details For:</p> <p>Prepared In the Offices of:</p> <p>750 N. Greenfield Pkwy, Garner, NC 27529</p>	<p>US 70 at SR 1761 (Hickman Hill Loop Rd.) / SR 1772 (Pine Grove Rd.)</p> <p>Division 2 Craven County HaveLock</p> <p>PLAN DATE: January 2017 REVIEWED BY:</p> <p>PREPARED BY: B. SIMMONS REVIEWED BY:</p> <p>REVISIONS</p>	<p>DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED</p> <p>SEAL</p> <p>DocuSign by: Cary M. Little 2/21/2017</p> <p>SIG. INVENTORY NO. 02-0563</p>
---	--	---

08-FEB-2017 13:53 S:\IT\SS\1715_Signal\work\hous\sig_Mark\Simmons\working_Folder\Electrical_Details\020563_sme.ele_xxx.dgn bjs/simmons

**EMERGENCY VEHICLE PREEMPTION
PROGRAMMING DETAIL**

(program controller as shown below)

From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions). Press 'NEXT' to advance to Preemption #3.

PREEMPTION #3	SETTINGS (NEXT:1-10)
INTERVAL/TIMING	CLEAR/DWELL PHASES
GRN YEL RED	12345678910111213141516
1 255 3.8 3.3	X X
2 0 0.0 0.0	
3 0 0.0 0.0	
4 0 0.0 0.0	
5 1 0.0 0.0	X X

EXIT CALLS



PRIORITY (Y/N TO SELECT)MED
 DELAY TIMER (0-255 SEC)0
 MIN GREEN BEFORE PRE (0= DEFAULT)...1
 PED CLEAR BEFORE PRE (0= DEFAULT)...0
 YELLOW CLEAR BEFORE PRE (0= DEFAULT)...0.0
 RED CLEAR BEFORE PRE (0= DEFAULT)...0.0
 DWELL MIN TIMER (0-255 SEC)7
 DWELL MAX TIMER (0=OFF,1-255MIN) ...0
 DWELL HOLD-OVER TIMER (0-255)0
 LATCH CALL?N
 LINK TO NEXT PREEMPT?N
 ENABLE BACKUP PROTECTION?Y
 HOLD CLEAR 1 PHASES DURING DELAY? ..N
 FAST GREEN FLASH DWELL PHASES?N
 PED CLEARANCE THROUGH YELLOW?N
 INHIBIT OVERLAP GREEN EXTENSION? ..N
 SERVICE DURING SOFTWARE FLASH?N
 REST IN RED DURING DWELL INTERVAL? ..N
 FLASH DWELL INTERVAL?N
 ALLOW PEDS IN DWELL INTERVAL?N
 RE-TIME DWELL INTERVAL?N
 OVERLAPS: ABCDEFGHIJKLMNPO
 DWELL INT FLASH YELLOW
 OMIT OVERLAPS:

Program extend time on optical
detector unit for 2.0 sec for EVP3.

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 02-0563
DESIGNED: October 2016
SEALED: 2/8/2017
REVISED: N/A


Electrical Detail - Final - Sheet 3 of 3

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

ELECTRICAL AND PROGRAMMING DETAILS FOR: Prepared In the Offices of:  750 N. Greenfield Pkwy, Garner, NC 27529	US 70 at SR 1761 (Hickman Hill Loop Rd.) / SR 1772 (Pine Grove Rd.)		SEAL 
	Division 2 PLAN DATE: January 2017 PREPARED BY: B. SIMMONS	Craven County REVIEWED BY: HaveLock REVIEWED BY:	HaveLock REVISIONS INIT. DATE DATE

02-0563-2017-13-52
S:\ITS\SSU\ITS_Signal\working\pous\sig\Map\Simmons\working\Folder\Electrical\Detail\02-0563-smc.ele_xxx.dgn
bjjsimmons

PHASING DIAGRAM




PHASING DIAGRAM DETECTION LEGEND

- ← ● DETECTED MOVEMENT
- ← ○ UNDETECTED MOVEMENT (OVERLAP)
- ← - - - UNSIGNALIZED MOVEMENT
- ← - - - PEDESTRIAN MOVEMENT

SIGNAL FACE	PHASE			
	02+5	02+6	04	F L E S H
21,22	G	G	R	Y
41	R	R	G	R
42	R	R	G	R
51	-	-	-	-
61,62	R	G	R	Y

SIGNAL FACE I.D.

All Heads L.E.D.




OASIS 2070 LOOP & DETECTOR INSTALLATION CHART												
LOOP	SIZE (FT)	DISTANCE FROM STOPBAR (FT)	TURNS	NEW LOOP	DETECTOR PROGRAMMING							
					PHASE	CALLING	EXTENSION	FULL TIME DELAY	STRETCH TIME	DELAY TIME	SYSTEM LOOP	NEW CARD
2A	6X6	420	6	Y	2	Y	Y	-	-	-	-	Y
2B	6X6	420	6	Y	2	Y	Y	-	-	-	-	Y
4A	6X40	0	2-4-2	Y	4	Y	Y	-	-	-	-	Y
5A	6X40	0	2-4-2	Y	5	Y	Y	-	-	-	-	Y
5B	6X40	0	2-4-2	Y	5	Y	Y	-	-	-	-	Y
6A	6X6	420	6	Y	6	Y	Y	-	-	-	-	Y
6B	6X6	420	6	Y	6	Y	Y	-	-	-	-	Y

3 Phase Fully Actuated Havelock CLS

NOTES

1. Refer to "Roadway Standard Drawings NCDOT" dated January 2012 and "Standard Specifications for Roads and Structures" dated January 2012.
2. Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
3. Phase 5 may be lagged.
4. Set all detector units to presence mode.
5. Locate new cabinet so as not to obstruct sight distance of vehicles turning right on red.
6. Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.
7. Closed loop system data: Controller Asset #: 0672.



FEATURE	PHASE			
	2	4	5	6
Min Green 1 *	14	7	7	14
Extension 1 *	6.0	2.0	2.0	6.0
Max Green 1 *	90	20	25	90
Yellow Clearance	5.3	3.0	3.0	5.3
Red Clearance	1.0	3.1	3.5	1.0
Walk 1 *	-	-	-	-
Don't Walk 1	-	-	-	-
Seconds Per Actuation *	1.5	-	-	1.5
Max Variable Initial *	46	-	-	46
Time Before Reduction *	15	-	-	15
Time To Reduce *	30	-	-	30
Minimum Gap	3.4	-	-	3.4
Recall Mode	MIN RECALL	-	-	MIN RECALL
Vehicle Call Memory	YELLOW	-	-	YELLOW
Dual Entry	-	-	-	-
Simultaneous Gap	ON	ON	ON	ON

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

PROPOSED	EXISTING
	N/A
N/A	
	NA
	NA
	NA
	NA

Signal Upgrade - Temporary Design (Phase II)

Prepared in the Offices of:

750 N. Greenfield Pkwy, Garner, NC 27529

US 70 at Slocum Road

Division 2 Craven County Havelock

PLAN DATE: October 2016 REVIEWED BY: JPG

PREPARED BY: KGP, Jr. REVIEWED BY:

REVISIONS: _____ INIT. DATE

SCALE: 0 40
1" = 40'

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL



Jason P. Gallaway 2/1/2017

SIG. INVENTORY NO. 02-0672T

2/1/2017 1:52:33
 R:\Projects\02-0672\02-0672-01\Drawings\Signal\Signal Upgrade - Temporary Design.dgn
 KGP:edf
 KGP:edf

EDI MODEL 2018ECL-NC CONFLICT MONITOR
PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



- NOTES:
- Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
 - Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
 - Ensure that Red Enable is active at all times during normal operation.
 - Connect serial cable from conflict monitor to comm. port 1 of 2070 controller. Ensure conflict monitor communicates with 2070.

NOTES

- To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
- Enable Simultaneous Gap-Out for all phases.
- Program phases 2 and 6 for Variable Initial and Gap Reduction.
- Program phases 2 and 6 for Start Up In Green.
- Program phases 2 and 6 for Yellow Flash.
- The cabinet and controller are part of the Havelock Closed Loop System.

EQUIPMENT INFORMATION

CONTROLLER.....2070
CABINET.....332
SOFTWARE.....ECONOLITE OASIS
CABINET MOUNT.....BASE
OUTPUT FILE POSITIONS...12
LOAD SWITCHES USED.....S2,S5,S7,S8
PHASES USED.....2,4,5,6
OVERLAPS.....NONE


SIGNAL HEAD HOOK-UP CHART

LOAD SWITCH NO.	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10	S11	S12
CMU CHANNEL NO.	1	2	13	3	4	14	5	6	15	7	8	16
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED
SIGNAL HEAD NO.	NU	21,22	NU	NU	41,42	NU	42	51	61,62	NU	NU	NU
RED		128			101				134			
YELLOW		129			102				135			
GREEN		130			103				136			
RED ARROW								131				
YELLOW ARROW							132	132				
GREEN ARROW							133	133				

NU = Not Used

INPUT FILE POSITION LAYOUT

(front view)




EX.: 1A, 2A, ETC. = LOOP NO.'S
FS = FLASH SENSE
ST = STOP TIME

INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	INPUT ASSIGNMENT NO.	DETECTOR NO.	NEMA PHASE	CALL	EXTEND	FULL TIME DELAY	STRETCH TIME	DELAY TIME
2A	TB2-5,6	I2U	39	1	2	2	Y	Y			
2B	TB2-7,8	I2L	43	5	12	2	Y	Y			
4A	TB4-9,10	I6U	41	3	4	4	Y	Y			
5A	TB3-1,2	J1U	55	17	5	5	Y	Y			
5B	TB3-3,4	J1L	55	17	5	5	Y	Y			
6A	TB3-5,6	J2U	40	2	6	6	Y	Y			
6B	TB3-7,8	J2L	44	6	16	6	Y	Y			

INPUT FILE POSITION LEGEND: J2L



THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 02-0672T
DESIGNED: October 2016
SEALED: 2/1/2017
REVISED: N/A

Electrical Detail - Temporary Design (Phase II)

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

US 70 at Slocum Road

Division 2 Craven County Havelock

PLAN DATE: January 2017 REVIEWED BY: BAS

PREPARED BY: S. Armstrong REVIEWED BY:

REVISIONS INIT. DATE

Seal: Keith M. Mims, Professional Engineer, No. 036880

DocuSigned by: Keith M. Mims 2/28/2017


750 N. Greenfield Pkwy, Garner, NC 27529

SIG. INVENTORY NO. 02-0672T

06-FEB-2017 06:52
S:\ITS\AS\15\S\Sig\edi\work\hgc\02-0672_sm.ele.xxx.dgn
sarmstrong

EDI MODEL 2018ECL-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumper and set switches as shown)



- NOTES:
- Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
 - Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
 - Ensure that Red Enable is active at all times during normal operation.
 - Connect serial cable from conflict monitor to comm. port 1 of 2070 controller. Ensure conflict monitor communicates with 2070.

NOTES

- To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
- Enable Simultaneous Gap-Out for all phases.
- Program phases 2 and 6 for Variable Initial and Gap Reduction.
- Program phases 2 and 6 for Start Up In Green.
- Program phases 2 and 6 for Yellow Flash.
- The cabinet and controller are part of the US 70 (Havelock) Closed Loop System.

EQUIPMENT INFORMATION

CONTROLLER.....2070
 CABINET.....336
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....POLE
 OUTPUT FILE POSITIONS...12
 LOAD SWITCHES USED.....S2,S3*,S5,S8,S9*
 PHASES USED.....2,4,6
 OVERLAPS.....NONE
 * Used for Advance Beacon only.


SIGNAL HEAD HOOK-UP CHART

LOAD SWITCH NO.	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10	S11	S12
CMU CHANNEL NO.	1	2	13	3	4	14	5	6	15	7	8	16
PHASE	1	2	2 PED ADVANCE BEACON	3	4	4 PED	5	6	6 PED ADVANCE BEACON	7	8	8 PED
SIGNAL HEAD NO.	NU	21,22 23	NU	24,26	NU	41,42 43,44	NU	NU	61,62	NU	25,27	NU
RED		128							134			
YELLOW		129							135			
GREEN		130							136			
RED ARROW					101							
YELLOW ARROW					102							
GREEN ARROW					103							
PED YELLOW					** 114				** 120			

NU = Not Used
 * Denotes install load resistor. See load resistor installation detail on sheet 2.
 ** Special advance beacons will be wired to S3-Y S9-Y. See wiring and programming details on sheet 2 of this electrical detail.

INPUT FILE POSITION LAYOUT

(front view)



EX. : 1A, 2A, ETC. = LOOP NO.'S
 FS = FLASH SENSE
 ST = STOP TIME

INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	INPUT ASSIGNMENT NO.	DETECTOR NO.	NEMA PHASE	CALL	EXTEND	FULL TIME DELAY	STRETCH TIME	DELAY TIME
2A	TB21-3,4	I2U	39	1	2	2	Y	Y			
2B	TB23-3,4	I2L	43	5	12	2	Y	Y			
4A	TB21-7,8	I4U	41	3	4	4	Y	Y			
4B	TB23-7,8	I4L	45	7	14	4	Y	Y			
6A	TB21-11,12	I6U	40	2	6	6	Y	Y			
6B	TB23-11,12	I6L	44	6	16	6	Y	Y			

INPUT FILE POSITION LEGEND: I2L
 FILE I
 SLOT 2
 LOWER

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 02-0672
 DESIGNED: October 2016
 SEALED: 2/2/2017
 REVISED: N/A

06-FEB-2017 06:05 S:\ITS\SSM\ITS_Signal\work\hgr\cds\g_Mon\Arms\strong\020672_sm.elec.xxx.dgn sarmsstrong

Electrical Detail - Final - Sheet 1 of 2

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Prepared In the Offices of:

 750 N. Greenfield Pkwy, Garner, NC 27529

US 70 at Slocum Road

Division 2 Craven County Havelock

PLAN DATE: January 2017 REVIEWED BY: BAS
 PREPARED BY: S. Armstrong REVIEWED BY:

REVISIONS INIT. DATE

Seal of Keith M. Mims, Professional Engineer, No. 036880, State of North Carolina.

DocuSigned by: Keith M. Mims 2/28/2017
 DATE: 2/28/2017
 SIG. INVENTORY NO. 02-0672

ADVANCE BEACON OUTPUT ASSIGNMENT PROGRAMMING DETAIL

(program controller as shown below)

FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '1' (OUTPUT ASSIGNMENTS). PRESS '+' UNTIL OUTPUT #33 (PIN 35) IS REACHED.

```

PAGE:1 C1 PIN:35 NOT ENABLED
OUTPUT ASSIGNMENT #.....33
FREQUENCY (0=DEFAULT) (0-25.5 HZ)...1.0
DUTY CYCLE (0=DEFAULT) (0 - 100%)...50
MODE (0=SOLID,1=FLASH).....1
SELECT ASSIGNMENT:
NOT ENABLED.....Y
VEHICLE PHASE.....
PEDESTRIAN PHASE.....
VEHICLE OVERLAP.....
PEDESTRIAN OVERLAP.....
WATCHDOG.....
DETECTOR RESET.....
ADVANCE BEACON.....Y
OUT OF PHASE FLASHER.....
CONTROLLER FLASH.....
RUN FREE.....
RESERVED.....
PREEMPT.....
SOFT PREEMPT.....
ANY PREEMPT.....
COORDINATION PLAN.....
OFFSET.....
PHASE CHECK.....
PHASE ON.....
PHASE NEXT.....
    
```

THE FIRST THREE PROGRAMMING ROWS DEFINE THE OUTPUT TO FLASH, ALONG WITH THE RATE IN WHICH AT WILL FLASH.

THE NOT ENABLED 'Y' WILL REMAIN UNTIL THE FUNCTION OF THIS OUTPUT IS CHANGED. DO NOT ENTER AN 'N'.

```

PAGE:1 C1 PIN:35 NOT ENABLED
SELECT BEACON INDEX (1-4).....1
    
```

WHEN A 'Y' IS ENTERED FOR 'ADVANCE BEACON' THE SCREEN SHOWN ABOVE WILL APPEAR. ENTER DATA AS SHOWN.

PRESS THE 'ENT' KEY AFTER ENTERING DATA, THEN 'ESC'.

DISPLAY WILL NOW SHOW THE SPECIFIED OUTPUT ASSIGNED AS 'ADVANCE BEACON' AS SHOWN BELOW.

```

PAGE:1 C1 PIN:35 ADVANCE BEACON
OUTPUT ASSIGNMENT #.....33
FREQUENCY (0=DEFAULT) (0-25.5 HZ)...1.0
DUTY CYCLE (0=DEFAULT) (0 - 100%)...50
MODE (0=SOLID,1=FLASH).....1
SELECT ASSIGNMENT:
NOT ENABLED.....
VEHICLE PHASE.....
PEDESTRIAN PHASE.....
VEHICLE OVERLAP.....
PEDESTRIAN OVERLAP.....
WATCHDOG.....
DETECTOR RESET.....
ADVANCE BEACON.....Y
OUT OF PHASE FLASHER.....
CONTROLLER FLASH.....
RUN FREE.....
RESERVED.....
PREEMPT.....
SOFT PREEMPT.....
ANY PREEMPT.....
COORDINATION PLAN.....
OFFSET.....
PHASE CHECK.....
PHASE ON.....
PHASE NEXT.....
    
```

FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '1' (OUTPUT ASSIGNMENTS). PRESS '+' UNTIL OUTPUT #34 (PIN 36) IS REACHED.

```

PAGE:1 C1 PIN:36 NOT ENABLED
OUTPUT ASSIGNMENT #.....34
FREQUENCY (0=DEFAULT) (0-25.5 HZ)...0.0
DUTY CYCLE (0=DEFAULT) (0 - 100%)...0
MODE (0=SOLID,1=FLASH).....0
SELECT ASSIGNMENT:
NOT ENABLED.....Y
VEHICLE PHASE.....
PEDESTRIAN PHASE.....
VEHICLE OVERLAP.....
PEDESTRIAN OVERLAP.....
WATCHDOG.....
DETECTOR RESET.....
ADVANCE BEACON.....
OUT OF PHASE FLASHER.....Y
CONTROLLER FLASH.....
RUN FREE.....
RESERVED.....
PREEMPT.....
SOFT PREEMPT.....
ANY PREEMPT.....
COORDINATION PLAN.....
OFFSET.....
PHASE CHECK.....
PHASE ON.....
PHASE NEXT.....
    
```

THE NOT ENABLED 'Y' WILL REMAIN UNTIL THE FUNCTION OF THIS OUTPUT IS CHANGED. DO NOT ENTER AN 'N'.

```

PAGE:1 C1 PIN:36 NOT ENABLED
SELECT OUTPUT ASSIGNMENT (1-64).....33
    
```

WHEN A 'Y' IS ENTERED FOR 'OUT OF PHASE FLASHER' THE SCREEN SHOWN ABOVE WILL APPEAR. ENTER DATA AS SHOWN.

PRESS THE 'ENT' KEY AFTER ENTERING DATA, THEN 'ESC'.


DISPLAY WILL NOW SHOW THE SPECIFIED OUTPUT ASSIGNED AS 'OUT OF PHASE FLASHER' AS SHOWN BELOW.

```

PAGE:1 C1 PIN:36 OUT OF PHASE FLASHER
OUTPUT ASSIGNMENT #.....34
FREQUENCY (0=DEFAULT) (0-25.5 HZ)...0.0
DUTY CYCLE (0=DEFAULT) (0 - 100%)...0
MODE (0=SOLID,1=FLASH).....0
SELECT ASSIGNMENT:
NOT ENABLED.....
VEHICLE PHASE.....
PEDESTRIAN PHASE.....
VEHICLE OVERLAP.....
PEDESTRIAN OVERLAP.....
WATCHDOG.....
DETECTOR RESET.....
ADVANCE BEACON.....
OUT OF PHASE FLASHER.....Y
CONTROLLER FLASH.....
RUN FREE.....
RESERVED.....
PREEMPT.....
SOFT PREEMPT.....
ANY PREEMPT.....
COORDINATION PLAN.....
OFFSET.....
PHASE CHECK.....
PHASE ON.....
PHASE NEXT.....
    
```

OUTPUT REFERENCE SCHEDULE	
OUTPUT 33 =	Ø 2 Ped Yellow
OUTPUT 34 =	Ø 6 Ped Yellow


ADVANCE BEACON WIRING DETAIL (wire flashers as shown below)



IMPORTANT

1. REMOVE, TAPE AND LABEL CONFLICT MONITOR WIRES ATTACHED TO THE REAR OF TERMINAL 114 (2PY) AND TERMINAL 120 (6PY).
2. INSERT LOADSWITCH FOR S3 AND S9.
3. MAKE SURE LOAD RESISTORS ARE IN PLACE AS SHOWN IN LOAD RESISTOR INSTALLATION DETAIL ON THIS SHEET.
4. TO ACTIVATE SIGN OPERATION AS INDICATED ON THE SIGNAL PLANS, REASSIGN OUTPUT 33 AND 34 AS SHOWN ON THIS SHEET.

LOAD RESISTOR INSTALLATION DETAIL



ADVANCE BEACON PROGRAMMING DETAIL

(program controller as shown below)

1. FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '2' (OUTPUT BEACON SETTINGS).

```

          OUTPUT BEACON SETTINGS
TRIGGER PHASES: 12345678910111213141516
BEACON #1 OFF      X
BEACON #2 OFF
BEACON #3 OFF
BEACON #4 OFF
          BEACON   1   2   3   4
OFF DELAY TIME (0-255); 0   0   0   0
ON DELAY TIME (0-255);  0   0   0   0
STOP-TIME HOLD (0-255); 2   0   0   0
    
```

SCROLL DOWN TO VIEW ALL DATA

← NOTICE STOP TIME HOLD

ADVANCE BEACON PROGRAMMING COMPLETE

NOTE: AN OUTPUT HAS TO BE ASSIGNED AS AN ADVANCE BEACON IN ORDER FOR PROPER OPERATION TO OCCUR. SEE OUTPUT ASSIGNMENT DETAIL ON THIS SHEET.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 02-0672
DESIGNED: October 2016
SEALED: 2/2/2017
REVISED: N/A

Electrical Detail - Final - Sheet 2 of 2

ELECTRICAL AND PROGRAMMING DETAILS FOR:	US 70 at Slocum Road	DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED
Prepared In the Offices of: 750 N. Greenfield Pkwy, Garner, NC 27529	Division 2 Craven County HaveLock PLAN DATE: January 2017 REVIEWED BY: BAS PREPARED BY: S. Armstrong REVIEWED BY:	SEAL Keith M. Minns 2/28/2017 DATE
REVISIONS		SIG. INVENTORY NO. 02-0672

06-FEB-2017 06:05
 S:\ITS\ASUM\ITS_Signals\work\hgr\oups\sig_Monitors\strong\020672_sml.elec.xxx.dgn
 sarmstrong

PHASING DIAGRAM






TABLE OF OPERATION

SIGNAL FACE	PHASE	
	03	06
31,32	(R)	(R)
61,62,63	R	G Y

SIGNAL FACE I.D.

All Heads L.E.D.




OASIS 2070 LOOP & DETECTOR INSTALLATION CHART

LOOP	SIZE (FT)	DISTANCE FROM STOPBAR (FT)	TURNS	NEW LOOP	DETECTOR PROGRAMMING							
					PHASE	CALLING	EXTENSION	FULL TIME DELAY	STRETCH TIME	DELAY TIME	SYSTEM LOOP	NEW CARD
3A	6X40	0	2-4-2	Y	3	Y	Y	-	-	-	-	Y
3B	6X40	0	2-4-2	Y	3	Y	Y	-	-	-	-	Y
6A	6X6	420	6	Y	6	Y	Y	-	-	-	-	Y
6B	6X6	420	6	Y	6	Y	Y	-	-	-	-	Y
6C	6X6	420	6	Y	6	Y	Y	-	-	-	-	Y

2 Phase Fully Actuated US 70 (Havelock) CLS

NOTES

- Refer to "Roadway Standard Drawings NCDOT" dated January 2012 and "Standard Specifications for Roads and Structures" dated January 2012.
- Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- Set all detector units to presence mode.
- The cabinet should be designed to include an Auxiliary Output file for future use.
- Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.
- Closed loop system data: Intersection Number #: 0911.




OASIS 2070 TIMING CHART

FEATURE	PHASE	
	3	6
Min Green 1 *	7	14
Extension 1 *	2.0	6.0
Max Green 1 *	25	90
Yellow Clearance	3.8	5.2
Red Clearance	4.4	1.9
Walk 1 *	-	-
Don't Walk 1	-	-
Seconds Per Actuation *	-	1.5
Max Variable Initial *	-	46
Time Before Reduction *	-	15
Time To Reduce *	-	30
Minimum Gap	-	3.4
Recall Mode	-	MIN RECALL
Vehicle Call Memory	-	YELLOW
Dual Entry	-	-
Simultaneous Gap	ON	ON

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

LEGEND



New Installation

Prepared In the Offices of:

750 N. Greenfield Pkwy, Garner, NC 27529

US 70 at Hickman Hill Loop Road EB U-turn

Division 2 Craven County Havelock

PLAN DATE: October 2016 REVIEWED BY: JPG

PREPARED BY: KGP, Jr. REVIEWED BY:

SEAL

DATE: 1/4/2017


SIG. INVENTORY NO. 02-0911

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


03-1485-2017_08-25-16 R:\MRF\03-1485-2017\08-25-16\03-1485-2017-08-25-16.dgn kgspeed

EDI MODEL 2018ECL-NC CONFLICT MONITOR
PROGRAMMING DETAIL

(set switches as shown)




DO NOT REMOVE ANY DIODE JUMPERS.



DO NOT REMOVE ANY DIODE JUMPERS

NOTES:

- Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
- Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
- Ensure that Red Enable is active at all times during normal operation.
- Connect serial cable from conflict monitor to comm. port 1 of 2070 controller. Ensure conflict monitor communicates with 2070.



■ = DENOTES POSITION OF SWITCH

NOTES

- To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
- Enable Simultaneous Gap-Out for all phases.
- Program phase 6 for Variable Initial and Gap Reduction.
- Program phase 6 for Start Up In Green.
- Program phase 6 for Yellow Flash.
- The cabinet and controller are part of the US 70 (Havelock) CLS.

EQUIPMENT INFORMATION

CONTROLLER.....2070
CABINET.....332 W/AUX
SOFTWARE.....ECONOLITE OASIS
CABINET MOUNT.....BASE
OUTPUT FILE POSITIONS...18 WITH AUX. OUTPUT FILE
LOAD SWITCHES USED.....S4,S8
PHASES USED.....3,6
OVERLAPS.....NONE


SIGNAL HEAD HOOK-UP CHART

LOAD SWITCH NO.	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10	S11	S12	AUX S1	AUX S2	AUX S3	AUX S4	AUX S5	AUX S6
EMU CHANNEL NO.	1	2	13	3	4	14	5	6	15	7	8	16	9	10	17	11	12	18
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED	OLA	OLB	SPARE	OLC	OLD	SPARE
SIGNAL HEAD NO.	NU	NU	NU	31,32	NU	NU	NU	61,62 63	NU	NU	NU	NU	NU	NU	NU	NU	NU	NU
RED								134										
YELLOW								135										
GREEN								136										
RED ARROW				116														
YELLOW ARROW				117														
GREEN ARROW				118														

NU = Not Used

INPUT FILE POSITION LAYOUT

(front view)




EX. : 1A, 2A, ETC. = LOOP NO.'S

FS = FLASH SENSE
ST = STOP TIME

INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	INPUT ASSIGNMENT NO.	DETECTOR NO.	NEMA PHASE	CALL	EXTEND	FULL TIME DELAY	STRETCH TIME	DELAY TIME
3A	TB4-5,6	15U	58	20	3	3	Y	Y			
3B	TB4-7,8	15L	58	20	3	3	Y	Y			
6A	TB3-5,6	J2U	40	2	6	6	Y	Y			
6B	TB3-7,8	J2L	44	6	16	6	Y	Y			
6C	TB3-9,10	J3U	64	26	36	6	Y	Y			

INPUT FILE POSITION LEGEND: J2L



THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 02-0911
DESIGNED: October 2016
SEALED: 1/4/2017
REVISED: N/A

Electrical Detail

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Prepared In the Offices of:
TRANSPORTATION MOBILITY AND SAFETY DIVISION
STATE OF NORTH CAROLINA
Signal Management Section
750 N. Greenfield Pkwy, Garner, NC 27529

US 70 at Hickman Hill Loop Road EB U-turn

Division 2 Craven County Havelock

PLAN DATE: January 2017 REVIEWED BY: BAS
PREPARED BY: S. Armstrong REVIEWED BY:

REVISIONS INIT. DATE

DocuSigned by: Keith M. Mins 3/3/2017
2F80768EC32445 DATE


SIG. INVENTORY NO. 02-0911

03-1485-2017_09-31
S:\MITS\SSM\15_Signal\work\groups\51g_MarkArmstrong\20911_sm_elec_xxx.dgn
sarmstrong

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

PROJECT I.D. NO. R-5516	SHEET NO. Sig.M1
-----------------------------------	----------------------------

STANDARD DRAWINGS FOR ALL METAL POLES



WIND ZONE LEGEND

WIND ZONE 1 (140 mph) Special Wind Zone	
WIND ZONE 2 (130 mph) Coastal Region	
WIND ZONE 3 (110 mph) Eastern Region	
WIND ZONE 4 (90 mph) Central & Mtn. Region	
WIND ZONE 5 (120 mph) Special Wind Zone	

<https://connect.ncdot.gov/resources/safety/Pages/ITS-Design-Resources.aspx>

Prepared In the Offices of:

750 N. Greenfield Pkwy.
Garner, NC 27529

Designed in conformance
with the latest
2015 Interim to the
6th Edition 2013
AASHTO
Standard Specifications for
Structural Supports for
Highway Signs, Luminaires,
and Traffic Signals

DRAWING NUMBER	DESCRIPTION
Sig. M 1	Statewide Wind Zone Map
Sig. M 2	Typical Fabrication Details-All Metal Poles
Sig. M 3	Typical Fabrication Details-Strain Poles
Sig. M 4	Typical Fabrication Details-Mast Arm Poles
Sig. M 5	Typical Fabrication Details-Mast Arm Connection
Sig. M 6	Typical Fabrication Details-Strain Pole Attachments
Sig. M 7	Construction Details-Foundations
Sig. M 8	Standard Strain Pole Foundation-All Soil Conditions

NC DOT CONTACTS:

MOBILITY AND SAFETY DIVISION - ITS AND SIGNALS UNIT

G. A. FULLER, P.E. - STATE ITS AND SIGNALS ENGINEER

G. G. MURR, JR., P.E. - STATE SIGNALS ENGINEER


D.C. SARKAR, P.E. - ITS AND SIGNALS SENIOR STRUCTURAL ENGINEER

C.F. ANDREWS - ITS AND SIGNALS JOURNEY STRUCTURAL ENGINEER

SEAL

DocuSigned by:
Debesh C. Sarkar

2/17/2016
DATE




MFG _____	MFG. DATE: MM/YY _____
SHAFT D/T/L/Y _____	_____
ARM-A D/T/L/Y _____	_____
ARM-B D/T/L/Y _____	_____
A.B. DIA./B.C./L/Y _____	_____
NCDOT SIG. INV. NO. _____	_____
NCDOT POLE NO. _____	_____

Shaft I.D. Tag
(Provide on Shaft of Strain Poles and Mast Arm Poles Shaft)


- Notes:**
- 1) D= Diameter, T= Thickness, L= Length, Y= Yield Strength
 - 2) A.B. = Anchor Bolt
 - 3) B.C. = Bolt Circle of Anchor Bolts
 - 4) If Custom Design, use "NCDOT STANDARD" line for Signal Inv. Number and pole I.D. number
 - 5) See drawing M3 and M4 for mounting positions of I.D. tags.

Identification Tag Details




Construct Templates and Plates from 1/4" min. thick Steel. Galvanizing is not required.

Base Plate Template and Anchor Bolt Lock Plate Details



Anchor Bolt Detail



Note: Base plate may be circular, octagonal, square or rectangular in shape.

Typical Base Plate Detail

Prepared in the Offices of:

750 N. Greenfield Pkwy, Garner, NC 27529

Typical Fabrication Details For All Metal Poles	
PLAN DATE: FEBRUARY 2016	DESIGNED BY: C.F. ANDREWS
PREPARED BY: N. BITTING	REVIEWED BY: D.C. SARKAR
REVISIONS	INITIALS DATE

SEAL


DocuSigned by
Debesh C. Sarkar

44E8E32E147E4C4...


2/17/2016 DATE

17-FEB-2016 16:02:31 TSC04115 Signal Design Section Eastern Region 0162014 Sig.M2 Std. Fabrication Detail Is-All Poles.dgn

Note:
 1. Opening in pole base plate shall be equal to pole base inside diameter minus 3 1/2" but shall not be less than 8 1/2".




Cable Entrances at Top of Pole




Section B-B
Pole Base Plate Details
(8 and 12 Bolt Pattern)


2 Cable Clamps designed for variable attachment heights from 1'-6" to 5'-0" below the top of the pole.



Section A-A
Radial Orientation for Factory Installed
Accessories at Top of Pole



Section C-C
(Pole Attachment to Base Plate)
Full-Penetration
Groove Weld Detail



Monotube Strain Pole

Prepared in the Offices of:

 750 N. Greenfield Pkwy, Garner, NC 27529


Typical Fabrication Details For Strain Poles			
PLAN DATE:	FEBRUARY 2016	DESIGNED BY:	K.C. DURIGON
PREPARED BY:	N. BITTING	REVIEWED BY:	D.C. SARKAR
REVISIONS	INIT.	DATE	

SEAL


 DocuSigned by
 Debesh C. Sarkar
 SIGNATURE
 44E8E32E147E4C4...
 2/17/2016
 DATE

Fabrication Details – Strain Poles


Note:
 1. Opening in pole base plate shall be equal to pole base inside diameter minus 3 1/2" but shall not be less than 8 1/2".




Section A-A
Pole Base Plate Details




Section B-B
 (Pole Attachment to Base Plate)
Full-Penetration Groove Weld Detail



Slip Fit Joint Detail for Mast Arm



Mast Arm Radial Orientation



Mast Arm Pole






Prepared in the Offices of: 750 N. Greenfield Pkwy, Garner, NC 27529	Typical Fabrication Details For Mast Arm Poles		SEAL DocuSigned by Dibesh C. Sarkar 44E8E32E147E4C4...	
	PLAN DATE: FEBRUARY 2016	DESIGNED BY: K.C. DURIGON		2/17/2016 DATE
	PREPARED BY: N. BITTING	REVIEWED BY: D.C. SARKAR		
	REVISIONS	INIT. DATE		

17-FEB-2016 16:05
 I:\CSG\4115_Sig.M4\Sig.M4.dwg
 Design Section Eastern Region
 RegionM4_Sheets\2016\2014_Sig.M4_Std. Fabrication Detail - Mast Arm Poles.dgn
 3:01:52

Fabrication Details – Mast Arm Poles



Welded Ring Stiffened Mast Arm Connection

PROJECT ID. NO. R-5516	SHEET NO. Sig.M5
----------------------------------	----------------------------



Notes:


1. Provide a permanent means of identification above the mast arm to indicate proper attachment orientation of the mast arm.
2. Designer will determine the size of all structural components, plates, fasteners, and welds shown unless they are already specified.
3. Fabricator is responsible for providing appropriate holes at drainage points to drain galvanizing materials.
4. For minimum edge distance follow AISC Table J3.4 and J3.5. For nominal bolt hole size use Table J3.3.
5. Provide upper handhole as necessary when shaft extensions are required for luminaire arms or camera. For poles without luminaires/camera, wiring can be done through the top of pole.
6. Allowable range of flange tilt angle will vary from 0° to as required.




Prepared in the Offices of: 750 N. Greenfield Pkwy, Garner, NC 27529	Typical Fabrication Details For Mast Arm Connection To Pole		SEAL DocuSigned by: Debesh C. Sarkar 44E8E32E147E4C4...
	PLAN DATE: FEBRUARY 2016 PREPARED BY: N. BITTING	DESIGNED BY: C.F. ANDREWS REVIEWED BY: D.C. SARKAR	
SCALE 0 NA NONE			

17-FEB-2016 16:06
 T:\SC04\115\Sig.M5.dgn
 Design Section\Eastern Region\115\Sig.M5.dgn
 Connection Fabrication Detail\Mast Arm Pole.dgn
 3/21/2016


Fabrication Details – Mast Arm Connection



Strain Pole Attachments



Attachment of Cable to Intermediate Metal Pole




Metal Pole Grounding Detail For Strain Pole and Mast Arm

NOTE:


1. Strap all signal cables to the side of the pole with 3/4" stainless steel straps when the distance between the spanwire attachment clamp and the weatherheads exceeds 3'-0".
2. Provide minimum two spanwire pole clamps per pole.
3. It is prohibited to attach two span wires at one pole clamp.
4. For general requirements refer to NCDOT Standard Specifications for Roadway and Structures, January 2012.

17-FEB-2016 16:09
 I:\SCD\MTS\Signal\sig\Design Section\Eastern Region\MTS\Sheets\2016\2014_Sig_M6_Std_Fabrication_Details-Strain_Poles.dgn
 3/21/2016


	<p>Typical Fabrication Details For Strain Pole Attachments</p>		
	<p>PLAN DATE: FEBRUARY 2016</p>	<p>DESIGNED BY: C.F. ANDREWS</p>	
<p>750 N. Greenfield Pkwy, Garner, NC 27529</p>	<p>SCALE: NA</p>	<p>REVISIONS</p>	<p>INIT. DATE</p>
<p>0 NONE</p>	<p>DocuSigned By: Debesh C. Sarkar</p>	<p>44E8E32E147E4C4...</p>	<p>2/17/2016</p>




Concrete Shaft Elevation



Section A-A




Typical "C" Bar Detail



Typical Foundation Conduit Details

"D" Shaft Dia.	Conc. Volume (cu. yds.)	Bar Name	MIN.	Size	Type	Length
4'-0"	.465 x L	V1	-	#8	STR.	**
		C	*	#4	CIR.	12'-6"

* See Note No. 2
 ** See Note No. 3




Typical Foundation Anchor Bolt Details

(Reinforcing Cage Not Shown for Clarity)

General Notes:

- If actual subsurface conditions differ significantly from boring data contact the Engineer before excavating or placing concrete.
- Circular tie reinforcing rings may be vertically adjusted by +/- 3" at a depth between 2'-0" and 3'-0" to facilitate the installation of electrical conduit entering in the cage.
- For standard foundations, see sheet Sig. M8 for details. Vertical reinforcing bars (V1) may be horizontally adjusted by +/- 3" to facilitate the installation of electrical conduit entering into the cage.
- Provide 2" to 5" foundation projection above ground level depending on the ground slope.
- Unless otherwise shown, foundation designs are based on non-sloping level ground surfaces with slope ratios of 8:1 (H:V) or flatter. If actual ground line slopes are steeper contact the Engineer before excavating or placing concrete.
- Construct foundations in accordance with NCDOT Standard Provisions SP09 R005- Foundations and Anchor Rod Assemblies for Metal Poles. All applicable 2012 NCDOT Standard Specifications are referenced in this provision. Refer to the NCDOT Resources/Specifications page located on the Connect NCDOT website.
[https://connect.ncdot.gov/resources/Specifications and Special Provisions.aspx](https://connect.ncdot.gov/resources/Specifications%20and%20Special%20Provisions.aspx)
- Use air entrained AA concrete mix with a compression strength of f'c=4500 psi.(min.) after 28 days.
- Use ASTM A615 grade 60 deformed bars for all reinforcing steel. Maintain at least 3" cover on all reinforcement.
- Locate the Identification Tag on the top of the base plate, directly above the conduit's entry point.
- Provide two layers of galvanized welded 23 gauge (0.25) 6" wide 4 mesh wire around pipes under the base plate and secure it with ties if necessary.
- Preferred location for the I.D. Tag is as shown in Detail-A; directly above the conduit entering the foundation.



Concrete Foundation Identification Tag Details

Detail-A

D = Diameter
 L = Length/Depth
 mm = Month
 yy = Year

	Construction Details For Foundations			
	PLAN DATE: FEBRUARY 2016	DESIGNED BY: C.B. COGDILL		
	PREPARED BY: N. BITTING	REVIEWED BY: D.C. SARKAR		
SCALE: NONE	REV. NO. 1	COMMENTS: Revised Foundation Top Details	INIT. N.B. DATE: 5/11/2015	

17-FEB-2016 16:11:03
 T:\CSG\W115\Signal\sig\Design\Section\Eastern_Region\MM_Sheets\2016\2014_Sig_M7_S1d_Construction_Detail\Is-Strain_Poles.dgn
 3:01:00

Construction Details - Foundations

SOIL CONDITION

PROJECT ID. NO.	SHEET NO.
R-5516	Sig.M8

		STANDARD STRAIN POLES					STANDARD FOUNDATIONS 48" Diameter Drilled Pier Length (L) - Feet							Reinforcement				
		Case No.	Pole Height (Ft.)	Base Plate BC (In.)	Reactions at the Pole Base			Clay				Sand			Longitudinal		Stirrups	
					Axial (kip)	Shear (kip)	Moment (ft-kip)	Medium N-Value 4-8	Stiff N-Value 9-15	Very Stiff N-Value 16-30	Hard N-Value >30	Loose N-Value 4-10	Medium N-Value 11-30	Dense N-Value >30	Bar Size (#)	Quantity (ea.)	Bar Size (#)	Spacing (in.)
WIND ZONE 1	LIGHT	S26L3	26	25	2	11	270	19	13	10	8	17	14.5	12.5	8	12	4	12
		S30L3	30	25	2	11	300	19.5	13.5	10	8	17.5	15	13	8	14	4	12
		S35L3	35	25	3	11	320	20	13.5	10.5	8	17.5	15	13	8	14	4	12
	HEAVY	S30H3	30	29	3	16	450	24.5	16	12	9	21	17.5	15	8	16	4	6
		S35H3	35	29	4	16	515	26	17	12.5	9.5	22	18.5	16	8	16	4	6
WIND ZONE 2	LIGHT	S26L2	26	23	2	10	245	18	12.5	9.5	8	16.5	14	12	8	12	4	12
		S30L2	30	23	2	10	270	18.5	12.5	10	8	16.5	14	12.5	8	12	4	12
		S35L2	35	23	3	10	300	19.5	13	10	8	17	14.5	13	8	12	4	12
	HEAVY	S30H2	30	29	3	15	415	23	15.5	11.5	9	20	17	14.5	8	16	4	6
		S35H2	35	29	4	15	475	25	16.5	12	9.5	21	17.5	15.5	8	16	4	6
WIND ZONE 3	LIGHT	S26L2	26	23	2	10	245	18	12.5	9.5	8	16.5	14	12	8	12	4	12
		S30L2	30	23	2	10	270	18.5	12.5	10	8	16.5	14	12.5	8	12	4	12
		S35L2	35	23	3	10	300	19.5	13	10	8	17	14.5	13	8	12	4	12
	HEAVY	S30H2	30	29	3	15	415	23	15.5	11.5	9	20	17	14.5	8	16	4	6
		S35H2	35	29	4	15	475	25	16.5	12	9.5	21	17.5	15.5	8	16	4	6
WIND ZONE 4	LIGHT	S26L1	26	22	2	8	190	16	11.5	8.5	8	15	12.5	11	8	12	4	12
		S30L1	30	22	2	8	205	16.5	11.5	9	8	15	13	11.5	8	12	4	12
		S35L1	35	22	3	8	230	17	12	9	8	15.5	13.5	11.5	8	12	4	12
	HEAVY	S30H1	30	25	3	12	320	20.5	13.5	10.5	8	18	15	13.5	8	16	4	6
		S35H1	35	25	4	12	350	21	14	10.5	8.5	18.5	15.5	13.5	8	16	4	6
WIND ZONE 5	LIGHT	S26L2	26	23	2	10	245	18	12.5	9.5	8	16.5	14	12	8	12	4	12
		S30L2	30	23	2	10	270	18.5	12.5	10	8	16.5	14	12.5	8	12	4	12
		S35L2	35	23	3	10	300	19.5	13	10	8	17	14.5	13	8	12	4	12
	HEAVY	S30H2	30	29	3	15	415	23	15.5	11.5	9	20	17	14.5	8	16	4	6
		S35H2	35	29	4	15	475	25	16.5	12	9.5	21	17.5	15.5	8	16	4	6

General Notes:



1. Values shown in the "Reactions at the Pole Base" column represent the minimum acceptable capacity allowed for design using a design CSR of 1.00.
2. Use chairs and spacers to maintain proper clearance.
3. For foundation, always use air-entrain concrete mix.

Foundation Selection:

1. Perform a standard penetration test at each proposed foundation site to determine "N" value.
2. Select the appropriate wind zone from M 1 drawing.
3. Select the soil type (Clay or Sand) that best describes the soil characteristics.
4. Get the appropriate standard pole case number from the plans or from the Engineer.
5. Select the appropriate column under "Standard Foundations" based on soil type and "N" value. Select the appropriate row based on the pole load case.
6. The foundation depth is the value shown in the "Standard Foundations" category where the column and the row intersect.
7. Use Construction Procedures and Design Methods prescribed by FHWA-NHI-10-016 for Reference Drilled Shafts.

Standard Strain Pole Foundation-All Soil Condition

48" Dia. Foundations Concrete Volume (cubic yards) = (0.465) x Drilled Pier Length

	<p>Standard Strain Pole Foundation for All Soil Conditions</p> <p>PLAN DATE: FEBRUARY 2016 DESIGNED BY: C.B. COGDILL PREPARED BY: N. BITTING REVIEWED BY: D.C. SARKAR</p>	<p>SEAL</p> 									
<p>0 NA</p> <p>NONE</p>	<p>REVISIONS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>NO.</th> <th>DATE</th> <th>INIT.</th> </tr> <tr> <td>1</td> <td>7/12/2015</td> <td>N.B.</td> </tr> <tr> <td colspan="3">Changed "Foundation Depth" to "Drilled Pier Length" in Conc. Egn.</td> </tr> </table>	NO.	DATE	INIT.	1	7/12/2015	N.B.	Changed "Foundation Depth" to "Drilled Pier Length" in Conc. Egn.			<p>DocuSigned by <i>Debash C. Sarkar</i></p> <p>2/17/2016</p>
NO.	DATE	INIT.									
1	7/12/2015	N.B.									
Changed "Foundation Depth" to "Drilled Pier Length" in Conc. Egn.											

I:\FEES\2016_16-14_S&T\2504115\Sig.M8\Sig.M8.Std.Strain Pole Found.-Saturated Soil Cond.H110n.dgn
 Sheets*2016*2014 Sig.M8 Std. Strain Pole Found.-Saturated Soil Cond.H110n.dgn

- 1 INSTALL REA, PE – 22, SHIELDED, TWISTED PAIR COMMUNICATIONS CABLE
- 2 INSTALL REA, PE – 38, (FIGURE 8) SHIELDED, TWISTED PAIR COMMUNICATIONS CABLE
- 3 INSTALL REA, PE – 39, (UNDERGROUND) SHIELDED, TWISTED PAIR COMMUNICATIONS CABLE
- 4 INSTALL SMFO CABLE
- 5 INSTALL MMFO CABLE
- 6 INSTALL FIBER OPTIC DROP CABLE
- 7 INSTALL TRACER WIRE
- 8 TRENCH
- 9 INSTALL PVC CONDUIT
- 10 INSTALL RIGID, GALVANIZED STEEL CONDUIT
- 11 INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD
- 12 INSTALL RIGID, GALVANIZED STEEL RISER WITH FIBER OPTIC CABLE SEAL
- 13 INSTALL OUTER-DUCT POLYETHYLENE CONDUIT
- 14 INSTALL POLYETHYLENE CONDUIT
- 15 DIRECTIONAL DRILL CONDUIT
- 16 BORE AND JACK CONDUIT
- 17 INSTALL CABLE(S) IN EXISTING CONDUIT
- 18 INSTALL CABLE(S) IN NEW CONDUIT
- 19 INSTALL CABLE(S) IN EXISTING RISER
- 20 INSTALL CABLE(S) IN NEW RISER
- 21 INSTALL CABLE(S) IN EXISTING CONDUIT STUB-OUTS
- 22 INSTALL NEW CONDUIT INTO EXISTING CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)
- 23 INSTALL NEW RISER INTO EXISTING CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)
- 24 INSTALL NEW CONDUIT INTO EXISTING POLE MOUNTED CABINET
- 25 INSTALL NEW RISER INTO EXISTING POLE MOUNTED CABINET
- 26 TERMINATE COMMUNICATIONS CABLE ON EXISTING TELEMETRY INTERFACE PANEL IN TRAFFIC SIGNAL CONTROLLER CABINET
- 27 INSTALL NEW TELEMETRY INTERFACE PANEL IN TRAFFIC SIGNAL CONTROLLER CABINET
- 28 INSTALL INTERCONNECT CENTER, PATCH PANEL, JUMPERS AND FUSION SPLICE CABLE IN CABINET
- 29 INSTALL UNDERGROUND SPLICE ENCLOSURE
- 30 INSTALL AERIAL SPLICE ENCLOSURE
- 31 INSTALL POLE MOUNTED SPLICE CABINET
- 32 INSTALL BASE MOUNTED SPLICE CABINET
- 33 REMOVE EXISTING SPLICE CABINET


- 34 INSTALL CABINET FOUNDATION
- 35 REMOVE EXISTING CABINET FOUNDATION
- 36 INSTALL CCTV CAMERA ASSEMBLY
- 37 INSTALL CCTV CAMERA WOOD POLE
- 38 INSTALL CCTV CAMERA METAL POLE AND FOUNDATION
- 39 INSTALL JUNCTION BOX
- 40 INSTALL OVERSIZED JUNCTION BOX
- 41 REMOVE EXISTING JUNCTION BOX
- 42 INSTALL WOOD POLE
- 43 REMOVE EXISTING WOOD POLE
- 44 INSTALL AERIAL GUY ASSEMBLY
- 45 INSTALL STANDARD GUY ASSEMBLY
- 46 INSTALL SIDEWALK GUY ASSEMBLY
- 47 INSTALL MESSENGER CABLE
- 48 REMOVE EXISTING COMMUNICATIONS AND MESSENGER CABLE
- 49 REMOVE EXISTING MESSENGER CABLE
- 50 INSTALL TELEPHONE SERVICE
- 51 INSTALL CABLE STORAGE RACKS (SNOW SHOES) AND STORE 100 FEET OF CABLE
- 52 INSTALL DELINEATOR MARKER
- 53 STORE 20 FEET OF COMMUNICATIONS CABLE
- 54 LASH CABLE(S) TO EXISTING SIGNAL/COMMUNICATIONS CABLE
- 55 LASH CABLE(S) TO EXISTING MESSENGER CABLE
- 56 LASH CABLE(S) TO NEW MESSENGER CABLE
- 57 MODIFY EXISTING ELECTRICAL SERVICE
- 58 INSTALL NEW ELECTRICAL SERVICE

LEGEND

- REL — EXISTING COMMUNICATIONS CABLE TO BE RELOCATED
- FO — NEW FIBER OPTIC COMMUNICATIONS CABLE
- TWIST PR — NEW TWISTED PAIR COMMUNICATIONS CABLE
- EXI — EXISTING COMMUNICATIONS CABLE
- REM — EXISTING COMMUNICATIONS CABLE TO BE REMOVED
- NEW AERIAL GUY ASSEMBLY
- NEW CONDUIT
- EXISTING CONDUIT
- DD — NEW DIRECTIONAL DRILLED CONDUIT
- B&J — NEW BORED AND JACKED CONDUIT
- EXISTING CCTV ASSEMBLY
- EXISTING JUNCTION BOX
- NEW WOOD POLE
- EXISTING WOOD POLE
- AERIAL SPLICE ENCLOSURE
- NEW METAL SIGNAL STRAIN POLE
- EXISTING CCTV METAL POLE
- RELOCATED CCTV ASSEMBLY
- NEW STANDARD GUY ASSEMBLY
- NEW SIDEWALK GUY ASSEMBLY
- NEW CABLE STORAGE RACKS (SNOW SHOES)
- EXISTING CONTROLLER AND CABINET
- EXISTING SPLICE CABINET
- NEW SPLICE CABINET
- SIGNAL POLE
- XX-XXXX SIGNAL INVENTORY NUMBER


CONSTRUCTION NOTE SYMBOLOGY KEY

- XX INDICATES NUMBER OF CABLES, LOOPS, ETC.
- XX INDICATES NUMBER OF FIBERS PER CABLE, TWISTED PAIRS PER CABLE, ETC.
- XX INDICATES NUMBER OF RISER(S)/CONDUIT(S)
- XX INDICATES DIAMETER OF RISER(S)/CONDUIT(S) (INCH)



DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

<p>750 N. Greenfield Pkwy., Garner, NC 27529</p>	<p>CONSTRUCTION NOTES</p>		
	<p>DIVISION 2 CRAVEN CO.</p> <p>PLAN DATE: FEBRUARY 2017</p> <p>PREPARED BY: H. T. BERGGREN</p>	<p>REVIEWED BY: I. N. Havelock</p> <p>REVIEWED BY: [Signature]</p>	
<p>7032CA0A8E87AFF</p>			<p>DATE: 2/15/2017</p>



LEGEND	
	YAGI ANTENNA (DOUBLE) FOR REPEATER OPERATION
	YAGI ANTENNA (SINGLE)
	OMNI ANTENNA
	EXISTING CONTROLLER AND CABINET
	EXISTING MASTER CONTROLLER AND CABINET
	SIGNAL INVENTORY NUMBER
	NEW METAL POLE W/MAST ARM
	EXISTING WOOD POLE
	NEW METAL POLE
	SIGNAL POLE
	EXISTING METAL POLE
	NEW OVERSIZED JUNCTION BOX
	EXISTING OVERSIZED JUNCTION BOX
	EXISTING CONDUIT
	NEW CONDUIT
	EXISTING COMMUNICATIONS CABLE


GENERAL NOTES:

1. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER, MARY MOORE, PE AT (252)439-2800 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON WIRELESS COMMUNICATION SYSTEM. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL COMMUNICATION CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
2. MODIFY RADIO INSTALLATION (RELOCATE EXISTING RADIO, ANTENNA, AND ANTENNA MOUNTING HARDWARE, TO NEW SIGNAL CABINET/SIGNAL POLE LOCATION).
3. INSTALL NEW COAXIAL CABLE THROUGH A NEW 2" RISER AND WEATHERHEAD. INSTALL COAXIAL CABLE SHIELD GROUNDING AND WEATHERPROOFING KIT.

TMP PHASE 2
(MAINTAIN WIRELESS SYSTEM)

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

	WIRELESS COMMUNICATIONS PLANS	
	DIVISION 2 CRAVEN CO.	HAVELock
PLAN DATE: FEBRUARY 2017	REVIEWED BY: I. N. Dyer	PREPARED BY: H. T. BERGGREN
REVISIONS	INIT.	DATE
SCALE: 1" = 50'	DATE: 2/15/2017	



LEGEND	
	YAGI ANTENNA (DOUBLE) FOR REPEATER OPERATION
	YAGI ANTENNA (SINGLE)
	OMNI ANTENNA
	EXISTING CONTROLLER AND CABINET
	EXISTING MASTER CONTROLLER AND CABINET
	SIGNAL INVENTORY NUMBER
	NEW METAL POLE W/MAST ARM
	EXISTING WOOD POLE
	NEW METAL POLE
	SIGNAL POLE
	EXISTING METAL POLE
	NEW OVERSIZED JUNCTION BOX
	EXISTING OVERSIZED JUNCTION BOX
	EXISTING CONDUIT
	NEW CONDUIT
	EXISTING COMMUNICATIONS CABLE

- GENERAL NOTES:**
- NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER, MARY MOORE, PE AT (252)439-2800 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON WIRELESS COMMUNICATION SYSTEM. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL COMMUNICATION CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
 - MODIFY RADIO INSTALLATION (RELOCATE EXISTING RADIO, MOUNTING HARDWARE, AND ANTENNA TO NEW SIGNAL CABINET/SIGNAL POLE LOCATION).
 - INSTALL NEW COAXIAL CABLE THROUGH A NEW 2" RISER AND WEATHERHEAD. INSTALL COAXIAL CABLE SHIELD GROUNDING AND WEATHERPROOFING KIT.

TMP PHASE 2
(MAINTAIN WIRELESS SYSTEM) **DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED**

<p>750 N. Greenfield Pkwy., Garner, NC 27529</p>	<p>WIRELESS COMMUNICATIONS PLANS</p> <p>DIVISION 2 CRAVEN CO., <small>DocuSigned by: HAVELock</small></p> <p>PLAN DATE: FEBRUARY 2017 REVIEWED BY: <i>L. N. Havelock</i></p> <p>PREPARED BY: H. T. BERGGREN REVIEWED BY: <small>08P0804CBED5443</small></p>		<p><small>DocuSigned by: Gregory A. Fuller</small> 2/15/2017</p>
	<p>SCALE 0 50</p> <p>1" = 50'</p>	<p>REVISIONS</p> <p>INIT. DATE</p>	

MASTER RADIO LOCATION





**US 70
AT WALMART ENTRANCE
SIG. INV. #02-0873**

Notes:
Unused fibers left coiled and stored in splice tray.
Unused Buffer Tubes left coiled and stored in splice tray.

LEGEND
X = FUSION SPICE

COLOR CODE TIA/EIA 598-A	
(1) BLUE	(7) RED
(2) ORANGE	(8) BLACK
(3) GREEN	(9) YELLOW
(4) BROWN	(10) VIOLET
(5) SLATE	(11) ROSE
(6) WHITE	(12) AQUA


GENERAL NOTE:
1. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER, MARY MOORE, PE, AT (252)439-2800, FIVE (5) DAYS PRIOR TO BEGINNING WORK ON WIRELESS COMMUNICATIONS SYSTEM. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL COMMUNICATION CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.



TMP PHASE 2
(MAINTAIN WIRELESS SYSTEM)

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

	WIRELESS COMMUNICATIONS PLANS	
	DIVISION 2 PLAN DATE: FEBRUARY 2017 PREPARED BY: H. T. BERGGREN	CRAVEN CO. REVIEWED BY: I. N. Lively REVIEWED BY:
SCALE: NONE N/A	REVISIONS:	INIT. DATE:



- GENERAL NOTES:**
1. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER, MARY MOORE, PE AT (252)439-2800 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL COMMUNICATION CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
 2. REMOVE EXISTING RADIO SYSTEM (RADIO, ANTENNA, ANTENNA MOUNTING HARDWARE, AND COAXIAL CABLE). RETURN RADIO, ANTENNA, AND ANTENNA MOUNTING HARDWARE TO THE DEPUTY DIVISION TRAFFIC ENGINEER.
 3. MODIFY INTERCONNECT CENTER (RECONNECT EXISTING\INSTALL NEW FIBER OPTIC JUMPERS BETWEEN EXISTING PATCH PANEL AND EXISTING FIBER OPTIC TRANCEIVER FOR COMMUNICATION LINK TO 02-0672).


LEGEND

	YAGI ANTENNA (DOUBLE) FOR REPEATER OPERATION
	YAGI ANTENNA (SINGLE)
	OMNI ANTENNA
	EXISTING CONTROLLER AND CABINET
	EXISTING MASTER CONTROLLER AND CABINET
	SIGNAL INVENTORY NUMBER
	NEW METAL POLE W/MAST ARM
	EXISTING WOOD POLE
	NEW METAL POLE
	SIGNAL POLE
	EXISTING METAL POLE
	NEW OVERSIZED JUNCTION BOX
	EXISTING OVERSIZED JUNCTION BOX
	EXISTING CONDUIT
	NEW CONDUIT
	EXISTING COMMUNICATIONS CABLE

TMP FINAL PHASE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

<p>750 N. Greenfield Pkwy., Garner, NC 27529</p>	<p>COMMUNICATIONS CABLE AND CONDUIT ROUTING PLANS</p>							
	<p>DIVISION 2 CRAVEN CO.</p> <p>PLAN DATE: FEBRUARY 2017</p> <p>PREPARED BY: H. T. BERGGREN</p>	<p>REVIEWED BY: I. N. Havelock</p> <p>REVIEWED BY: [Signature]</p>		<p>SEAL</p> <p>SEAL 023919</p> <p>DATE</p>				
<p>SCALE</p> <p>0 50</p> <p>1" = 50'</p>	<table border="1"> <thead> <tr> <th>REVISIONS</th> <th>INIT.</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	REVISIONS	INIT.	DATE				<p>DATE</p> <p>2/15/2017</p>
REVISIONS	INIT.	DATE						



LEGEND

- YAGI ANTENNA (DOUBLE) FOR REPEATER OPERATION
- YAGI ANTENNA (SINGLE)
- OMNI ANTENNA
- EXISTING CONTROLLER AND CABINET
- EXISTING MASTER CONTROLLER AND CABINET
- SIGNAL INVENTORY NUMBER
- NEW METAL POLE W/MAST ARM
- EXISTING WOOD POLE
- NEW METAL POLE
- SIGNAL POLE
- EXISTING METAL POLE
- NEW OVERSIZED JUNCTION BOX
- EXISTING OVERSIZED JUNCTION BOX
- EXISTING CONDUIT
- NEW CONDUIT
- EXISTING COMMUNICATIONS CABLE

GENERAL NOTES:

1. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER, MARY MOORE, PE AT (252)439-2800 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL COMMUNICATION CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
2. REMOVE EXISTING RADIO SYSTEM (RADIO, ANTENNA, ANTENNA MOUNTING HARDWARE, AND COAXIAL CABLE). RETURN RADIO, ANTENNA, AND ANTENNA MOUNTING HARDWARE TO THE DEPUTY DIVISION TRAFFIC ENGINEER.


DO NOT BOND TRACER WIRE TO EQUIPMENT GROUND BUS

TMP FINAL PHASE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

<p>750 N. Greenfield Pkwy., Garner, NC 27529</p>	<p>COMMUNICATIONS CABLE AND CONDUIT ROUTING PLANS</p>		
	<p>DIVISION 2 CRAVEN CO.</p> <p>PLAN DATE: FEBRUARY 2017</p> <p>PREPARED BY: H. T. BERGGREN</p>	<p>DocuSigned by: HAVELOCK</p> <p>REVIEWED BY: I. M. LIVERY</p> <p>REVIEWED BY: [Signature]</p>	


SCALE: 1" = 50'



GENERAL NOTES:
 1. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER, MARY MOORE, PE AT (252)439-2800 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL COMMUNICATION CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.

BOND TRACER WIRE TO EQUIPMENT GROUND BUS

<p>TMP FINAL PHASE</p> <p>Prepared in the Offices of:</p> <p>750 N. Greenfield Pkwy., Garner, NC 27529</p>		<p>DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED</p>	
<p>COMMUNICATIONS CABLE AND CONDUIT ROUTING PLANS</p> <p>DIVISION 2 CRAVEN CO.</p> <p>PLAN DATE: FEBRUARY 2017</p> <p>PREPARED BY: H. T. BERGGREN</p>		<p>SEAL</p> <p>PROFESSIONAL ENGINEER</p> <p>SEAL 023919</p> <p>REG. STATE OF NORTH CAROLINA</p> <p>Gregory A. Fuller</p> <p>2/15/2017</p>	
<p>SCALE 0 50</p> <p>1" = 50'</p>		<p>REVISIONS</p> <p>INIT. DATE</p>	



GENERAL NOTES:

1. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER, MARY MOORE, PE AT (252)439-2800 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL COMMUNICATION CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
2. REMOVE EXISTING RADIO SYSTEM (RADIO, ANTENNA, ANTENNA MOUNTING HARDWARE, AND COAXIAL CABLE). RETURN RADIO, ANTENNA, AND ANTENNA MOUNTING HARDWARE TO THE DEPUTY DIVISION TRAFFIC ENGINEER.

LEGEND

	YAGI ANTENNA (DOUBLE) FOR REPEATER OPERATION
	YAGI ANTENNA (SINGLE)
	OMNI ANTENNA
	EXISTING CONTROLLER AND CABINET
	EXISTING MASTER CONTROLLER AND CABINET
	SIGNAL INVENTORY NUMBER
	NEW METAL POLE W/MAST ARM
	EXISTING WOOD POLE
	NEW METAL POLE
	SIGNAL POLE
	EXISTING METAL POLE
	NEW OVERSIZED JUNCTION BOX
	EXISTING OVERSIZED JUNCTION BOX
	EXISTING CONDUIT
	NEW CONDUIT
	EXISTING COMMUNICATIONS CABLE

TMP FINAL PHASE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

	<p>COMMUNICATIONS CABLE AND CONDUIT ROUTING PLANS</p>		
	DIVISION 2 CRAVEN CO. <i>DocuSigned by: HAVELock</i> PLAN DATE: FEBRUARY 2017 REVIEWED BY: <i>I. M. Iverson</i> PREPARED BY: H. T. BERGGREN REVIEWED BY: <i>Gregory A. Fuller</i>	REVISIONS _____ _____	
750 N. Greenfield Plaza, Garner, NC 27529		SCALE 0 50 1" = 50'	DATE _____

**EXISTING UNDERGROUND SPlice ENCLOSURE
(IN EXISTING JUNCTION BOX #1)**

US 70
AT WALMART ENTRANCE
SIG. INV. # 02-0873

Notes:
Unused fibers left coiled and stored in splice tray.
Unused Buffer Tubes left coiled and stored in splice tray.

- 1) NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER, MARY MOORE, PE, AT (252)439-2800, FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL COMMUNICATION CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
- 2) MODIFY INTERCONNECT CENTER (RECONNECT EXISTING\INSTALL NEW FIBER OPTIC JUMPERS BETWEEN EXISTING PATCH PANEL AND EXISTING FIBER OPTIC TRANCEIVER FOR FIBERS TO 02-0672).
- 3) TRANSCIEVER TERMINATION CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING\ENSURING PROPER TERMINATIONS.
- 4) INCLUDE ON THE COVER OF EACH SPlice TRAY THE FOLLOWING:
REFERENCE SECTION 1731 "FIBER OPTIC SPlice ENCLOSURE"


1) SPlice LOCATION
2) DATE
3) COMPANY NAME
4) NAME OF INDIVIDUAL PERFORMING THE SPlicing

PRIOR TO INSTALLING THE COVER ON THE SPlice TRAY TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPlice TRAY AND INFORMATION SHOWN ABOVE (1-4) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS.


COLOR CODE
TIA/EIA 598-A
(1) BLUE
(2) ORANGE
(3) GREEN
(4) BROWN
(5) SLATE
(6) WHITE

EXISTING CABINET 02-0873

MODIFY INTERCONNECT CENTER



NOTE:
REMOVE EXISTING RADIO SYSTEM (RADIO, ANTENNA, ANTENNA MOUNTING HARDWARE, AND COAXIAL CABLE). RETURN RADIO, ANTENNA, AND ANTENNA MOUNTING HARDWARE TO THE DEPUTY DIVISION TRAFFIC ENGINEER.



TMP FINAL PHASE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


<p>750 N. Greenfield Plaza, Garner, NC 27529</p>	<p>SPlice DETAILS</p>					
	<p>DIVISION 2 CRAVEN CO.</p> <p>PLAN DATE: FEBRUARY 2017 REVIEWED BY: I. N. Lively</p> <p>PREPARED BY: H. T. BERGGREN REVIEWED BY: [Signature]</p>	<p>SCALE: 0 N/A</p>		<p>REVISIONS</p> <table border="1"> <tr> <th>INIT.</th> <th>DATE</th> </tr> <tr> <td> </td> <td> </td> </tr> </table>	INIT.	DATE
INIT.	DATE					

**NEW UNDERGROUND SPLICE ENCLOSURE
(IN EXISTING JUNCTION BOX #2)**

ALONG US 70
SOUTH OF
SIG. INV. # 02-0672

Notes:
Unused fibers left coiled and stored in splice tray.
Unused Buffer Tubes left coiled and stored in splice tray.

COLOR CODE TIA/EIA 598-A	
(1) BLUE	(7) RED
(2) ORANGE	(8) BLACK
(3) GREEN	(9) YELLOW
(4) BROWN	(10) VIOLET
(5) SLATE	(11) ROSE
(6) WHITE	(12) AQUA





NEW UNDERGROUND SPLICE ENCLOSURE

- 1) NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER, MARY MOORE, PE, AT (252)439-2800, FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL COMMUNICATION CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
- 2) INCLUDE ON THE COVER OF EACH SPLICE TRAY THE FOLLOWING: REFERENCE SECTION 1731 "FIBER OPTIC SPLICE ENCLOSURE"
 - 1) SPLICE LOCATION
 - 2) DATE
 - 3) COMPANY NAME
 - 4) NAME OF INDIVIDUAL PERFORMING THE SPLICING

PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (1-4) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS.

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

 Prepared in the Offices of: 750 N. Greenfield Plaza, Garner, NC 27529	SPLICE DETAILS		 DocuSigned by: Gregory A. Fuller 7032CA0AEE87AF... DATE: 2/15/2017
	DIVISION 2 CRAVEN CO., <small>DocuSigned by: HAVELOCK</small> PLAN DATE: FEBRUARY 2017 REVIEWED BY: <i>L. M. Lively</i> PREPARED BY: H. T. BERGGREN REVIEWED BY: <small>08P0804CB05443</small>	REVISIONS _____ _____ _____	
SCALE: 0 N/A NONE			


NEW UNDERGROUND SPLICE ENCLOSURE

US 70
AT SLOCUM RD
SIG. INV. # 02-0672

COLOR CODE TIA/EIA 598-A		LEGEND
(1) BLUE	(7) RED	
(2) ORANGE	(8) BLACK	
(3) GREEN	(9) YELLOW	
(4) BROWN	(10) VIOLET	
(5) SLATE	(11) ROSE	
(6) WHITE	(12) AQUA	

X = NEW FUSION SPLICE INDIVIDUAL FIBER
C = CAP, COIL, AND SEAL

Notes:
Unused fibers left coiled and stored in splice tray.
Unused Buffer Tubes left coiled and stored in splice tray.



- 1) NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER, MARY MOORE, PE, AT (252)439-2800, FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL COMMUNICATION CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
- 2) TRANSCEIVER TERMINATION CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING\ENSURING PROPER TERMINATIONS.
- 3) INCLUDE ON THE COVER OF EACH SPLICE TRAY THE FOLLOWING: REFERENCE SECTION 1731 "FIBER OPTIC SPLICE ENCLOSURE"
 - 1) SPLICE LOCATION
 - 2) DATE
 - 3) COMPANY NAME
 - 4) NAME OF INDIVIDUAL PERFORMING THE SPLICING

PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (1-4) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS.

TMP FINAL PHASE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


<p>750 N. Greenfield Pkwy., Garner, NC 27529</p>	<p>SPLICE DETAILS</p>		
	<p>DIVISION 2 CRAVEN CO.</p> <p>PLAN DATE: FEBRUARY 2017</p> <p>PREPARED BY: H.T. BERGGREN</p>	<p>DocuSigned by: HAVELOCK</p> <p>REVIEWED BY: N. Avery</p> <p>REVIEWED BY: 9F5094CBED3443</p>	
<p>SCALE</p> <p>N/A</p>	<p>REVISIONS</p>	<p>INIT.</p>	<p>DATE</p>

NEW UNDERGROUND SPLICE ENCLOSURE

US 70
AT HICKMAN HILL
EAST BOUND U-TURN
SIG. INV. # 02-0911



COLOR CODE TIA/EIA 598-A		LEGEND	
(1) BLUE	(7) RED	X = NEW FUSION SPLICE INDIVIDUAL FIBER	
(2) ORANGE	(8) BLACK	C = CAP, COIL, AND SEAL	
(3) GREEN	(9) YELLOW		
(4) BROWN	(10) VIOLET		
(5) SLATE	(11) ROSE		
(6) WHITE	(12) AQUA		

Notes:
Unused fibers left coiled and stored in splice tray.
Unused Buffer Tubes left coiled and stored in splice tray.



- 1) NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER, MARY MOORE, PE, AT (252)439-2800, FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL COMMUNICATION CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
- 2) TRANSCEIVER TERMINATION CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING \ENSURING PROPER TERMINATIONS.
- 3) INCLUDE ON THE COVER OF EACH SPLICE TRAY THE FOLLOWING: REFERENCE SECTION 1731 "FIBER OPTIC SPLICE ENCLOSURE"
 - 1) SPLICE LOCATION
 - 2) DATE
 - 3) COMPANY NAME
 - 4) NAME OF INDIVIDUAL PERFORMING THE SPLICING

PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (1-4) AND SUBMIT PHOTOGRAPH ALONG WITH OTRD TEST RESULTS.


 Prepared in the Offices of: 750 N. Greenfield Pkwy., Garner, NC 27529	SPLICE DETAILS		 SEAL NORTH CAROLINA PROFESSIONAL ENGINEER GREGORY A. FULLER
	DIVISION 2 CRAVEN CO. DocuSigned by: HAVELOCK PLAN DATE: FEBRUARY 2017 REVIEWED BY: N. Avery PREPARED BY: H.T. BERGGREN REVIEWED BY: 9F5094CBED3443	REVISIONS INIT. DATE _____ _____	
SCALE 0 N/A	DocuSigned by: Gregory A. Fuller 2/15/2017 DATE		7032CAGAE874FF

NEW UNDERGROUND SPLICE ENCLOSURE

US 70
AT HICKMAN HILL LOOP RD/
PINE GROVE RD
SIG. INV. # 02-0563

COLOR CODE TIA/EIA 598-A		LEGEND	
(1) BLUE	(7) RED	X = NEW FUSION SPLICE INDIVIDUAL FIBER	
(2) ORANGE	(8) BLACK	C = CAP, COIL, AND SEAL	
(3) GREEN	(9) YELLOW		
(4) BROWN	(10) VIOLET		
(5) SLATE	(11) ROSE		
(6) WHITE	(12) AQUA		

Notes:
Unused fibers left coiled and stored in splice tray.
Unused Buffer Tubes left coiled and stored in splice tray.



NEW UNDERGROUND SPLICE ENCLOSURE

- 1) NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER, MARY MOORE, PE, AT (252)439-2800, FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE NCDOT DEPUTY DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL COMMUNICATION CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
- 2) TRANSCEIVER TERMINATION CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING\ENSURING PROPER TERMINATIONS.
- 3) INCLUDE ON THE COVER OF EACH SPLICE TRAY THE FOLLOWING: REFERENCE SECTION 1731 "FIBER OPTIC SPLICE ENCLOSURE"
 - 1) SPLICE LOCATION
 - 2) DATE
 - 3) COMPANY NAME
 - 4) NAME OF INDIVIDUAL PERFORMING THE SPLICING

PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (1-4) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS.

TMP FINAL PHASE

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

<p>750 N. Greenfield Pkwy., Garner, NC 27529</p>	<p>SPLICE DETAILS</p> <p>DIVISION 2 CRAVEN CO.</p>		
	<p>PLAN DATE: FEBRUARY 2017</p> <p>PREPARED BY: H.T. BERGGREN</p>	<p>REVIEWED BY: <i>N. Avery</i></p> <p>REVIEWED BY: 99F5094CBED0443</p>	
<p>SCALE: 0 N/A</p>	<p>REVISIONS</p>	<p>INIT. DATE</p>	<p>DATE: 2/15/2017</p>