

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

| | |
|---|------------------------------------|
| Kimley»Horn <small>©2017</small> | |
| <small>421 FAYETTEVILLE STREET, SUITE 600 RALEIGH, NC 27601</small> | |
| <small>RIGHT-OF-WAY REV.</small> | <small>CONST. REV.</small> |
| <small>PROJECT REFERENCE NO. B-5345</small> | <small>SHEET NO. EC-3A</small> |
| <small>ROADWAY DESIGN ENGINEER</small> | <small>HYDRAULICS ENGINEER</small> |

SOIL STABILIZATION TIMEFRAMES

| <i>SITE DESCRIPTION</i> | <i>STABILIZATION TIME</i> | <i>TIMEFRAME EXCEPTIONS</i> |
|--|---------------------------|--|
| PERIMETER DIKES, SWALES, DITCHES AND SLOPES | 7 DAYS | NONE |
| HIGH QUALITY WATER (HQW) ZONES | 7 DAYS | NONE |
| SLOPES STEEPER THAN 3:1 | 7 DAYS | IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED. |
| SLOPES 3:1 OR FLATTER | 14 DAYS | 7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH. |
| ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1 | 14 DAYS | NONE, EXCEPT FOR PERIMETERS AND HQW ZONES. |

K:\RAL_Roadway\01036275 - B-5345\Erosion Control\B5345_ero_ast\EC02-RF1.dgn

2/20/2017