

PROJECT NO.	SHEET NO.	TOTAL NO.
2018CPT.04.07.10511	4	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	2" MILLING SY	0" TO 4" MILLING SY	INTER-MEDIATE COURSE, 119.0D TONS	SURFACE COURSE, S9.5C TONS	ASPHALT CONC SURFACE COURSE, TYPE S9.5D TON	ASPHALT BINDER FOR PLANT MIX TONS	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX TONS	INDUCTIVE LOOP LF	
2018CPT.04.07.10511	Johnston	1	US70 CLAYTON BYPASS WESTBOUND	SR 2566 TO WAKE COUNTY LINE	1,3	2	MD	NO	NO	9.6	24	135,168	1,000	912		15,244	41	869		
		2	US70 CLAYTON BYPASS EASTBOUND	WAKE COUNTY LINE TO SR 2566	1	2	MD	NO	NO	9.6	24	149,115				16,806		958		
		3	WB EXIT 326A LOOP	US 70 BYPASS TO US 70 BUSS	2	2		NO	NO	0.25	16	2,347				266		16		
		4	WB ENTRANCE RAMP	US 70 BUSS TO US 70 BYPASS	2	2		NO	NO	0.45	35	11,196				1,259		74		
		5	WB RANCH RD EXIT RAMP	US 70 BYPASS TO SR 1560	2	2		NO	NO	0.28	16	2,628				297		18		
		6	WB RANCH RD ENTRANCE RAMP	SR 1560 TO US 70 BYPASS	2	2		NO	NO	0.49	16	4,600				521		31		
		7	WB NC 42 EXIT RAMP	US 70 BYPASS TO NC 42	2	2		NO	NO	0.49	16	4,783				541		32		400
		8	WB ENTRANCE RAMP NC 42	NC 42 TO US 70 BYPASS	2	2		NO	NO	0.45	16	4,224				478		28		
		9	EB NC 42 EXIT RAMP	US 70 BYPASS TO NC 42	2	2		NO	NO	0.29	16	3,028				376		22		400
		10	EB ENTRANCE RAMP US 70 BYPASS	NC 42 TO US 70 BYPASS	2	2		NO	NO	0.48	16	4,506				510		30		
		11	EB RANCH RD EXIT RAMP	US 70 BYPASS TO SR 1560	2	2		NO	NO	0.26	16	2,929				331		20		104
		12	EB RANCH RD ENTRANCE RAMP	SR 1560 TO US 70 BYPASS	2	2		NO	NO	0.5	16	4,693				531		31		
		13	EB US 70 BUSS EXIST RAMP	70 BYPASS TO 70 BUSS TO US 70	2	2		NO	NO	0.7	16	5,989				889		52		600
		14	EB US BUSS TO US 70 LOOP	US 70 BUSS TO US 70 ENTRANCE	2	2		NO	NO	0.53	15	4,664				528		31		
TOTAL FOR PROJ NO. 2018CPT.04.07.10511										24.37		339,870	1,000	912	6,527	32,050	426	1,827	1,504	
GRAND TOTAL										24.37		339,870	1,000	912	6,527	32,050	426	1,827	1,504	