

PROJECT NO.	SHEET NO.	TOTAL NO.
2018CPT.14.03.10561.1, 2018CPT.14.03.20561.1	10	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	SHOULDER RECONSTRUCTION SMI	0" TO 1.5" MILLING SY	INTERMEDIATE COURSE, I19.0B (WEDGING) TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TONS	LEVELING COURSE, SF9.5A TON	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	ASPHALT FOR PAVEMENT INTERLAYER TON	PAVEMENT INTERLAYER 50 MIL FABRIC SY	PAVEMENT INTERLAYER 100 MIL FABRIC SY	INDUCTIVE LOOP SAWCUT LF	LEAD-IN CABLE, 14-2 LF
2018CPT.14.03.10561.1	Macon	1	US 64	FROM BRIDGE #9 TO BEG OF DIV HWY	1	2	2WU	NO	NO	0.18	24	0.36	423		274			16						
TOTAL FOR MAP NO. 1										0.18		0.36	423		274			16						
2018CPT.14.03.10561.1	Macon	2	US 64 WEST	FROM .03 MI EAST OF SR 1448 TO WEST END OF BRIDGE #96	2	2	MD	YES	NO	5.35	32	10.54	1,068		19,556			1,173		300	39,233.00	39,233.00	265	120
TOTAL FOR MAP NO. 2										5.35		10.54	1,068		19,556			1,173		300	39,233.00	39,233.00	265	120
2018CPT.14.03.10561.1	Macon	3	US 64 EAST	.02 MI EAST OF SR 1477 TO WEST END OF BRIDGE #97	2	2	MD	YES	NO	5.37	32	10.74	1,068		19,629			1,178		600	39,233.00	39,233.00	263	120
TOTAL FOR MAP NO. 3										5.37		10.74	1,068		19,629			1,178		600	39,233.00	39,233.00	263	120
2018CPT.14.03.10561.1	Macon	4	RAMP TO US 64 WEST	FROM SR 1442 TO US 64 WBL	3	1	2WU	NO	NO	0.4	20	0.80			436			26						
TOTAL FOR MAP NO. 4										0.4		0.80			436			26						
2018CPT.14.03.10561.1	Macon	5	EXIT & ENTRANCE TO SR-1442	FROM SR-1442 TO US 64	4	2	2WU	NO	NO	0.18	40	0.36			392			23						
TOTAL FOR MAP NO. 5										0.18		0.36			392			23						
2018CPT.14.03.10561.1	Macon	6	EXIT RAMP WBL TO SR-1442	FROM US 64 WBL TO SR 1442	3	1	2WU	NO	NO	0.26	18	0.52			251			15						
TOTAL FOR MAP NO. 6										0.26		0.52			251			15						
2018CPT.14.03.10561.1	Macon	7	EXIT RAMP WBL TO SR-1463	FROM US 64 WBL TO SR 1463	3	1	2WU	NO	NO	0.13	31	0.26			215			13						
TOTAL FOR MAP NO. 7										0.13		0.26			215			13						
TOTAL FOR PROJ NO. 2018CPT.14.03.10561.1										11.87		23.58	2,559		40,753			2,444		900	78,466.00	78,466.00	528	240
2018CPT.14.03.20561.1	Macon	8	SR 1337 (RIVERBEND ROAD)	FROM 0.09MI NORTH OF NC 28 TO 0.09MI EAST OF NC 28	5	2	2WU	NO	NO	2.99	18	5.98				2,041	200	149						
TOTAL FOR MAP NO. 8										2.99		5.98			2,041	200	149							
2018CPT.14.03.20561.1	Macon	9	SR 1310 (WAYAH ROAD)	FROM USFS RD 711 TO SR 1401(JUNALUSKA RD)	6	2	2WU	NO	NO	7.69	19	15.38		100		7,072		479	892					
TOTAL FOR MAP NO. 9										7.69		15.38	100		7,072		479	892						
TOTAL FOR PROJ NO. 2018CPT.14.03.20561.1										10.68		21.36	100		9,113	200	628	892						
GRAND TOTAL										22.55		44.94	2,559	100	40,753	9,113	200	3,072	892	900	78,466.00	78,466.00	528	240