DocuSign Envelope ID: AE99E563-29BD-48E7-992E-C1053ED36E24

| TIP NO. | SHEET NO. |
|---|---|
| U-3621A | SIGN-2 |

APPROVED: William J. Hamilton (DocuSigned by: A056BD704E4E4E4...)

DATE: 3/13/2017

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 32396 ENGINEER WILLIAM J. HAMILTON

**DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED**

(401) QUANTITY REQ'D 8

36" X 36"
R1-1

ONE "U" POST PER SIGN

(402) QUANTITY REQ'D 1

30" X 30"
W14-1

ONE "U" POST PER SIGN

(403) QUANTITY REQ'D 6

30" X 36"
R2-1

ONE "U" POST PER SIGN

(404) QUANTITY REQ'D 7

36" X 12"
R6-1 (R)

ONE "U" POST PER SIGN
MOUNT ABOVE SIGN 401.
IN 7 INSTALLATIONS

(405) QUANTITY REQ'D 3

54" X 18"
R6-1 (L)

TWO "U" POSTS PER SIGN

(406) QUANTITY REQ'D 1



36" X 36"
W12-1

ONE "U" POST PER SIGN

(407) QUANTITY REQ'D 2

24" X 30"
R4-7

ONE "U" POST PER SIGN

(408) QUANTITY REQ'D 2

18" x 18"
OM4-3

MOUNT BELOW SIGN 407.
IN 2 INSTALLATIONS

(409) QUANTITY REQ'D 1

36" X 36"
R5-1

ONE "U" POST PER SIGN

(410) QUANTITY REQ'D 3

54" X 18"
R6-1 (R)

TWO "U" POSTS PER SIGN

Prepared in the offices of:
RAMEY KEMP & ASSOCIATES, INC.
Transportation Engineers
5808 Farrington Place, Suite 100
Raleigh, North Carolina 27609
919-872-5115 Tel. 919-878-5410 Fax.
www.rameykemp.com

# TYPE "E" SIGNS